



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Janet T. Mills  
GOVERNOR

Bruce A. Van Note  
COMMISSIONER

June 9, 2020  
Subject: Half Mile Pond Brook Bridge  
Replacement  
State WIN: 021870.00  
Location: **Amherst**  
**Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

**ADD** the attached SPECIAL PROVISION – SECTION 105 – GENERAL SCOPE OF WORK – (Traffic Control and Management), 1 page, dated May 12, 2020.

Consider these changes and information prior to submitting your bid on **June 17, 2020**.

Sincerely,

A handwritten signature in black ink that reads "George M. A. Macdougall".

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

**SPECIAL PROVISION**  
**SECTION 105**  
**GENERAL SCOPE OF WORK**  
**(Traffic Control and Management)**

Section 105, General Scope of Work, of the Standard Specifications is amended as follows:

105.3 Traffic Control and Management:

Add the following to the end of the subsection:

The Contractor may choose to construct the Special Detour and install the precast box culvert during the 2020 in-water work window or construct the Special Detour in 2020 and install the precast box culvert during the 2021 in-water work window, in which case, the Special Detour shall not be activated until the Contractor is prepared and ready to begin precast box culvert installation.

Prior to Activating the Special Detour:

At least one lane of alternating traffic shall be maintained on Route 9 through the project area at all times, using temporary traffic signals or flaggers. Flaggers shall only be used for lane closures during daytime hours. The minimum roadway width shall be 20 feet. Route 9 at this location is 40 feet wide (two 12-ft lanes with 8-ft shoulders).

Upon Activation of the Special Detour:

At least one lane of alternating traffic shall be maintained on Route 9 through the project area at all times, using temporary traffic signals or flaggers. The minimum roadway width shall be 26 feet as required by the Contract.