



Paul R. LePage
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

David Bernhardt
COMMISSIONER

April 2, 2018
Subject: Parking Lot Paving
State WIN: 021942.07
Location: **Portland**
Amendment No. 2

Dear Sir/Ms.:

Please make the following changes to the Bid documents:

In the Bid Book:

REMOVE pages 17 – 19, Proposal Schedule of Items, 3 pages, dated 2/28/2018, and **REPLACE** with the attached, revised Proposal Schedule of Items, 3 pages, dated March 30/2018

In the Plan Set:

On Sheet Number 3 of 8, Quantity Sheet, **CHANGE** the quantity for Pay Item 304.09 - Aggregate Base Course – Crushed - Type A, to read **340 CY**. Make this change in pen and ink.

On Sheet Number 3 of 8, Quantity Sheet, **CHANGE** the quantity for Pay Item 304.104 - Aggregate Subbase Course – Gravel - Type D, to read **670 CY**. Make this change in pen and ink.

The following questions have been received:

Question: How will the 1.5-inch overlay dovetail with the edge of porous pavement?

Response: Provide a butt joint with dimensions 360 feet long by 1 foot wide.

Question: At the pre-bid on 3/21/2018 it was stated that the addendum with answers to the questions asked at meeting would be out by then end of the day on 3/22/2018 to allow Contractors time to get the information into the hands of the electrical subs. I have not seen the addendum yet; does this mean the bid is being delayed to allow enough time to get the addendum out to the subs and get pricing back?

Response: Yes. The new bid date is April 4, 2018.

Question: Contract drawing G02 Environmental notes state: "Ash may be encountered on this project.... this material, if encountered, must be reused on-site as fill material. If the material cannot be reused on site, the contractor is responsible for obtaining all approvals or permits and any required analytical results for proper disposal at a MDEP facility...". Since there are no areas of fill on this project any testing will fall on the contractor. Who will be responsible for the soil disposal fee at the licensed MDEP facility?



PRINTED ON RECYCLED PAPER

Response: The MaineDOT will be responsible for the soil disposal fee for any ash materials that must be disposed at a MDEP facility. The MaineDOT's Resident will identify and notify the Contractor of suitable locations within the Terminal for on-site disposals, if possible. The length of haul for "on-site disposal" would be the distance between the area of excavation to Cassidy Point Road on Commercial Street. This distance shall be considered incidental to the Common Excavation pay item.

Question: At the pre-bid meeting it was stated that the detector loops in the pavement at the NW gate to Commercial Street were to remain in place. It appears that the limit of full depth construction, based on plan sheet C01, goes beyond the gate towards Commercial street which would necessitate removal of the loops. Do the loops need to be replaced and if they need to be replaced, is that incidental to the contract?

Response: Yes, the loops need to be replaced. Their replacement shall be incidental to the contract.

Question: Please check the quantities for item 304.09 and 304.104. It appears that these may be reversed.

Response: Agreed: the quantities were reversed. The correct quantities are as follows:
Item 304.09, Aggregate Base Course – Crushed – Type A: 340 cy
Item 304.104, Aggregate Subbase Course – Gravel – Type D: 670 cy

Question: New pavement detail, plan sheet 5 of 8, shows Type D Gravel being twice as thick as Type A. Bid items show twice as much Type A as Type D, and the Type D is plan quantity. Why? Am I missing something?

Response: See response above. The quantities were accidentally transposed.

Question: Item 304.09 and Item 304.14, it seems the quantities are backwards considering the 304.14 item is 14" and the 304.09 item is 7". Are quantities on the bid sheet correct?


Response: See response above. The quantities were accidentally transposed.

Question: Bid Amendment 1 added pay item 202.203 Pavement Butt Joints to sheet number 3 of 8 - quantity sheet of the plans. Will this item be added to the proposal schedule of items?

Response: See above changes.

Consider these changes and information prior to submitting your bid on **April 4, 2018**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021942.07

Project(s): 021942.07

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.01 REMOVING STRUCTURES AND OBSTRUCTIONS - UTILITY POLE	LUMP SUM		LUMP SUM		
0020	202.110 REMOVING, STORING, AND RESETTING STRUCTURES AND OBSTRUCTIONS - FIRE PULL BOX AND KEYCARD READER	3.000 EA				
0030	202.203 PAVEMENT BUTT JOINTS	40.000 SY				
0040	203.20 COMMON EXCAVATION	1,420.000 CY				
0050	304.09 AGGREGATE BASE COURSE - CRUSHED	340.000 CY				
0060	304.104 AGGREGATE SUBBASE COURSE (PLAN QUANTITY)	670.000 CY				
0070	403.2071 19 MM POLYMER MODIFIED HOT MIX ASPHALT	580.000 T				
0080	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	1,370.000 T				
0090	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	140.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	1,020.000 G				
0110	419.30 SAW CUTTING BITUMINOUS PAVEMENT	650.000 LF				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 021942.07

Project(s): 021942.07

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	504.7011 INSTALL UTILITY POLE - 20'	1.000 L S	_____	 _____	_____	 _____
0130	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	18.000 EA	_____	 _____	_____	 _____
0140	607.1701 TEMPORARY CHAIN LINK FENCE - 6' MOVEABLE	115.000 LF	_____	 _____	_____	 _____
0150	607.232 CHAIN LINK FENCE GATE, 3 FOOT	1.000 EA	_____	 _____	_____	 _____
0160	607.4911 MOTORIZED SLIDE GATE - 24 FT.	1.000 EA	_____	 _____	_____	 _____
0170	607.4927 REMOVE MOTORIZED SLIDE GATE - 20' CHAIN LINK	1.000 EA	_____	 _____	_____	 _____
0180	626.332 30 INCH DIAMATER GREATER THAN 8 FEET LONG & 36 INCH DIAMETER, 42 INCH DIAMETER FOUNDATION	2.000 CY	_____	 _____	_____	 _____
0190	626.74 PANELBOARD	LUMP SUM		 LUMP SUM	_____	 _____
0200	626.742 FIRE ALARM PULL STATIONS	LUMP SUM		 LUMP SUM	_____	 _____
0210	626.743 CARD READER	1.000 L S	_____	 _____	_____	 _____
0220	626.744 FIBER OPTIC CABLE	1.000 L S	_____	 _____	_____	 _____
0230	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____

3/30/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 021942.07

Project(s): 021942.07

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0250	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____