



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

December 13, 2021
Subject: Multi-Use Path
State WIN: 022138.00
Location: **South Portland**
Amendment No. 2

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE from Amendment No. 1, Proposal Schedule of Items, 4 pages, dated 12/1/2021, and **REPLACE** with the attached, revised Proposal Schedule of Items, 4 pages, dated 12/13/2021.

ADD the attached SPECIAL PROVISION - SECTION 105 – GENERAL SCOPE OF WORK – (Reserve Limits), 1 page, dated December 13, 2021.

ADD the attached SPECIAL PROVISION - SECTION 803 - UTILITY & DRAINAGE TEST PITS, 1 page, dated December 10, 2021.

The following questions have been received:

Question: On Note #3 and #13 (signal and equipment notes in plans), it states that "the contractor is responsible for exact location of existing utilities", as well as "the contractor will be required to pre-excavate (pothole) over utility crossings to confirm utility elevations for under pavement conduit installations". Can a test pit item be added to the schedule of items to cover these requirements? The notes leave a lot of room for interpretation on quantity of test pits needed, if it is considered incidental.

Response: The item 803.01 TEST PIT will be added to the contract. The Special Provision and revised Schedule of Items are attached.

Question: On Note #8 in the signal notes, it states that the contractor is responsible for "opening permits". Can you clarify what opening permits are needed for this project?

Response: Any necessary permits can be obtained free of charge from the City of South Portland.

Consider these changes and information prior to submitting your bid on **December 15, 2021**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022138.00

Project(s): 022138.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	480.000 CY	_____	 _____	_____	 _____
0020	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	360.000 CY	_____	 _____	_____	 _____
0030	403.210 HOT MIX ASPHALT 9.5 MM	106.000 T	_____	 _____	_____	 _____
0040	604.161 ALTERING CATCH BASIN	3.000 EA	_____	 _____	_____	 _____
0050	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	5.000 EA	_____	 _____	_____	 _____
0060	608.26 CURB RAMP DETECTABLE WARNING FIELD	166.000 SF	_____	 _____	_____	 _____
0070	609.11 VERTICAL CURB TYPE 1	260.000 LF	_____	 _____	_____	 _____
0080	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	35.000 LF	_____	 _____	_____	 _____
0090	609.21 CONCRETE SLIPFORM CURB	68.000 LF	_____	 _____	_____	 _____
0100	609.219 CONCRETE SLIPFORM CURB - TERMINAL END	58.000 LF	_____	 _____	_____	 _____
0110	609.221 TERMINAL CURB TYPE 1	65.000 LF	_____	 _____	_____	 _____
0120	609.38 RESET CURB TYPE 1	120.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022138.00

Project(s): 022138.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	615.07 LOAM	34.000 CY	_____	 _____	_____	 _____
0140	618.13 SEEDING METHOD NUMBER 1	3.000 UN	_____	 _____	_____	 _____
0150	626.11 PRECAST CONCRETE JUNCTION BOX	10.000 EA	_____	 _____	_____	 _____
0160	626.22 NON-METALLIC CONDUIT	200.000 LF	_____	 _____	_____	 _____
0170	626.251 NON-METALLIC UNDER PAVEMENT CONDUIT (SCHEDULE 80 OR GREATER RATING)	110.000 LF	_____	 _____	_____	 _____
0180	626.411 18 INCH DIAMETER FOUNDATION	55.000 LF	_____	 _____	_____	 _____
0190	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	2,100.000 SF	_____	 _____	_____	 _____
0200	627.77 REMOVING PAVEMENT MARKINGS	1,450.000 SF	_____	 _____	_____	 _____
0210	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	 _____	_____	 _____
0220	643.71 TRAFFIC SIGNAL MODIFICATION Main Street & Broadway	LUMP SUM	LUMP SUM	 _____	_____	 _____
0230	643.71 TRAFFIC SIGNAL MODIFICATION Main Street & Rumery Street	LUMP SUM	LUMP SUM	 _____	_____	 _____
0240	643.83 VIDEO DETECTION SYSTEM	LUMP SUM	LUMP SUM	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022138.00

Project(s): 022138.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	643.90 INTERCONNECT WIRE BETWEEN Controller Cabinet & GWI splice point	LUMP SUM		LUMP SUM		
0260	643.92 PEDESTAL POLE	10.000 EA				
0270	643.931 REMOVE AND RESET WOODEN STRAIN POLE Remove and Reset Wooden Strain Pole	1.000 EA				
0280	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	3.000 EA				
0290	645.108 DEMOUNT POLE	3.000 EA				
0300	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	3.000 EA				
0310	645.118 REINSTALL POLE	3.000 EA				
0320	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	70.000 SF				
0330	652.33 DRUM	50.000 EA				
0340	652.34 CONE	100.000 EA				
0350	652.35 CONSTRUCTION SIGNS	250.000 SF				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022138.00

Project(s): 022138.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	180.000 CD	_____	 _____	_____	 _____
0370	652.38 FLAGGER	400.000 HR	_____	 _____	_____	 _____
0380	652.381 TRAFFIC OFFICER	40.000 HR	_____	 _____	_____	 _____
0390	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	 _____	_____	 _____
0400	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
0410	803.01 TEST PITS	4.000 EA	_____	 _____	_____	 _____
0420	832.071 CONTRACTOR ALLOWANCE - (GWI)	LUMP SUM		 LUMP SUM		 3,000.00
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____

SPECIAL PROVISION
SECTION 105
GENERAL SCOPE OF WORK
(Reserve Limits)

It is hereby brought to the Contractor's attention that use of the following area will not become available to the Contractor until on or before May 31, 2022:

- Station 17+10RT to 17+30RT. The Contractor cannot work within an area of 40' right of centerline up to the temporary construction limits. The existing electronic sign is slated to be relocated by others. No work shall take place within these limits until after May 31, 2022 or unless released prior to that date by the Department. The Contractor shall mark out any proposed work behind the roadside curb within station 17+10RT to 17+30RT and must first get approval by the Resident before any work can begin.

SPECIAL PROVISION
SECTION 803
UTILITY & DRAINAGE TEST PITS

Description This work shall consist of excavating and back filling test holes to locate existing utilities or drainage at locations shown on the plans or as directed by the Resident.

Construction Requirements The work shall be done in a manner that provides safe passage of the traveling public at all times. Coordination with the utilities is required prior and during the test pit activities. An authorized representative from the utility shall be present during the test pit activity. Test pits shall be completed in a manner that does not damage any utilities. Any damage to utilities or other roadway features by the test pit operations shall be repaired by the Contractor at no additional cost and shall be to the Resident's satisfaction.

The Contractor shall coordinate with the Resident on locating the utilities once exposed.

Once the location work is complete, the Contractor shall backfill the hole, place gravel and pavement over the test pits in a manner consistent with the existing conditions and in accordance with the standard specifications for backfilling.

Basis of Payment The accepted quantity of Test Pits will be paid for at the contract unit price per each, which shall be full compensation for all labor, materials, tools, equipment, and incidentals necessary to the complete the work. Associated traffic control will not be paid for separately and is considered incidental to the test pit item.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
803.01 Test Pits	Each