



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

July 14, 2025
Subject: Bridge Replacement
WIN: 022382.00
Location: **Cumberland-Yarmouth**
Amendment No. 6

Dear Sir/Ms.:

In the Plan Set:

REMOVE Sheet Number 2 of 121, ESTIMATED QUANTITIES dated 7/10/2025 and **REPLACE** with the attached Sheet Number 2 of 121, ESTIMATED QUANTITIES dated 7/11/2025.

In the contract bid book:

REMOVE Special Provision 524 TEMPORARY STRUCTURAL SUPPORTS (Temporary Support of Earth for Pier Foundation Installation) dated 5/27/2020 (1 page) and **REPLACE** with the attached Special Provision 524 TEMPORARY STRUCTURAL SUPPORTS (Temporary Support of Earth for Pier Foundation Installation) (Temporary Support of Earth Excavation for MSE Wall Installation) dated 7/11/2025 (1 page).

REMOVE pages 16 to 37 titled Proposal Schedule of Items dated 6/30/2025 (12 pages) and **REPLACE** with the attached Proposal Schedule of Items dated 7/14/2025 (12 pages)

The following questions have been received:

Question: According to the MSE Wall plan sheets, the Northeast MSE Wall footing at Abutment No. 2 is at approximate elevation 110. With the existing abutment footing elevation at approximately 127' it is apparent that an earth support system will be required for installation of the MSE Wall at this location. How will the installation and removal of this earth support system be paid?

Response: Payment will be under Item 524.301 Temporary Structural Support – Existing Abutment. Please see revised Plan Sheet 2 and Special Provision Section 524 – Temporary Structural Supports.

Question: The lighting general notes mention junction boxes in several places. The plans do not show any junctions boxes in the lighting system and there are none included in the schedule of items. Will junction boxes be required?

Response: Junction boxes are not required for the lighting system. If junction boxes are a part of the equipment and materials to be provided under Standard Specification Section 634.022, junction boxes would be incidental to item 634.160 (lighting general note 28).

Consider these changes and information prior to submitting your bid on **July 16, 2025**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

SPECIAL PROVISION
SECTION 524
TEMPORARY STRUCTURAL SUPPORTS
(Temporary Support of Earth for Pier Foundation Installation)
(Temporary Support of Earth Excavation for MSE Wall Installation)

The following is added to Standard Specification Section 524:

524.01 Description

This work shall consist of designing, fabricating, erecting, maintaining, and dismantling temporary structural support wall(s) for the purpose of supporting partially excavated Roadway during staged construction. Temporary Structural Support shall include support, bracing, or otherwise stabilizing any structures disturbed or partially removed as part of the Work.

524.03 Design

The temporary structure and approaches shall achieve acceptable minimum factors of safety. Minimum factors of safety for slope stability are 1.3 for approach embankment slopes and 1.5 for embankment slopes that contain or support structures. The minimum factor of safety for sliding and overturning is 1.3.

The design for the Temporary Structural Support shall be submitted to the Resident at least 3 weeks prior to the start of Work.

524.05 Method of Measurement

Temporary Structural Supports for Roadway support during staged construction will be measured as one lump sum satisfactorily designed, installed, maintained, dismantled, and removed for the entire project. Installation and reinstallation of Temporary Structural Supports between construction phases, if required, will not be measured separately, but will be considered incidental to the Temporary Structural Support Pay Item. Any work associated with support, bracing, or otherwise stabilizing any structures disturbed or partially removed as part of the Work or with removal and reinstallation of existing highway appurtenances (e.g. guardrails, sign supports, etc.) to facilitate the erection of Temporary Structural Supports will not be measured for payment, but will be considered incidental to the Temporary Structural Support Pay Item.

524.06 Basis of Payment

Temporary Structural Support for Roadway support will be paid for at the Contract lump sum price, which shall be full compensation for all materials, equipment, labor, and incidentals necessary for the design, installation, maintenance, dismantling, and removal of such supports in accordance with the Standard Specifications and as specified herein.

Payments will be made under:

<u>Pay Item</u>		<u>Pay Unit</u>
524.301	Temporary Structural Support - Pier	Lump Sum
524.301	Temporary Structural Support – Existing Abutment	Lump Sum

ESTIMATED QUANTITIES			
ITEM NO.	DESCRIPTION	QUANTITY	UNIT
201.11	CLEARING	2.10	AC
202.15	REMOVE EXISTING MANHOLE OR CATCH BASIN	2	EA
202.19	REMOVING EXISTING BRIDGE	1	LS
202.202	REMOVING PAVEMENT SURFACE	1,150	SY
202.205	RUMBLE STRIPS - SHOULDER	1,500	LF
202.207	RUMBLE STRIPS, FILL	1,500	LF
203.20	COMMON EXCAVATION	11,300	CY
203.24	COMMON BORROW	41,500	CY
203.25	GRANULAR BORROW	380	CY
203.4338	LIGHTWEIGHT FILL FOAMED GLASS AGGREGATE	1,300	CY
206.082	STRUCTURAL EARTH EXCAVATION-MAJOR STRUCTURES	196	CY
304.10	AGGREGATE SUBBASE COURSE - GRAVEL	11,000	CY
403.2081	HOT MIX ASPHALT - 12.5 MM (POLYMER MODIFIED)	1,430	T
403.209	HOT MIX ASPHALT - 9.5 MM (SIDEWALKS, DRIVES, & INCIDENTALS)	330	T
403.2131	HOT MIX ASPHALT - 12.5 MM (BASE AND INTERMEDIATE COURSE POLYMER MOD.)	4,850	T
409.15	BITUMINOUS TACK COAT - APPLIED	885	T
461.131	TEMPORARY PAVEMENT	600	T
501.239	DYNAMIC LOADING TEST - PROVIDING FOR	3	EA
501.50	STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	1,750	LF
501.501	STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	1,600	LF
501.90	PILE TIPS	35	EA
501.91	PILE SPLICES	14	EA
501.92	PILE DRIVING EQUIPMENT MOBILIZATION	1	LS
502.219	STRUCTURAL CONCRETE, ABUTMENT & RETAINING WALLS (125 CY)	1	LS
502.239	STRUCTURAL CONCRETE PIERS (230 CY)	1	LS
502.26	STRUCTURAL CONCRETE ROAD & SIDEWALK SLABS ON STEEL BRIDGE (540 CY)	1	LS
502.31	STRUCTURAL CONCRETE APPROACH SLABS (40 CY)	1	LS
503.12	REINFORCING STEEL, FABRICATED AND DELIVERED	5,400	LB
503.13	REINFORCING STEEL, PLACING	5,400	LB
503.17	MECHANICAL WELDED SPLICE	626	EA
503.19	LOW-CARBON CHROMIUM REINFORCEMENT - FABRICATED AND DELIVERED	189,600	LB
503.20	LOW-CARBON CHROMIUM REINFORCEMENT - PLACING	189,600	LB
504.702	STRUCTURAL STEEL FABRICATED & DELIVERED, WELDED (791,000 LB)	1	LS
504.71	STRUCTURAL STEEL ERECTION (791,000 LB)	1	LS
505.08	SHEAR CONNECTORS (4431 EA)	1	LS
506.9104	THERMAL SPRAY COATING - SHOP APPLIED	1	LS
507.0833	BARRIER MOUNTED BRIDGE RAIL, BICYCLE (273 LF)	1	LS
507.0848	BARRIER-MOUNTED STEEL BRIDGE RAIL, 2 BAR (546 LF)	1	LS
508.14	HIGH PERFORMANCE WATERPROOFING MEMBRANE (1700 SY)	1	LS
515.21	PROTECTIVE COATING FOR CONCRETE SURFACES (1200 SY)	1	LS
519.60	EXPANSION DEVICE - ASPHALTIC PLUG JOINT	110	LF
523.52	BEARING INSTALLATION	7	EA
523.5401	LAMINATED ELASTOMERIC BEARINGS, FIXED	7	EA
524.301	TEMPORARY STRUCTURAL SUPPORT - PIER	1	LS
524.301	TEMPORARY STRUCTURAL SUPPORT - EXISTING ABUTMENT	1	LS
524.40	PROTECTIVE SHIELD	1	LS
526.301	PORTABLE CONCRETE BARRIER TYPE 1 (2800 LF)	1	LS
526.341	PERMANENT CONCRETE BARRIER, SPECIAL (820 LF)	1	LS
527.33	TRUCK MOUNTED ATTENUATOR	2	EA
527.34	WORK ZONE CRASH CUSHIONS	4	UN
603.169	15" CULVERT PIPE OPTION III	160	LF
603.175	18" RCP CLASS III	192	LF
603.179	18" CULVERT PIPE OPTION III	286	LF
604.092	CATCH BASIN TYPE B1-C	3	EA
604.16	ALTER CATCH BASIN TO MANHOLE	1	EA
604.262	CATCH BASIN TYPE B5-C	14	EA
605.11	12" UNDERDRAIN TYPE C	614	LF
605.13	18" UNDERDRAIN TYPE C	306	LF
606.1301	31" W-BEAM GUARDRAIL, MID-WAY SPLICE - SINGLE FACED	1,275	LF
606.1305	31" W-BEAM GUARDRAIL, MID-WAY SPLICE FLARED TERMINAL	4	EA
606.1306	31" W-BEAM GUARDRAIL, MID-WAY SPLICE TANGENT TERMINAL	2	EA
606.1307	BRIDGE TRANSITION TYPE 1A - ASYMMETRICAL	4	EA
606.23	GUARDRAIL TYPE 3C - SINGLE RAIL	25	LF
606.232	GUARDRAIL TYPE 3C - OVER 15' RADIUS	75	LF
606.265	TERMINAL END - SINGLE RAIL - GALVANIZED	4	EA
606.353	REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	14	EA
607.16	CHAIN LINK FENCE - 4'	850	LF
607.1811	CHAIN LINK FENCE - 3'	180	LF
607.421	SCREENING FENCE	184	LF
608.26	CURB RAMP DETECTABLE WARNING FIELD	150	SF
609.11	VERTICAL CURB TYPE 1	475	LF
609.12	VERTICAL CURB TYPE 1- CIRCULAR	105	LF
609.221	TERMINAL CURB TYPE 1	16	LF
609.222	TERMINAL CURB TYPE 1- CIRCULAR	16	LF
609.31	CURB TYPE 3	1,025	LF
609.34	CURB TYPE 5	2,775	LF
609.35	CURB TYPE 5 - CIRCULAR	95	LF
610.08	PLAIN RIPRAP	35	CY
610.18	STONE DITCH PROTECTION	20	CY
613.319	EROSION CONTROL BLANKET	4,750	SY
615.07	LOAM	1,480	CY

[illegible]

SHEET NUMBER 2	RELOCATED US 1 BRIDGE INTERSTATE 295 CUMBERLAND-YARMOUTH CUMBERLAND COUNTY						
	PROJ. MANAGER		J.Broski	BY	DATE		
	DESIGN-DETAILED	JCC	LDC	OCT. 2024			
	CHECKED-REVISED	GOK	STJ	OCT. 2024			
	DESIGN2-DETAILED2	RPM	SMA	OCT. 2024	SIGNATURE		
	DESIGN3-DETAILED3	PAVEMENT MARKINGS			8/27/25	P.E. NUMBER	
ESTIMATED QUANTITIES							
REVISIONS 1							
REVISIONS 2							
REVISIONS 3							
REVISIONS 4							
FIELD CHANGES							
BRIDGE NO. 5804 WIN 22382.00 BRIDGE PLANS							

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	2.100 AC	_____	_____	_____	_____
0020	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	2.000 EA	_____	_____	_____	_____
0030	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	_____
0040	202.202 REMOVING PAVEMENT SURFACE	1,150.000 SY	_____	_____	_____	_____
0050	202.205 RUMBLE STRIPS - SHOULDER	1,500.000 LF	_____	_____	_____	_____
0060	202.207 RUMBLE STRIPS, FILL	1,500.000 LF	_____	_____	_____	_____
0070	203.20 COMMON EXCAVATION	11,300.000 CY	_____	_____	_____	_____
0080	203.24 COMMON BORROW	41,500.000 CY	_____	_____	_____	_____
0090	203.25 GRANULAR BORROW	380.000 CY	_____	_____	_____	_____
0100	203.4338 LIGHTWEIGHT FILL FOAMED GLASS AGGREGATE	1,300.000 CY	_____	_____	_____	_____
0110	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	196.000 CY	_____	_____	_____	_____
0120	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	11,000.000 CY	_____	_____	_____	_____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	1,430.000 T	_____	 _____	_____	 _____
0140	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	330.000 T	_____	 _____	_____	 _____
0150	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	4,850.000 T	_____	 _____	_____	 _____
0160	409.15 BITUMINOUS TACK COAT - APPLIED	885.000 G	_____	 _____	_____	 _____
0170	461.131 TEMPORARY PAVEMENT	600.000 T	_____	 _____	_____	 _____
0180	501.239 DYNAMIC LOADING TESTS - PROVIDING FOR	3.000 EA	_____	 _____	_____	 _____
0190	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	1,750.000 LF	_____	 _____	_____	 _____
0200	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	1,600.000 LF	_____	 _____	_____	 _____
0210	501.90 PILE TIPS	35.000 EA	_____	 _____	_____	 _____
0220	501.91 PILE SPLICES	14.000 EA	_____	 _____	_____	 _____
0230	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP	SUM	_____	_____
0250	502.239 STRUCTURAL CONCRETE PIERS	LUMP SUM	LUMP	SUM	_____	_____
0260	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP	SUM	_____	_____
0270	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0280	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	5,400.000 LB	_____	_____	_____	_____
0290	503.13 REINFORCING STEEL, PLACING	5,400.000 LB	_____	_____	_____	_____
0295	503.17 MECHANICAL WELDED SPLICE	626.000 EA	_____	_____	_____	_____
0300	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	189,600.000 LB	_____	_____	_____	_____
0310	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	189,600.000 LB	_____	_____	_____	_____
0320	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM	LUMP	SUM	_____	_____
0330	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	SUM	_____	_____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0350	506.9104 THERMAL SPRAY COATING - SHOP APPLIED	LUMP SUM	LUMP	SUM	_____	_____
0360	507.0833 BARRIER MOUNTED BRIDGE RAIL, BICYCLE	LUMP SUM	LUMP	SUM	_____	_____
0370	507.0848 BARRIER-MOUNTED STEEL BRIDGE RAILING, 2 BAR	LUMP SUM	LUMP	SUM	_____	_____
0380	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0390	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0400	519.60 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	110.000 LF	_____	_____	_____	_____
0410	523.52 BEARING INSTALLATION	7.000 EA	_____	_____	_____	_____
0420	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	7.000 EA	_____	_____	_____	_____
0430	524.301 TEMPORARY STRUCTURAL SUPPORT PIER	LUMP SUM	LUMP	SUM	_____	_____
0435	524.301 TEMPORARY STRUCTURAL SUPPORT EXISTING ABUTMENT	LUMP SUM	LUMP	SUM	_____	_____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0440	524.40 PROTECTIVE SHIELD	LUMP SUM		LUMP SUM		
0450	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM		
0460	526.341 PERMANENT CONCRETE BARRIER	LUMP SUM		LUMP SUM		
0470	527.33 TRUCK MOUNTED ATTENUATOR	2.000 EA				
0480	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0490	603.169 15 INCH CULVERT PIPE OPTION III	160.000 LF				
0500	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	192.000 LF				
0510	603.179 18 INCH CULVERT PIPE OPTION III	286.000 LF				
0520	604.092 CATCH BASIN TYPE B1-C	3.000 EA				
0530	604.16 ALTERING CATCH BASIN TO MANHOLES	1.000 EA				
0540	604.262 CATCH BASIN TYPE B5-C	14.000 EA				
0550	605.11 12 INCH UNDERDRAIN TYPE C	614.000 LF				

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0560	605.13 18 INCH UNDERDRAIN TYPE C	306.000 LF	_____	_____	_____	_____
0570	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	1,275.000 LF	_____	_____	_____	_____
0580	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	4.000 EA	_____	_____	_____	_____
0590	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	2.000 EA	_____	_____	_____	_____
0600	606.1307 BRIDGE TRANSITION (ASYMMETRICAL) - TYPE 1A	4.000 EA	_____	_____	_____	_____
0610	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	25.000 LF	_____	_____	_____	_____
0620	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	75.000 LF	_____	_____	_____	_____
0630	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000 EA	_____	_____	_____	_____
0640	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	14.000 EA	_____	_____	_____	_____
0650	607.16 CHAIN LINK FENCE - 4 FOOT	850.000 LF	_____	_____	_____	_____
0660	607.1811 CHAIN LINK FENCE - 3 FOOT	180.000 LF	_____	_____	_____	_____
0670	607.421 SCREENING FENCE	184.000 LF	_____	_____	_____	_____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0680	608.26 CURB RAMP DETECTABLE WARNING FIELD	150.000 SF	_____	 _____	_____	 _____
0690	609.11 VERTICAL CURB TYPE 1	475.000 LF	_____	 _____	_____	 _____
0700	609.12 VERTICAL CURB TYPE 1 - CIRCULAR	105.000 LF	_____	 _____	_____	 _____
0710	609.221 TERMINAL CURB TYPE 1	16.000 LF	_____	 _____	_____	 _____
0720	609.222 TERMINAL CURB TYPE 1 - CIRCULAR	16.000 LF	_____	 _____	_____	 _____
0730	609.31 CURB TYPE 3	1,025.000 LF	_____	 _____	_____	 _____
0740	609.34 CURB TYPE 5	2,775.000 LF	_____	 _____	_____	 _____
0750	609.35 CURB TYPE 5 - CIRCULAR	95.000 LF	_____	 _____	_____	 _____
0760	610.08 PLAIN RIPRAP	35.000 CY	_____	 _____	_____	 _____
0770	610.18 STONE DITCH PROTECTION	20.000 CY	_____	 _____	_____	 _____
0780	613.319 EROSION CONTROL BLANKET	4,750.000 SY	_____	 _____	_____	 _____
0790	615.07 LOAM	1,480.000 CY	_____	 _____	_____	 _____
0800	618.14 SEEDING METHOD NUMBER 2	120.000 UN	_____	 _____	_____	 _____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0810	619.12 MULCH	120.000 UN	_____	_____	_____	_____
0820	619.14 EROSION CONTROL MIX	2,960.000 CY	_____	_____	_____	_____
0830	620.58 EROSION CONTROL GEOTEXTILE	40.000 SY	_____	_____	_____	_____
0840	626.22 NON-METALLIC CONDUIT	2,280.000 LF	_____	_____	_____	_____
0850	626.35 CONTROLLER CABINET FOUNDATION	3.000 EA	_____	_____	_____	_____
0860	626.36 REMOVE OR MODIFY CONCRETE FOUNDATION	9.000 EA	_____	_____	_____	_____
0870	626.421 24 INCH DIAMETER FOUNDATION	115.000 LF	_____	_____	_____	_____
0880	627.18 12 " SOLID WHITE PAVEMENT MARKING	300.000 LF	_____	_____	_____	_____
0885	627.30 GROOVING FOR PAVEMENT MARKING	5,600.000 SF	_____	_____	_____	_____
0890	627.734 4" WHITE OR YELLOW POLYUREA PAVEMENT MARKING LINE (RECESSED)	9,900.000 LF	_____	_____	_____	_____
0900	627.745 6" WHITE OR YELLOW POLYUREA PAVEMENT MARKING LINE (RECESSED)	2,150.000 LF	_____	_____	_____	_____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0910	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	825.000 SF	_____	_____	_____	_____
0920	627.77 REMOVING PAVEMENT MARKINGS	500.000 SF	_____	_____	_____	_____
0930	627.782 TEMPORARY 4 INCH POLYUREA PAVEMENT MARKING LINE, WHITE OR YELLOW	8,000.000 LF	_____	_____	_____	_____
0940	627.783 TEMPORARY 6 INCH POLYUREA PAVEMENT MARKING LINE, WHITE OR YELLOW	42,000.000 LF	_____	_____	_____	_____
0950	629.05 HAND LABOR, STRAIGHT TIME	100.000 HR	_____	_____	_____	_____
0960	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	50.000 HR	_____	_____	_____	_____
0970	631.11 AIR TOOL (INCLUDING OPERATOR)	50.000 HR	_____	_____	_____	_____
0980	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR	_____	_____	_____	_____
0990	631.13 BULLDOZER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
1000	631.14 GRADER (INCLUDING OPERATOR)	50.000 HR	_____	_____	_____	_____
1010	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR	_____	_____	_____	_____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 10 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1020	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	50.000 HR	_____	 _____	_____	 _____
1030	631.22 FRONT END LOADER (INCLUDING OPERATOR)	50.000 HR	_____	 _____	_____	 _____
1040	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
1050	634.160 HIGHWAY LIGHTING	LUMP SUM	LUMP SUM		_____	 _____
1060	634.2042 LED LUMINARIES	7.000 EA	_____	 _____	_____	 _____
1070	634.210 CONVENTIONAL LIGHT STANDARD	7.000 EA	_____	 _____	_____	 _____
1080	634.2223 REMOVE AND RESET LIGHT STANDARD WITH LUMINAIRE	9.000 EA	_____	 _____	_____	 _____
1090	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
1100	643.62 RECTANGULAR RAPID FLASHING BEACON	1.000 EA	_____	 _____	_____	 _____
1110	643.65 PEDESTRIAN HYBRID BEACON SIGNAL LIGHT	LUMP SUM	LUMP SUM		_____	 _____
1120	643.97 WOOD POLES WITH GUYS AND SPAN WIRE	1.000 EA	_____	 _____	_____	 _____
1130	645.103 DEMOUNT GUIDE SIGN	65.000 EA	_____	 _____	_____	 _____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 11 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1140	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	43.000 EA	_____	_____	_____	_____
1150	645.108 DEMOUNT POLE	1.000 EA	_____	_____	_____	_____
1160	645.113 REINSTALL GUIDE SIGN	65.000 EA	_____	_____	_____	_____
1170	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	43.000 EA	_____	_____	_____	_____
1180	645.118 REINSTALL POLE	1.000 EA	_____	_____	_____	_____
1190	645.271 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS, TYPE I	95.000 SF	_____	_____	_____	_____
1200	652.312 TYPE III BARRICADE	10.000 EA	_____	_____	_____	_____
1210	652.33 DRUM	250.000 EA	_____	_____	_____	_____
1220	652.34 CONE	250.000 EA	_____	_____	_____	_____
1230	652.35 CONSTRUCTION SIGNS	660.000 SF	_____	_____	_____	_____
1240	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	_____

7/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 12 of 12

Proposal ID: 022382.00

Project(s): 022382.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1250	652.38 FLAGGER	3,000.000 HR	_____	_____	_____	_____
1260	652.381 TRAFFIC OFFICER	240.000 HR	_____	_____	_____	_____
1270	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	_____	_____	_____
1280	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
1290	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	1,130.000 SY	_____	_____	_____	_____
1300	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
1310	677.20 MECHANICALLY STABILIZED EARTH RETAINING WALL	6,900.000 SF	_____	_____	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____