



Janet T. Mills
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Bruce A. Van Note
COMMISSIONER

April 11, 2019
Subject: Pavement Milling, HMA Overlay,
Bridge Work with Drainage & Safety
Improvements
State WINs: 022420.00, 022422.00 &
023615.00
Location: **Falmouth, Portland &
South Portland**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

ADD the attached SPECIAL PROVISION – SECTION 202 – Remove Structures and Obstructions, 1 page,
dated 3/27/2019.

ADD the attached SPECIAL PROVISION – SECTION 202 – Remove Structures and Obstructions, 1 page,
dated 3/27/2019.

Consider these changes and information prior to submitting your bid on **April 17, 2019**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

Portland- South Portland
WIN 23615.00
3/27/2019

SPECIAL PROVISION
SECTION 202
Remove Structures and Obstructions

Item # 202.1212 Remove Existing Header Concrete.

Saw cutting header concrete to create a neat line up to 3 inches deep and remove concrete from the saw cut line to the existing pavement or another up to 3 inch deep saw cut line. As directed by the resident.

Portland- South Portland
WIN 23615.00
3/27/2019

SPECIAL PROVISION
SECTION 202
Remove Structures and Obstructions

Item # 202.1231 Scarify Concrete Header.

Remove and profile a depth up to ½ inch of the concrete joint header. This will be performed using mechanical means (i.e. scabbler) to create a uniform profiled surface. As directed by the resident.