



Janet Mills
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Bruce A. Van Note
COMMISSIONER

March 8, 2019

Subject: Pavement Milling, HMA Overlay,
Cyclical Pavement Resurfacing
with Drainage & Safety Improvements
State WINs: 022428.00, 022430.00,
024021.00 & 024023.00

Location: **Canton, Dixfield, Hartford, Jay
& Wilton**
Amendment No. 1

Dear Sir/Ms.:

The following questions have been received:

Question: Can you provide stations for guardrail item 606.362?

Response: This is an item to be determined and used in the field as needed. No specific stations were determined.

Question: Typically the Department uses Item 202.2023 Removing Pavement Surface Medium Cut Drum (8MM) for thinner lift milling typically .75" other than is specified for this contract at 1.5". Would the Department consider using Item 202.202 Removing Pavement Surface using a 15MM Drum spacing for this contract?

Response: The Department has specified the use of a medium cut, 8mm drum for this contract given the traffic levels and placement of surface without a required shim layer. The finer texture typically provides a smoother milled surface to place the surface upon, and holds up better to traffic. This is consistent with what was required on the Route 4 project in 2018.

Consider these changes and information prior to submitting your bid on **March 13, 2019**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer