



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

September 27, 2023
Subject: Spring Brook Bridge Replacement
State WIN: 022608.00
Location: **Camden**
Amendment No. 1

Dear Sir/Ms.:

Make The following changes to the Bid Documents

In The Bid Book:

Remove Pages Sixteen to Twenty-Two Proposal Schedule of Items dated 8/23/2023 and **Replace** with the attached Proposal Schedule of items dated 9/26/2023 Totaling Seven Pages

Remove Page fifty five titled SPECIAL PROVISION SECTION 107 TIME (Supplemental Liquidated Damage) and **Replace** with the attached SPECIAL PROVISION SECTION 107 TIME (Supplemental Liquidated Damage)

Insert SPECIAL PROVISION SECTION 105 GENERAL SCOPE OF WORK (Traffic Control and Management) totaling one page

The following questions have been received:

Question: There don't appear to be any pay items for either permanent or temporary pavement markings. Nor is there an item for Pavement Marking removal. Please advise.

Response: Please see updated Proposal Schedule of Items dated 9/26/23. On sheet 2 *Estimated Quantities & General Construction Notes* of the plan set, add the following items:

627.77 REMOVING PAVEMENT MARKINGS 450.00 SF

627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE 2,700 LF

627.78 TEMPORARY 4 INCH PAINTED MARKING LINE, WHITE OR YELLOW 1,900 lf

Make these changes in pen and ink.

Consider these changes and information prior to submitting your bid on **October 11, 2023**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022608.00

Project(s): 022608.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.19 REMOVING EXISTING BRIDGE	LUMP SUM				
0020	202.202 REMOVING PAVEMENT SURFACE	3,125.000 SY				
0030	203.20 COMMON EXCAVATION	20.000 CY				
0040	203.2318 DISPOSAL OF SPECIAL WASTE	20.000 T				
0050	203.24 COMMON BORROW	100.000 CY				
0060	203.25 GRANULAR BORROW	510.000 CY				
0070	203.33 SPECIAL FILL	350.000 CY				
0080	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	440.000 CY				
0090	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	2,520.000 CY				
0100	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	320.000 T				
0110	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	620.000 T				
0120	409.15 BITUMINOUS TACK COAT - APPLIED	120.000 G				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022608.00

Project(s): 022608.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	461.131 TEMPORARY PAVEMENT	790.000 T	_____	 _____	_____	 _____
0140	501.239 DYNAMIC LOADING TESTS - PROVIDING FOR	2.000 EA	_____	 _____	_____	 _____
0150	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	380.000 LF	_____	 _____	_____	 _____
0160	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	320.000 LF	_____	 _____	_____	 _____
0170	501.903 PILE TIPS - ROCK INJECTOR POINT	12.000 EA	_____	 _____	_____	 _____
0180	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
0190	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP SUM		_____	 _____
0200	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP SUM		_____	 _____
0210	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP SUM		_____	 _____
0220	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM		_____	 _____
0230	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	14,200.000 LB	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022608.00

Project(s): 022608.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	503.13 REINFORCING STEEL, PLACING	14,200.000 LB	_____	 _____	_____	 _____
0250	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	6,000.000 LB	_____	 _____	_____	 _____
0260	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	6,000.000 LB	_____	 _____	_____	 _____
0270	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP SUM		LUMP SUM	_____	 _____
0280	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM		LUMP SUM	_____	 _____
0290	505.08 SHEAR CONNECTORS	LUMP SUM		LUMP SUM	_____	 _____
0300	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM		LUMP SUM	_____	 _____
0310	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	 _____	_____	 _____
0320	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM		LUMP SUM	_____	 _____
0330	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED 28 FT	LUMP SUM		LUMP SUM	_____	 _____
0340	511.07 COFFERDAM: ABUT NO.1	LUMP SUM		LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022608.00

Project(s): 022608.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	511.07 COFFERDAM: ABUT NO.2	LUMP SUM	LUMP	SUM	_____	_____
0360	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0370	519.60 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	65.000 LF	_____	_____	_____	_____
0380	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN	_____	_____	_____	_____
0390	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	43,700.000 LF	_____	_____	_____	_____
0400	530.31 GFRP, REINFORCEMENT BARS, PLACING	43,700.000 LF	_____	_____	_____	_____
0410	603.17 18 INCH CULVERT PIPE OPTION I	78.000 LF	_____	_____	_____	_____
0420	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	56.000 LF	_____	_____	_____	_____
0430	603.199 24 INCH CULVERT PIPE OPTION III	32.000 LF	_____	_____	_____	_____
0440	603.229 42 INCH CULVERT PIPE OPTION III	74.000 LF	_____	_____	_____	_____
0450	604.072 CATCH BASIN TYPE A1-C	4.000 EA	_____	_____	_____	_____
0460	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	1,025.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022608.00

Project(s): 022608.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	50.000 LF	_____	 _____	_____	 _____
0480	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	 _____	_____	 _____
0490	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	 _____	_____	 _____
0500	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	 _____	_____	 _____
0510	606.366 GUARDRAIL, REMOVE & RESET	188.000 LF	_____	 _____	_____	 _____
0520	610.08 PLAIN RIPRAP	1,700.000 CY	_____	 _____	_____	 _____
0530	610.16 HEAVY RIPRAP	1,650.000 CY	_____	 _____	_____	 _____
0540	610.18 STONE DITCH PROTECTION	390.000 CY	_____	 _____	_____	 _____
0550	610.210 STREAM CHANNEL ROCK	400.000 CY	_____	 _____	_____	 _____
0560	610.212 STREAMBED ROCK FEATURES	320.000 CY	_____	 _____	_____	 _____
0570	613.319 EROSION CONTROL BLANKET	180.000 SY	_____	 _____	_____	 _____
0580	620.58 EROSION CONTROL GEOTEXTILE	3,100.000 SY	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022608.00

Project(s): 022608.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	620.66 DRAINAGE GEOCOMPOSITE	125.000 SY	_____	 _____	_____	 _____
0595	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2,700.000 LF	_____	 _____	_____	 _____
0597	627.77 REMOVING PAVEMENT MARKINGS	450.000 SF	_____	 _____	_____	 _____
0598	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,900.000 LF	_____	 _____	_____	 _____
0600	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	 _____	_____	 _____
0610	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0620	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0630	652.312 TYPE III BARRICADE	9.000 EA	_____	 _____	_____	 _____
0640	652.33 DRUM	20.000 EA	_____	 _____	_____	 _____
0650	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0660	652.35 CONSTRUCTION SIGNS	500.000 SF	_____	 _____	_____	 _____
0670	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 022608.00

Project(s): 022608.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0680	652.38 FLAGGER	120.000 HR	_____	_____	_____	_____
0690	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0700	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0710	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____

SPECIAL PROVISION
SECTION 107
TIME
(Supplemental Liquidated Damages)

Single lane closures with alternating one-way traffic may be allowed between the Tuesday following Labor Day and July 3rd. Between the hours of 5:00am and 9:00pm, complete traffic stoppages shall not exceed a maximum of 10-minutes. Between the hours of 9:00pm and 5:00am complete traffic stoppages shall not exceed 30-minutes. The Contractor will be assessed Supplemental Liquidated Damages at the rate of Five Hundred (\$500.00) per occurrence when these complete stoppages are exceeded.

Single lane closures with alternating one-way traffic may be allowed between July 4th and Labor Day. Between the hours of 5:00am and 9:00pm complete traffic stoppages shall not exceed a maximum of 5-minutes. Between the hours of 9:00pm and 5:00am complete traffic stoppages shall not exceed 30-minutes. The Contractor will be assessed Supplemental Liquidated Damages at the rate of Five Hundred (\$500.00) per occurrence when these complete stoppages are exceeded.

From December 15th through March 15th, two lanes of traffic shall be maintained during all non-working hours. The Contractor will be assessed Supplemental Liquidated Damages at the rate of Two Thousand (\$2,000.00) per hour, or portion of an hour, when two lanes of traffic are not maintained between December 15th and March 15th.

SPECIAL PROVISION
SECTION 105
GENERAL SCOPE OF WORK
(Traffic Control and Management)

Two lanes of traffic shall be maintained at all times unless otherwise allowed.

A minimum lane width of 11'-0" shall be maintained at all times.