



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Dale F. Doughty
COMMISSIONER

September 29, 2026
Subject: Highway Reconstruction
WIN:022656.00
Location: Frenchville
Amendment No. 2

Dear Sir/Ms.:

Make the Following changes to the Bid Documents

In the Bid Book:

Remove Pages 17-23 Proposal Schedule of Items dated 9/1/2026 and **Replace** with the attached Proposal Schedule of Items dated 9/29/2026.

In the Plan Set:

Remove Sheet 8 dated 9/11/2026 and **replace** with the attached Sheet 8, dated 9/29/2026.

The following questions have been received:

Question: Just looking for clarification on the 72" Option III culvert. What Gauge, corrugation profile etc. Thank you

Response: MaineDOT does not have a specific preference for pipes under 10' in diameter beyond what the standard specs call for. Standard Spec 603.02 (Materials) provides information to the 700 standard specs where

Question: On sheet 5 of the final plans it shows a retaining wall with 4' snow fence, is the fencing incidental to the retaining wall or should there be an item for the fence added to the schedule of items?

Response: Please add Item Number 607.163, Chain Link Fence, 4', PVC Coated, quantity 190 Fencing is to be installed on the retaining wall as shown on the plans.

Consider these changes and information prior to submitting your bid on **October 7, 2026.**

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

9/29/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	6.000 AC	_____	_____	_____	_____
0020	201.23 REMOVING SINGLE TREE TOP ONLY	15.000 EA	_____	_____	_____	_____
0030	201.24 REMOVING STUMP	15.000 EA	_____	_____	_____	_____
0040	203.20 COMMON EXCAVATION	121,500.000 CY	_____	_____	_____	_____
0050	203.21 ROCK EXCAVATION	750.000 CY	_____	_____	_____	_____
0060	203.25 GRANULAR BORROW	100.000 CY	_____	_____	_____	_____
0070	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	200.000 CY	_____	_____	_____	_____
0080	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	50.000 CY	_____	_____	_____	_____
0090	304.16 AGGREGATE BASE COURSE - TYPE C	83,700.000 CY	_____	_____	_____	_____
0100	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	7,200.000 T	_____	_____	_____	_____
0110	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	450.000 T	_____	_____	_____	_____
0120	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	16,800.000 T	_____	_____	_____	_____

9/29/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	409.15 BITUMINOUS TACK COAT - APPLIED	5,800.000 G				
0140	511.07 COFFERDAM: CULVERT STA. 678+00 - DOWNSTREAM	LUMP SUM		LUMP SUM		
0150	511.07 COFFERDAM: CULVERT STA. 678+00 - UPSTREAM	LUMP SUM		LUMP SUM		
0160	511.07 COFFERDAM: SLOPE STABILIZATION	LUMP SUM		LUMP SUM		
0170	603.159 12 INCH CULVERT PIPE OPTION III	50.000 LF				
0180	603.16 15 INCH CULVERT PIPE OPTION I	635.000 LF				
0190	603.169 15 INCH CULVERT PIPE OPTION III	110.000 LF				
0200	603.17 18 INCH CULVERT PIPE OPTION I	75.000 LF				
0210	603.179 18 INCH CULVERT PIPE OPTION III	590.000 LF				
0220	603.199 24 INCH CULVERT PIPE OPTION III	850.000 LF				
0230	603.209 30 INCH CULVERT PIPE OPTION III	260.000 LF				
0240	603.219 36 INCH CULVERT PIPE OPTION III	130.000 LF				
0250	603.229 42 INCH CULVERT PIPE OPTION III	90.000 LF				

9/29/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0260	603.279 72 INCH CULVERT PIPE OPTION III	90.000 LF				
0270	604.092 CATCH BASIN TYPE B1-C	24.000 EA				
0280	604.096 60 INCH CATCH BASIN TYPE B1-C	1.000 EA				
0290	604.097 72 INCH CATCH BASIN TYPE B1-C	1.000 EA				
0300	605.09 6 INCH UNDERDRAIN TYPE B	5,650.000 LF				
0310	605.10 6 INCH UNDERDRAIN OUTLET	160.000 LF				
0320	605.11 12 INCH UNDERDRAIN TYPE C	965.000 LF				
0330	605.12 15 INCH UNDERDRAIN TYPE C	455.000 LF				
0340	605.13 18 INCH UNDERDRAIN TYPE C	220.000 LF				
0350	605.15 24 INCH UNDERDRAIN TYPE C	180.000 LF				
0360	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	8,800.000 LF				
0370	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	250.000 LF				

9/29/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0380	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	27.000 LF	_____	 _____	_____	 _____
0390	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	8.000 EA	_____	 _____	_____	 _____
0400	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	10.000 EA	_____	 _____	_____	 _____
0410	606.3511 SNOW POLE	18.000 EA	_____	 _____	_____	 _____
0420	606.356 UNDERDRAIN DELINEATOR POST	10.000 EA	_____	 _____	_____	 _____
0425	607.163 CHAIN LINK FENCE - 4 FOOT P.V.C. COATED	190.000 LF	_____	 _____	_____	 _____
0430	609.31 CURB TYPE 3	3,800.000 LF	_____	 _____	_____	 _____
0440	610.08 PLAIN RIPRAP	10,780.000 CY	_____	 _____	_____	 _____
0450	610.16 HEAVY RIPRAP	1,700.000 CY	_____	 _____	_____	 _____
0460	613.319 EROSION CONTROL BLANKET	6,200.000 SY	_____	 _____	_____	 _____
0470	615.07 LOAM	2,500.000 CY	_____	 _____	_____	 _____
0480	615.10 DIRTY BORROW	5,000.000 CY	_____	 _____	_____	 _____

9/29/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0490	618.13 SEEDING METHOD NUMBER 1	200.000 UN	_____	_____	_____	_____
0500	618.14 SEEDING METHOD NUMBER 2	800.000 UN	_____	_____	_____	_____
0510	619.12 MULCH	1,000.000 UN	_____	_____	_____	_____
0520	620.58 EROSION CONTROL GEOTEXTILE	36,340.000 SY	_____	_____	_____	_____
0530	620.591 EROSION CONTROL GEOTEXTILE - RIPRAP SLOPES	1,810.000 SY	_____	_____	_____	_____
0540	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	74,000.000 LF	_____	_____	_____	_____
0550	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	148,000.000 LF	_____	_____	_____	_____
0560	629.05 HAND LABOR, STRAIGHT TIME	120.000 HR	_____	_____	_____	_____
0570	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0580	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0590	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR	_____	_____	_____	_____

9/29/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0600	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	150.000 HR	_____	_____	_____	_____
0610	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	5.000 HR	_____	_____	_____	_____
0620	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0630	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	5.000 HR	_____	_____	_____	_____
0640	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	_____	_____	_____
0650	652.33 DRUM	150.000 EA	_____	_____	_____	_____
0660	652.34 CONE	150.000 EA	_____	_____	_____	_____
0670	652.35 CONSTRUCTION SIGNS	500.000 SF	_____	_____	_____	_____
0680	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	480.000 CD	_____	_____	_____	_____
0690	652.38 FLAGGER	15,100.000 HR	_____	_____	_____	_____
0700	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	_____	_____	_____

9/29/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0710	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0720	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
0730	660.21 ON-THE-JOB TRAINING (BID)	1,000.000 HR	_____	_____	_____	_____
0740	672.10 PRECAST CONCRETE BLOCK GRAVITY WALL	980.000 SF	_____	_____	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____

ITEM NO.	ITEM	UNIT	QUANTITY
606.265	TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	EA	10
606.353	REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	EA	18
606.356	UNDERDRAIN DELINEATOR POST	EA	10
607.163	CHAIN LINK FENCE - 4 FT - PVC COATED	LF	190
609.31	CURB TYPE 3	LF	3800
610.08	PLAIN RIPRAP	CY	10780
610.16	HEAVY RIPRAP	CY	1700
613.319	EROSION CONTROL BLANKET	SY	6200
615.07	LOAM	CY	2500
615.10	DIRTY BORROW	CY	5000
618.13	SEEDING METHOD NUMBER 1	Unit	200
618.14	SEEDING METHOD NUMBER 2	Unit	800
619.12	MULCH	Unit	1000
620.58	EROSION CONTROL GEOTEXTILE	SY	36340
620.591	EROSION CONTROL GEOTEXTILE - RIPRAP SLOPES	SY	1810
627.733	4" WHITE OR YELLOW PAVEMENT MARKING LINE	LF	74000
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LF	148000
629.05	HAND LABOR - STRAIGHT TIME	HR	120
631.10	AIR COMPRESSOR (INCLUDING OPERATOR)	HR	10
631.11	AIR TOOL (INCLUDING OPERATOR)	HR	10
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	HR	100
631.172	TRUCK, LARGE (INCLUDING OPERATOR)	HR	150
631.20	STUMP CHIPPER RENTAL (INCLUDING OPERATOR)	HR	5
631.22	FRONT END LOADER (INCLUDING OPERATOR)	HR	20
631.32	CULVERT CLEANER (INC. OPERATOR)	HR	5
639.18	FIELD OFFICE TYPE A	EA	1
652.33	DRUM	EA	150
652.34	CONE	EA	150
652.35	CONSTRUCTION SIGNS	SF	500
652.36	MAINTENANCE OF TRAFFIC CONTROL DEVICES	CD	480
652.38	FLAGGERS	HR	15,100
652.41	PORTABLE CHANGEABLE MESSAGE SIGN	EA	4
656.75	TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LS	1
659.10	MOBILIZATION	LS	1
672.10	PRECAST CONCRETE BLOCK GRAVITY WALL	SF	980

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION

STP-2265(600)

WIN
22656.00
HIGHWAY PLANS

PROJ. MANAGER
DESIGN-DETAILED
CHECKED-REVIEWED
DESIGN-DETAILED
REVISIONS 1
REVISIONS 2
REVISIONS 3
REVISIONS 4
FIELD CHANGES

M. ROONEY
T. KERREY
B. WATSON
B. WATSON

BY
T. KERREY
B. WATSON

DATE
9/29/27
9/29/26

SIGNATURE

P.E. NUMBER

DATE

FRENCHVILLE - FORT KENT
U.S. ROUTE 1

ESTIMATED QUANTITIES

SHEET NUMBER

8

OF 384

TYLININTERNATIONAL