



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Dale F. Doughty
COMMISSIONER

October 2, 2026
Subject: Highway Reconstruction
WIN:022656.00
Location: Frenchville
Amendment No. 4

Dear Sir/Ms.:

Make the following changes to the Bid book:

Remove PP 17-23 Proposal Schedule of Items and **Replace** with the attached Schedule of Items dated 10/1/2026.

In the Plan Sheet:

Remove Sheet 7 dated 9/11/2026 and **Replace** with the attached Sheet 7, dated 10/1/2026.

The following questions have been received:

Question: If RCP is used for option III pipes, will pipe ties be paid for separate or considered incidental to option III pipes.

Response: If RCP is used, pipe ties will be paid for separately, two on each end for each cross pipe. Pipe Ties will only be used if the contractor elects to use RCP.

Question: Could you provide the Earthwork Summary for this project if available?

Response: An excavation quantities worksheet has been posted under a prior amendment.

Question: Do you anticipate the 750 CY of Rock Excavation from stations 647+00 to 651+00 area?

Response: The 750 CY that is included in the plans for STA 647+00 to 651+00 LT is an estimated quantity based on available boring information. There is a chance this number will be reduced, based on the nature of the ledge that is encountered once construction begins,

Question: Will Canadian produced RCP pipe be acceptable?

Response: No. This Project is subject to the Buy America (23 CFR 635.410) and Build America, Buy America Act (BABA) included in the Infrastructure Investment and Jobs Act (IIJA), Public Law No. 117-58. Further guidance can be found at the FHWA Buy America Construction Program Guide linked here:

<https://www.fhwa.dot.gov/construction/cqit/buyam.cfm>

Consider these changes and information prior to submitting your bid on **October 7, 2026**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

10/1/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	6.000 AC	_____	_____	_____	_____
0020	201.23 REMOVING SINGLE TREE TOP ONLY	15.000 EA	_____	_____	_____	_____
0030	201.24 REMOVING STUMP	15.000 EA	_____	_____	_____	_____
0040	203.20 COMMON EXCAVATION	121,500.000 CY	_____	_____	_____	_____
0050	203.21 ROCK EXCAVATION	750.000 CY	_____	_____	_____	_____
0060	203.25 GRANULAR BORROW	100.000 CY	_____	_____	_____	_____
0070	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	200.000 CY	_____	_____	_____	_____
0080	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	50.000 CY	_____	_____	_____	_____
0090	304.16 AGGREGATE BASE COURSE - TYPE C	83,700.000 CY	_____	_____	_____	_____
0100	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	7,200.000 T	_____	_____	_____	_____
0110	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	450.000 T	_____	_____	_____	_____
0120	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	16,800.000 T	_____	_____	_____	_____

10/1/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	409.15 BITUMINOUS TACK COAT - APPLIED	5,800.000 G				
0140	511.07 COFFERDAM: CULVERT STA. 678+00 - DOWNSTREAM	LUMP SUM	LUMP	SUM		
0150	511.07 COFFERDAM: CULVERT STA. 678+00 - UPSTREAM	LUMP SUM	LUMP	SUM		
0160	511.07 COFFERDAM: SLOPE STABILIZATION	LUMP SUM	LUMP	SUM		
0170	603.159 12 INCH CULVERT PIPE OPTION III	50.000 LF				
0180	603.16 15 INCH CULVERT PIPE OPTION I	635.000 LF				
0190	603.169 15 INCH CULVERT PIPE OPTION III	110.000 LF				
0200	603.17 18 INCH CULVERT PIPE OPTION I	75.000 LF				
0210	603.179 18 INCH CULVERT PIPE OPTION III	590.000 LF				
0220	603.199 24 INCH CULVERT PIPE OPTION III	850.000 LF				
0230	603.209 30 INCH CULVERT PIPE OPTION III	260.000 LF				
0240	603.219 36 INCH CULVERT PIPE OPTION III	130.000 LF				
0250	603.229 42 INCH CULVERT PIPE OPTION III	90.000 LF				

10/1/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0260	603.279 72 INCH CULVERT PIPE OPTION III	90.000 LF				
0265	603.55 CONCRETE PIPE TIES	64.000 GP				
0270	604.092 CATCH BASIN TYPE B1-C	24.000 EA				
0280	604.096 60 INCH CATCH BASIN TYPE B1-C	1.000 EA				
0290	604.097 72 INCH CATCH BASIN TYPE B1-C	1.000 EA				
0300	605.09 6 INCH UNDERDRAIN TYPE B	5,650.000 LF				
0310	605.10 6 INCH UNDERDRAIN OUTLET	160.000 LF				
0320	605.11 12 INCH UNDERDRAIN TYPE C	965.000 LF				
0330	605.12 15 INCH UNDERDRAIN TYPE C	455.000 LF				
0340	605.13 18 INCH UNDERDRAIN TYPE C	220.000 LF				
0350	605.15 24 INCH UNDERDRAIN TYPE C	180.000 LF				
0360	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	8,800.000 LF				
0370	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	250.000 LF				

10/1/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0380	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	27.000 LF	_____	_____	_____	_____
0390	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	8.000 EA	_____	_____	_____	_____
0400	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	10.000 EA	_____	_____	_____	_____
0410	606.3511 SNOW POLE	18.000 EA	_____	_____	_____	_____
0420	606.356 UNDERDRAIN DELINEATOR POST	10.000 EA	_____	_____	_____	_____
0425	607.163 CHAIN LINK FENCE - 4 FOOT P.V.C. COATED	190.000 LF	_____	_____	_____	_____
0430	609.31 CURB TYPE 3	3,800.000 LF	_____	_____	_____	_____
0440	610.08 PLAIN RIPRAP	10,780.000 CY	_____	_____	_____	_____
0450	610.16 HEAVY RIPRAP	1,700.000 CY	_____	_____	_____	_____
0460	613.319 EROSION CONTROL BLANKET	6,200.000 SY	_____	_____	_____	_____
0470	615.07 LOAM	2,500.000 CY	_____	_____	_____	_____
0480	615.10 DIRTY BORROW	5,000.000 CY	_____	_____	_____	_____

10/1/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0490	618.13 SEEDING METHOD NUMBER 1	200.000 UN				
0500	618.14 SEEDING METHOD NUMBER 2	800.000 UN				
0510	619.12 MULCH	1,000.000 UN				
0520	620.58 EROSION CONTROL GEOTEXTILE	36,340.000 SY				
0530	620.591 EROSION CONTROL GEOTEXTILE - RIPRAP SLOPES	1,810.000 SY				
0540	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	74,000.000 LF				
0550	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	148,000.000 LF				
0560	629.05 HAND LABOR, STRAIGHT TIME	120.000 HR				
0570	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR				
0580	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR				
0590	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR				

10/1/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0600	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	150.000 HR	_____	 _____	_____	 _____
0610	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	5.000 HR	_____	 _____	_____	 _____
0620	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0630	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	5.000 HR	_____	 _____	_____	 _____
0640	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0650	652.33 DRUM	150.000 EA	_____	 _____	_____	 _____
0660	652.34 CONE	150.000 EA	_____	 _____	_____	 _____
0670	652.35 CONSTRUCTION SIGNS	500.000 SF	_____	 _____	_____	 _____
0680	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	480.000 CD	_____	 _____	_____	 _____
0690	652.38 FLAGGER	15,100.000 HR	_____	 _____	_____	 _____
0700	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	 _____	_____	 _____

10/1/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 7

Proposal ID: 022656.00

Project(s): 022656.00

SECTION: 1 INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0710	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0720	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
0730	660.21 ON-THE-JOB TRAINING (BID)	1,000.000 HR	_____	_____	_____	_____
0740	672.10 PRECAST CONCRETE BLOCK GRAVITY WALL	980.000 SF	_____	_____	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____

ITEM NO.	ITEM	UNIT	QUANTITY
201.11	CLEARING	AC	6
201.23	REMOVING SINGLE TREE TOP ONLY	EA	15
201.24	REMOVING STUMP	EA	15
203.20	COMMON EXCAVATION	CY	121,500
203.21	ROCK EXCAVATION	CY	750
203.25	GRANULAR BORROW	CY	100
206.061	STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES BELOW GRADE	CY	200
206.07	STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	CY	50
304.16	AGGREGATE BASE COURSE - TYPE C	CY	83,700
403.2081	12.5 MM Polymer Modified HMA	Ton	7200
403.209	HOT MIX ASPHALT, 9.5 MM NOMINAL MAX. SIZE (DRIVES, SIDEWALKS, AND INCIDENTALS)	Ton	450
403.2131	12.5 MM Polymer Modified HMA Base	Ton	16800
409.15	BITUMINOUS TACK COAT, APPLIED	G	5800
511.07	COFFERDAM: SLOPE STABILIZATION	LS	1
511.07	COFFERDAM: CULVERT STA. 678+00 UPSTREAM	LS	1
511.07	COFFERDAM: CULVERT STA. 678+00 DOWNSTREAM	LS	1
603.159	12" CULVERT PIPE OPTION III	LF	50
603.16	15" CULVERT PIPE OPTION I	LF	635
603.169	15" CULVERT PIPE OPTION III	LF	110
603.17	18" CULVERT PIPE OPTION I	LF	75
603.179	18" CULVERT PIPE OPTION III	LF	590
603.199	24" CULVERT PIPE OPTION III	LF	850
603.209	30" CULVERT PIPE OPTION III	LF	260
603.219	36" CULVERT PIPE OPTION III	LF	130
603.229	42" CULVERT PIPE OPTION III	LF	90
603.279	72" CULVERT PIPE OPTION III	LF	90
603.55	CONCRETE PIPE TIES	GROUP	64
604.092	CATCH BASIN TYPE B1-C	EA	24
604.096	60" CATCH BASIN TYPE B1-C	EA	1
604.097	72" CATCH BASIN TYPE B1-C	EA	1
605.09	6" UNDERDRAIN TYPE B	LF	5650
605.10	6" UNDERDRAIN OUTLET	LF	160
605.11	12" UNDERDRAIN TYPE C	LF	965
605.12	15" UNDERDRAIN TYPE C	LF	455
605.13	18" UNDERDRAIN TYPE C	LF	220
605.15	24" UNDERDRAIN TYPE C	LF	180
606.1301	31" W-BEAM GUARDRAIL - MID-WAY SPLICE (STEEL POST, 8" OFFSET BLOCKS, SINGLE FACED)	LF	8800
606.1303	31" W-BEAM GUARDRAIL - MID-WAY SPLICE (STEEL POST, 8" OFFSET BLOCKS, 15' RADIUS AND LESS)	LF	250
606.1304	31" W-BEAM GUARDRAIL - MID-WAY SPLICE (STEEL POST, 8" OFFSET BLOCKS, OVER 15' RADIUS)	LF	27
606.1305	31" W-BEAM GUARDRAIL - MID-WAY SPLICE FLARED TERMINAL (31" HEIGHT)	EA	8

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION

STP-2265(600)

WIN
22656.00
HIGHWAY PLANS

PROJ. MANAGER
DESIGN-DETAILED
CHECKED-REVIEWED
DESIGNS-DETAILED
REVISIONS 1
REVISIONS 2
REVISIONS 3
REVISIONS 4
FIELD CHANGES

M. ROONEY
T. KERKEY
B. WATSON
B. WATSON

BY
T. KERKEY
B. WATSON

DATE
9/2/07
8/2/06

SIGNATURE

P.E. NUMBER

DATE

FRENCHVILLE - FORT KENT
U.S. ROUTE 1

ESTIMATED QUANTITIES

SHEET NUMBER

7

OF 384