



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

April 22, 2019
Subject: Pavement Milling, HMA Overlay
With Drainage & Safety Improvements
State WINS: 022881.00 & 022883.00
Location: **Holden**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 17 – 19, Proposal Schedule of Items, 3 pages, dated 3/15/2019, and **REPLACE** with the attached, revised Proposal Schedule of Items, 3 pages, dated 4/18/2019.

The following questions have been received:

Question: Could you please provide information on the intended use of the following items.

203.20 Common Excavation

304.10 Aggregate Subbase – Coarse Gravel

Response: Item No. 203.20, Common Excavation is being used for the boxing out on WIN 022881.00, and driveways and slope corrections on both WINS. Item No. 304.10, Aggregate Subbase Course Gravel is being replaced with 411.10 Untreated Aggregate Surface Course, and will be used for rebuilding driveways.

Question: Based on the typical sections given on both sections of roadway, the 202.202 Remove Pavement Surface Item in the schedule of values appears to be low, please advise.

Response: The quantity has been updated. See revised schedule of items.

Question: Is item 202.202 Remove Pavement Surface to be used on mainline only?

Response: Yes.

Question: Where is the 203.20 common excavation item to be used? Could more information be provided for this work.

Response: For both WINs common excavation is to be used for driveways and slope corrections, and for WIN 022881.00 it is to be used for the boxing out in the shoulders where the shoulders are being reduced to accommodate the additional lane.

Question: What is the intent of the hourly rental items? Could more information be provided for what these items will be used for?

Response: The intent is for these items to be used at the Resident's discretion.

Question: Should there be an item for APE or Loader added to the hourly items to pick up material generated with the dozer or grader or is are these items just to smooth up existing material?

Response: See revised schedule of items. APE has been added and Bulldozer removed

Question: What is the 631.172 Truck Large to be used for?

Response: To be used with APE added in the revised schedule of items.

Question: Where is item 615.07 Loam to be used? Could more information be provided on where the Loam should be utilized.

Response: Loam is to be used behind where the new curbing is being placed.

Question: Where is item 304.10 Agg Subbase Course Gravel to be used?

Response: See revised schedule of items. Item No. 304.10 Aggregate Subbase Course Gravel is being replaced with Item No. 411.10 Untreated Aggregate Surface Course, and will be used for rebuilding driveways.

Question: Is the 202.202 remove pavement surface item quantity correct?

Response: No. See revised schedule of items.

Question: Can the stationing be provided for items 203.20 common excavation and 304.10?


Response: For both WINs 203.20 Common Excavation is to be used for driveways and slope corrections, and for WIN 022881.00 it is to be used for the boxing out in the shoulders where the shoulders are being reduced to accommodate the additional lane. See the typical. Item 304.10 has been replaced with Item 411.10 Untreated Aggregate Surface Course, and will be used for rebuilding drives.

Question: Once pavement has been removed off the shoulders at the 5 ½" depth, how long before they need to be paved back in?

Response: Refer to Standard Specification 652.3.4 General.

Consider these changes and information prior to submitting your bid on **April 24, 2019**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

4/18/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 022881.00

Project(s): 022881.00, 022883.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	24,650.000 SY	_____	 _____	_____	 _____
0020	202.203 PAVEMENT BUTT JOINTS	1,215.000 SY	_____	 _____	_____	 _____
0030	203.20 COMMON EXCAVATION	3,340.000 CY	_____	 _____	_____	 _____
0040	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	3,805.000 T	_____	 _____	_____	 _____
0050	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	245.000 T	_____	 _____	_____	 _____
0060	403.211 HOT MIX ASPHALT (SHIMMING)	320.000 T	_____	 _____	_____	 _____
0070	403.213 HOT MIX ASPHALT 12.5 MM BASE	3,650.000 T	_____	 _____	_____	 _____
0080	409.15 BITUMINOUS TACK COAT - APPLIED	2,300.000 G	_____	 _____	_____	 _____
0090	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	1,735.000 CY	_____	 _____	_____	 _____
0100	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	27.000 EA	_____	 _____	_____	 _____
0110	606.356 UNDERDRAIN DELINEATOR POST	11.000 EA	_____	 _____	_____	 _____
0120	606.47 SINGLE WOOD POST	23.000 EA	_____	 _____	_____	 _____

4/18/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 3

Proposal ID: 022881.00

Project(s): 022881.00, 022883.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	609.31 CURB TYPE 3	7,545.000 LF	_____	_____	_____	_____
0140	615.07 LOAM	825.000 CY	_____	_____	_____	_____
0150	618.13 SEEDING METHOD NUMBER 1	74.000 UN	_____	_____	_____	_____
0160	619.12 MULCH	74.000 UN	_____	_____	_____	_____
0170	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	37,300.000 LF	_____	_____	_____	_____
0180	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	720.000 SF	_____	_____	_____	_____
0190	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	111,900.000 LF	_____	_____	_____	_____
0200	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR	_____	_____	_____	_____
0210	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0220	631.13 BULLDOZER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0230	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____

4/18/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 022881.00

Project(s): 022881.00, 022883.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____
0250	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0260	652.33 DRUM	50.000 EA	_____	_____	_____	_____
0270	652.34 CONE	100.000 EA	_____	_____	_____	_____
0280	652.35 CONSTRUCTION SIGNS	496.000 SF	_____	_____	_____	_____
0290	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000 CD	_____	_____	_____	_____
0300	652.38 FLAGGER	1,200.000 HR	_____	_____	_____	_____
0310	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0320	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	66.000 SY	_____	_____	_____	_____
0330	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____