



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Paul R. LePage  
GOVERNOR

David Bernhardt  
COMMISSIONER

February 9, 2018  
Subject: Catch Basin Improvements  
& Culvert Replacement  
State WIN: 022935.00 & 024232.00  
Location: **Rangeley & Carthage**  
**Amendment No. 1**

Dear Sir/Ms.:

The following questions have been received:

**Question:** How far below grade are the existing culverts buried?

**Response:** Approximately 36".

**Question:** Do the guard rail post have to be removed and reset or just the guard rails?

**Response:** To be determined in the field.

**Question:** What is the length of the guard rails sections?

**Response:** The only section of guardrail to be removed and reset is adjacent to the section of 15' metal pipe that is to be removed and relayed. It is anticipated that a 50' section of guardrail (four beams) will need to be removed, but this quantity may be adjusted by the Resident in the field.

**Question:** Can the asphalt be hand laid and plate wacked?

**Response:** The asphalt may be placed by hand, but shall be compacted with a minimum 3-4 ton drum roller.

**Question:** Who is responsible for providing the new culverts?

**Response:** The 2 replacement Culverts are Contractor supplied.



PRINTED ON RECYCLED PAPER

**Question:** Do either of the culverts cross across the road?

**Response:** Yes, both replacement culverts cross the road.

Consider these changes and information prior to submitting your bid on **February 14, 2018**.

Sincerely,



George M. A. Macdougall P.E.  
Contracts & Specifications Engineer