



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

December 11, 2023
Subject: Slope Stabilization
State WIN: 023020.00
Location: **Tremont**
Amendment No. 3

Dear Sir/Ms.:

Make the following changes to the Bid Book:

In the Bid Book:

Remove pages 17 to 20 titled Proposal Schedule of items dated 11/2/2023 and **Replace** with the attached Proposal Schedule of items dated 11/13/2023 totaling four page

The following questions have been received:

Question: Can you please clarify if the excavation of the existing riprap is incidental? The earthwork summary within the drawings specifies the quantity of anticipated riprap excavation, but the quantity for the common excavation pay item appears to be only for the roadway area excavation.

Response: Riprap excavation is shown on the Earthwork Summary to quantify the amount of surplus material on the project. Per Standard Specification 610.06, excavation for riprap is incidental to the pay item.

Question: IN a previous RFI Response the department stated that existing Heavy Rip Rap may be reused. However the department did not state whether the re-handling and reuse of the existing Heavy Rip Rap would be paid under the Heavy Rip Rap item; or if it would be considered a common excavation or common borrow item. Please advise if reused Heavy Rip Rap will be paid under that item; and if so; what types of lengths should the contractor go to regarding separating the unsuitable material surrounding the existing rip-rap. Will it be up to the department or the contractor whether existing rip-rap is reused?

Response: Please see Standard Specification 104.3.13. The removal outside of the incidental excavation limits will be paid under common excavation. If the contractor elects to reuse acceptable material, it will be paid under the appropriate pay item – in this case Heavy Riprap. It is the contractor's choice as to what efforts they put into reusing existing material

Consider these changes and information prior to submitting your bid on **December 13, 2023.**

Sincerely,

A handwritten signature in blue ink, reading "George Macdougall". The signature is written in a cursive, flowing style.

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

11/13/2023

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 4

Proposal ID: 023020.00

Project(s): 023020.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	5.000 EA	_____	_____	_____	_____
0020	201.24 REMOVING STUMP	5.000 EA	_____	_____	_____	_____
0030	202.202 REMOVING PAVEMENT SURFACE	100.000 SY	_____	_____	_____	_____
0040	203.20 COMMON EXCAVATION	370.000 CY	_____	_____	_____	_____
0050	203.2318 DISPOSAL OF SPECIAL WASTE	900.000 T	_____	_____	_____	_____
0060	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	390.000 CY	_____	_____	_____	_____
0070	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	100.000 T	_____	_____	_____	_____
0080	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	2.000 T	_____	_____	_____	_____
0090	403.211 HOT MIX ASPHALT (SHIMMING)	25.000 T	_____	_____	_____	_____
0100	409.15 BITUMINOUS TACK COAT - APPLIED	35.000 G	_____	_____	_____	_____
0110	603.159 12 INCH CULVERT PIPE OPTION III	8.000 LF	_____	_____	_____	_____
0120	603.219 36 INCH CULVERT PIPE OPTION III	12.000 LF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 4

Proposal ID: 023020.00

Project(s): 023020.00

SECTION: 1

INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	1.000 EA	_____	 _____	_____	 _____
0140	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	581.250 LF	_____	 _____	_____	 _____
0150	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	50.000 LF	_____	 _____	_____	 _____
0160	606.1306 31" W-BM GR, MID-WAY SPLICE TANGENT TERMINAL	4.000 EA	_____	 _____	_____	 _____
0170	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	_____	 _____	_____	 _____
0180	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	12.000 EA	_____	 _____	_____	 _____
0190	610.16 HEAVY RIPRAP	2,070.000 CY	_____	 _____	_____	 _____
0200	615.07 LOAM	35.000 CY	_____	 _____	_____	 _____
0210	618.143 SPECIAL SEED MIX: A	5.000 UN	_____	 _____	_____	 _____
0220	618.146 HGM BIOTIC SOIL HYDROMULCH MEDIA	5.000 UN	_____	 _____	_____	 _____
0230	620.58 EROSION CONTROL GEOTEXTILE	1,555.000 SY	_____	 _____	_____	 _____

11/13/2023

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 4

Proposal ID: 023020.00

Project(s): 023020.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	800.000 LF	_____	_____	_____	_____
0250	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	_____	_____	_____
0260	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0270	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0280	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0290	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0300	652.33 DRUM	20.000 EA	_____	_____	_____	_____
0310	652.34 CONE	40.000 EA	_____	_____	_____	_____
0320	652.35 CONSTRUCTION SIGNS	320.000 SF	_____	_____	_____	_____
0330	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	60.000 CD	_____	_____	_____	_____
0340	652.38 FLAGGER	1,500.000 HR	_____	_____	_____	_____
0350	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023020.00

Project(s): 023020.00

SECTION: 1

INITIAL GROUP

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	659.10 MOBILIZATION	LUMP SUM		LUMP SUM		
		Section: 1	Total:			
			Total Bid:			