



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

April 11, 2019
Subject: Bridge Wearing Surface
Replacement Projects
State WINs: 023048.00 & 023631.00
Location: **Kingfield & New Portland**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 16 thru 21, Proposal Schedule of Items, 6 pages, dated 3/22/2019 and **REPLACE** with the attached, revised Proposal Schedule of Items, 6 pages, dated 4/9/2019.

ADD the attached SPECIAL PROVISION - SECTION 606 – GUARDRAIL, 1 page, dated April 9, 2019.

REMOVE page 56, SPECIAL PROVISION, SECTION 104 - GENERAL RIGHTS&RESPONSIBILITIES - (Bridge Closure Notification), dated March 19, 2019 for New Portland, New Great Works Bridge WIN 023631.00.

In the plan set:

REMOVE SHEET NUMBER 2 OF 12, ESTIMATED QUANTITIES & GENERAL CONSTRUCTION NOTES, and **REPLACE** with the attached SHEET NUMBER 2A OF 12, ESTIMATED QUANTITIES & GENERAL CONSTRUCTION NOTES.

The following question has been received:

Question: In the plans it calls for Remove & Reset Bridge Transitions and Remove, Modify and Reset Guardrail. There are no item numbers or quantities for these in the Schedule of Items.

Response: The following items have been deleted from the Contract:

606.1722 Bridge Transition-Type 2
606.23 Guardrail Type 3c-Single rail


The following items have been added to the Contract:

606.1726 Bridge Transition – Remove and Reset
606.365 Guardrail, Remove, Modify, and Reset, Type 3b to 3c

Please refer to the revised Proposal Schedule of Items and the revised sheet 2A.

Consider these changes and information prior to submitting your bid on **April 17, 2019**.

Sincerely,

A handwritten signature in blue ink, reading "George Macdougall". The signature is fluid and cursive, with the first name "George" and last name "Macdougall" clearly legible.

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

4/9/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 6

Proposal ID: 023048.00

Project(s): 023048.00, 023631.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.20 REMOVING BITUMINOUS CONCRETE PAVEMENT	315.000 SY	_____	 _____	_____	 _____
0020	202.202 REMOVING PAVEMENT SURFACE	1,985.000 SY	_____	 _____	_____	 _____
0030	202.30 REMOVING EXISTING CONCRETE WEARING SURFACE	LUMP SUM	LUMP SUM		_____	 _____
0040	203.20 COMMON EXCAVATION	210.000 CY	_____	 _____	_____	 _____
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	220.000 CY	_____	 _____	_____	 _____
0060	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	233.000 T	_____	 _____	_____	 _____
0070	403.213 HOT MIX ASPHALT 12.5 MM BASE	52.000 T	_____	 _____	_____	 _____
0080	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	200.000 T	_____	 _____	_____	 _____
0090	409.15 BITUMINOUS TACK COAT - APPLIED	196.000 G	_____	 _____	_____	 _____
0100	502.75 PLUGGING EXISTING BRIDGE DRAINS	4.000 EA	_____	 _____	_____	 _____
0110	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP SUM		_____	 _____

4/9/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 6

Proposal ID: 023048.00

Project(s): 023048.00, 023631.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM		LUMP SUM		
0130	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	360.000 SF				
0140	518.51 REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL < 8 IN.	225.000 SF				
0150	518.52 REPAIR OF UPWARD FACING SURFACES >= 8 IN.	6.000 CY				
0160	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	310.000 SF				
0170	518.70 REPAIR OF OVERHEAD SURFACES < 8 IN.	60.000 SF				
0180	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	52.000 LF				
0190	520.233 EXPANSION DEVICE - SILICONE COATED PRECOMPRESSED FOAM	150.000 LF				
0200	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM		LUMP SUM		
0210	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				

4/9/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 6

Proposal ID: 023048.00

Project(s): 023048.00, 023631.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	606.1726 BRIDGE TRANSITION - REMOVE AND RESET	4.000 EA	_____	_____	_____	_____
0230	606.365 GUARDRAIL REMOVE, MODIFY, AND RESET TYPE 3B TO 3C	7.000 LF	_____	_____	_____	_____
0240	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0250	606.79 GUARDRAIL 350 FLARED TERMINAL	4.000 EA	_____	_____	_____	_____
0260	610.08 PLAIN RIPRAP	23.000 CY	_____	_____	_____	_____
0270	613.319 EROSION CONTROL BLANKET	54.000 SY	_____	_____	_____	_____
0280	615.07 LOAM	10.000 CY	_____	_____	_____	_____
0290	618.14 SEEDING METHOD NUMBER 2	1.000 UN	_____	_____	_____	_____
0300	619.12 MULCH	1.000 UN	_____	_____	_____	_____
0310	619.14 EROSION CONTROL MIX	19.000 CY	_____	_____	_____	_____
0320	620.58 EROSION CONTROL GEOTEXTILE	69.000 SY	_____	_____	_____	_____
0330	627.18 12 " SOLID WHITE PAVEMENT MARKING	450.000 LF	_____	_____	_____	_____

4/9/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 6

Proposal ID: 023048.00

Project(s): 023048.00, 023631.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3,350.000 LF	_____	_____	_____	_____
0350	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	150.000 SF	_____	_____	_____	_____
0360	627.77 REMOVING PAVEMENT MARKINGS	1,700.000 SF	_____	_____	_____	_____
0370	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	2,400.000 LF	_____	_____	_____	_____
0380	629.05 HAND LABOR, STRAIGHT TIME	70.000 HR	_____	_____	_____	_____
0390	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0400	631.11 AIR TOOL (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0410	631.111 TRACTOR MOUNTED HYDRAULIC HAMMER	10.000 HR	_____	_____	_____	_____
0420	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	35.000 HR	_____	_____	_____	_____
0430	631.131 SMALL BULLDOZER-GRADER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0440	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____

4/9/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 6

Proposal ID: 023048.00

Project(s): 023048.00, 023631.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0450	631.16 ROLLER, PAVEMENT (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0460	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	35.000 HR	_____	_____	_____	_____
0470	631.21 ROAD BROOM (INCLUDING OPERATORS AND HAULER)	10.000 HR	_____	_____	_____	_____
0480	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0490	643.72 TEMPORARY TRAFFIC SIGNAL KINGFIELD	LUMP SUM	LUMP SUM		_____	_____
0500	643.72 TEMPORARY TRAFFIC SIGNAL NEW PORTLAND	LUMP SUM	LUMP SUM		_____	_____
0510	652.311 TYPE II BARRICADE	10.000 EA	_____	_____	_____	_____
0520	652.312 TYPE III BARRICADE	8.000 EA	_____	_____	_____	_____
0530	652.33 DRUM	125.000 EA	_____	_____	_____	_____
0540	652.34 CONE	100.000 EA	_____	_____	_____	_____
0550	652.343 TEMPORARY MODULAR DELINEATOR CURB	200.000 LF	_____	_____	_____	_____
0560	652.35 CONSTRUCTION SIGNS	1,900.000 SF	_____	_____	_____	_____

4/9/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 6

Proposal ID: 023048.00

Project(s): 023048.00, 023631.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0570	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM		 LUMP SUM		
0580	652.38 FLAGGER	500.000 HR				
0590	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	5.000 EA				
0600	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM		
0610	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM		
Section: 1			Total:			
			Total Bid:			

SPECIAL PROVISION
SECTION 606
GUARDRAIL

Amend Subsection 606.09 by adding the following pay item:

<u>Pay Item</u>	<u>Pay Unit</u>
606.1726 Bridge Transition – Remove and Reset	Each

606.1726	BRIDGE TRANSITION - REMOVE AND RESET	4	EA
606.353	REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8	EA
606.365	GUARDRAIL REMOVE, MODIFY AND RESET, TYPE 3B TO 3C	7	LF

c. If a design change results in changes to estimated quantities for Lump Sum pay items, price adjustments will be made in accordance with Standard Specifications Section 109.7, Equitable Adjustments to Compensation.

1 Revised April 9, 2019
Deleted Item Numbers: 606.1722 and 606.23
Added Item Numbers: 606.1726 and 606.365