



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

February 20, 2025

Subject: Roundabout Construction
State WIN: 023689.00 & 026924.00
Location: Palmyra, Newport &
Pittsfield
Amendment No. 2

Dear Sir/Ms.:

Make the following changes to the roundabout construction Plan Set (023689.00)

Remove sheet five titled ESTIMATED QUANTITIES totaling one page dated 1/16/2025 and
Replace with the attached ESTIMATED QUANTITIES DATED 2/19/2025 totaling one page.

Remove pages 17 – 25, Proposal Schedule of Items, 9 pages, dated 1/22/2025, and
Replace with the attached, revised Proposal Schedule of Items, 9 pages, dated 2/20/2025

The following questions have been received:

Question: Could someone review the bid quantity for Bid Item 203.20 "Common Excavation"?
From reviewing the Earthwork Summary, it appears that the quantity listed on the Bid Form is
the quantity of excess excavated material needing to be disposed of.

Response: The correct value is 10,635 CY. A revised sheet five titled ESTIMATED
QUANTITIES DATED 2/19/2025 is attached.

Question: Is there a written scope of work to be completed in Pittsfield?

Response: The scope of work can be found on the Pittsfield Title Sheet on page 40 of the bid
book.

Consider these changes and information prior to submitting your bid on February 26, 2025.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

ESTIMATED QUANTITIES			
ITEM NO.	DESCRIPTION	QUANTITY	UNIT
202.15	REMOVING EXISTING MANHOLE OR CATCH BASIN	18	EA
203.20	COMMON EXCAVATION	10,635	CY
203.21	ROCK REMOVAL	3	CY
203.25	GRANULAR BORROW	100	CY
304.10	AGGREGATE SUBBASE COURSE - GRAVEL	7,920	CY
403.2081	HOT MIX ASPHALT 12.5mm (POLYMER MODIFIED)	1,390	TON
403.209	HOT MIX ASPHALT, 9.5mm (SW, DRIVES, INCIDENTALS)	890	TON
403.2131	12.5 MM POLYMER MODIFIED HMA BASE	4,150	TON
409.15	BITUMINOUS TACK COAT - APPLIED	1,510	GAL
411.09	UNTREATED AGGREGATE SURFACE COURSE	100	CY
502.342	STR CONCRETE ROADWAY TRUCK APRON	160	CY
603.159	12" OPT. III	167	LF
603.16	15" OPT. I	219	LF
603.169	15" OPT. III	105	LF
603.170	18" OPT. I	144	LF
603.175	18" RCP	362	LF
603.179	18" OPT. III	130	LF
603.195	24" RCP	189	LF
603.199	24" OPT. III	100	LF
603.370	64 S X 43 R PIPE ARCH	88	LF
603.550	CONCRETE PIPE TIES	16	GP
604.161	ALTERING CATCH BASIN	2	EA
604.180	ADJUSTING MH OR CB TO GRADE	5	EA
604.248	CATCH BASIN TYPE F6	5	EA
604.249	CATCH BASIN TYPE F6-C	5	EA
604.262	CATCH BASIN TYPE B5-C	38	EA
604.2621	60" CATCH BASIN TYPE B5-C	3	EA
604.2622	72" CATCH BASIN TYPE B5-C	3	EA
605.09	6 INCH UNDERDRAIN TYPE B	2,011	LF
605.11	12 INCH UNDERDRAIN TYPE C	1,007	LF
605.12	15 INCH UNDERDRAIN TYPE C	297	LF
605.13	18 INCH UNDERDRAIN TYPE C	389	LF
605.15	24 INCH UNDERDRAIN TYPE C	395	LF
606.356	UNDERDRAIN DELINEATOR POST	4	EA
608.26	CURB RAMP DETECTABLE WARNING FIELD	40	SF
609.21	CONCRETE SLIPFORM CURB	8,225	LF
609.214	CONCRETE SLIPFORM CURB - 4' TERMINAL END	8	EA
609.218	CONCRETE SLIPFORM CURB - 8' TERMINAL END	5	EA
609.341	CURB TYPE 5 - TRUCK APRON	535	LF
610.08	PLAIN RIPRAP	25	CY
613.319	EROSION CONTROL BLANKET	135	SY
615.07	LOAM	600	CY
615.081	COMPOST BLANKET	385	CY
618.13	SEEDING METHOD NUMBER 1	47	UNIT
619.12	MULCH	47	UNIT
620.58	EROSION CONTROL GEOTEXTILE	80	SY
621.031	EVERGREEN TR (4'-5') GP A	3	EA
621.037	EVERGREEN TR (5'-6') GP A	3	EA
621.043	EVERGREEN TR (6'-8') GP A	3	EA
621.101	PLUG/ STARTER PLANT	750	EA
621.102	GROUND COVER PLUGS - PEAT POTS 2 1/2 IN.	700	EA
621.395	EVERGREENS (18"-24") GP A	60	EA

ESTIMATED QUANTITIES			
ITEM NO.	DESCRIPTION	QUANTITY	UNIT
CONTINUED			
621.5351	DECID SHRUBS (15"-18") GP A	72	EA
621.54	DECID SHRUBS (18"-24") GP A	72	EA
621.546	DECID SHRUBS (2'-3') GP A	24	EA
621.552	DECID SHRUBS (3'-4') GP A	12	EA
621.708	HERBACEOUS PERENNIALS - CONT. (3") GP A	900	EA
621.71	HERBACEOUS PERENNIALS GP A	200	EA
621.8	ESTABLISHMENT PERIOD	1	LS
626.11	PRECAST CONCRETE JUNCTION BOX	28	EA
626.21	METALLIC CONDUIT	50	LF
626.22	NON-METALLIC CONDUIT	1,360	LF
626.251	NON-METALLIC UNDER PAVEMENT CONDUIT (SCHEDULE 80 OR GREATER RATING)	500	LF
626.35	CONTROLLER CABINET FOUNDATION	1	EA
626.421	24-INCH DIAMETER FOUNDATION	28	LF
626.43	30-INCH DIAMETER FOUNDATION	128	LF
626.501	SPREAD FOOTING FOUNDATION	14	CY
627.18	12" SOLID WHITE PAVEMENT MARKING	450	LF
627.733	4" WHITE OR YELLOW PAINT PWMT MARKING LINE	14,350	LF
627.75	WHITE OR YELLOW PAVEMENT AND CURB MARKING	1,100	SF
627.752	TEMP WHITE OR YELLOW PAVEMENT & CURB MARK	600	SF
627.77	REMOVING PAVEMENT MARKINGS	500	SF
627.780	TEMP. 4" PAINTED PWMT. MARK LINE, WHITE OR YELLOW	30,525	LF
627.94	PREFORMED THERMOPLASTIC PAVEMENT MARKING	200	SF
629.05	HAND LABOR	20	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10	HR
631.17	TRUCK - LARGE (INCLUDING OPERATOR)	10	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	10	HR
634.160	HIGHWAY LIGHTING	1	LS
634.21	CONVENTIONAL LIGHT STANDARD	21	EA
639.18	FIELD OFFICE TYPE A	1	EA
643.62	RECTANGULAR RAPID FLASHING BEACON	4	EA
643.72	TEMPORARY TRAFFIC SIGNAL: MOOSEHEAD TRL AT BANKS RD	1	LS
643.72	TEMPORARY TRAFFIC SIGNAL: MOOSEHEAD TRL AT HIGH ST	1	LS
645.103	DEMOUNT GUIDE SIGN	6	EA
645.106	DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	72	EA
645.108	DEMOUNT POLE	34	EA
645.113	REINSTALL GUIDE SIGN	1	EA
645.118	REINSTALL POLE	1	EA
645.162	BREAKAWAY DEVICE MULTI POLE	8	EA
645.251	ROADSIDE GUIDE SIGNS, TYPE I	400	SF
645.289	STEEL H-BEAM POLES	2,750	LB
645.291	ROADSIDE GUIDE SIGNS, TYPE II	60	SF
645.292	REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	450	SF
652.330	DRUM	200	EA
652.340	CONE	200	EA
652.35	CONSTRUCTION SIGNS	1500	SF
652.36	MAINTENANCE OF TRAFFIC CONTROL DEVICES	400	CD
652.38	FLAGGER	10,000	HR
652.41	PORTABLE CHANGEABLE MESSAGE SIGN	4	EA
656.75	TEMP. SOIL EROSION AND WATER POLLUTION CONTROL PLAN	1	LS
658.2	ACRYLIC LATEX COLOR FINISH, GREEN	3,275	SY
659.10	MOBILIZATION	1	LS

EARTHWORK SUMMARY	
COMMON EXCAVATION FOR ESTIMATE	
COMMON EXCAVATION (FROM MODEL OR PLANS)	10,132.87 CY
GRUBBING IN FILL	272.43 CY
LOAM SALVAGE IN FILL	0 CY
UNDERCUT	0 CY
MUCK EXCAVATION	0 CY
PEAT EXCAVATION	0 CY
CULVERT INLET AND OUTLET DITCHES	0 CY
PAVEMENT SALVAGE IN FILL	227.87 CY
TOTAL COMMON EXCAVATION	10,633.17 CY
FILL FOR BORROW CALCULATIONS	
COMMON FILL (FROM MODEL OR PLANS)	965.64 CY
GRUBBING IN FILL	272.43 CY
LOAM SALVAGE IN FILL	0 CY
UNDERCUT	0 CY
MUCK EXCAVATION	0 CY
PEAT EXCAVATION	0 CY
PAVEMENT SALVAGE IN FILL	227.87 CY
RECYCLED PAVEMENT REMOVAL IN FILL	0 CY
TOTAL FILL	1,465.94 CY
ROCK EXCAVATION FOR ESTIMATE	
ROCK EXCAVATION (FROM CROSS SECTIONS)	0 CY
ROCK EXCAVATION (BOULDERS)	3 CY
TOTAL ROCK EXCAVATION	3 CY
AVAILABLE COMMON EXCAVATION FOR BORROW CALCULATIONS	
ALL DEDUCTIONS:	
GRUBBING IN CUT	0 CY
GRUBBING IN FILL	272.43 CY
LOAM SALVAGE IN CUT	0 CY
LOAM SALVAGE IN FILL	0 CY
UNDERCUT	0 CY
MUCK EXCAVATION	0 CY
PEAT EXCAVATION	0 CY
PAVEMENT SALVAGE (CUT & FILL)	3,162.26 CY
TOTAL DEDUCTIONS	3,434.69 CY
TOTAL AVAILABLE COMMON EXCAVATION (-) TOTAL DEDUCTIONS	7,198.48 CY
TOTAL AVAILABLE STRUCTURAL EXCAVATION (UNDERDRAIN ONLY)	772.41 CY
RIPRAP EXCAVATION	22.9 CY
TOTAL AVAILABLE NON-ROCK EXCAVATION	7,993.79 CY
COMPUTATION OF WASTE STORAGE & WASTE MATERIAL	
TOTAL AVAILABLE WASTE STORAGE AREA (FROM CROSS SECTIONS)	0 CY
GRUBBING IN CUT	0 CY
GRUBBING IN FILL	272.43 CY
UNDERCUT	0 CY
MUCK EXCAVATION	0 CY
PEAT EXCAVATION	0 CY
TOTAL WASTE MATERIAL	272.43 CY
TOTAL WASTE MATERIAL TO BE UTILIZED*	0 CY
TOTAL WASTE MATERIAL TO BE WASTED	272.43 CY
COMPUTATION FOR SURPLUS MATERIAL OR COMMON BORROW FOR ESTIMATE	
TOTAL AVAILABLE NON-ROCK EXCAVATION	7,993.79 x 0.90 = 7,194.41 CY
TOTAL AVAILABLE ROCK EXCAVATION	3 x 1.30 = 3.9 CY
TOTAL AVAILABLE STRUCTURAL ROCK EXCAVATION	0 x 1.30 = 0 CY
TOTAL WASTE MATERIAL TO BE UTILIZED	0 x 0.90 = 0 CY
TOTAL AVAILABLE EXCAVATION	7,198.31 CY
BORROW NEEDED = TOTAL FILL (-) TOTAL AVAILABLE EXCAVATION	0.00 CY
IF NO BORROW IS NEEDED, SURPLUS MATERIAL = AVAILABLE EXCAVATION (-) TOTAL FILL, (+) TOTAL WASTE MATERIAL TO BE WASTED	6,004.80 CY
SURPLUS MATERIAL	6,005 CY

STATE OF MAINE DEPARTMENT OF TRANSPORTATION	2368900	WIN 23689.00	HIGHWAY PLANS
PALMYRA - NEWPORT RTE 2 \ RTE 7 \ RTE 11 \ RTE 100		ESTIMATED QUANTITIES	
SHEET NUMBER		5	
		OF 154	

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	18.000 EA	_____	 _____	_____	 _____
0020	203.20 COMMON EXCAVATION	10,635.000 CY	_____	 _____	_____	 _____
0030	203.21 ROCK EXCAVATION	3.000 CY	_____	 _____	_____	 _____
0040	203.25 GRANULAR BORROW	100.000 CY	_____	 _____	_____	 _____
0050	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	8,390.000 CY	_____	 _____	_____	 _____
0060	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	1,435.000 T	_____	 _____	_____	 _____
0070	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	890.000 T	_____	 _____	_____	 _____
0080	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	4,250.000 T	_____	 _____	_____	 _____
0090	409.15 BITUMINOUS TACK COAT - APPLIED	1,526.000 G	_____	 _____	_____	 _____
0100	411.09 UNTREATED AGGREGATE SURFACE COURSE	100.000 CY	_____	 _____	_____	 _____
0110	502.342 STRUCTURAL CONCRETE ROADWAY TRUCK APRON	160.000 CY	_____	 _____	_____	 _____
0120	603.159 12 INCH CULVERT PIPE OPTION III	167.000 LF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	603.16 15 INCH CULVERT PIPE OPTION I	219.000 LF	_____	 _____	_____	 _____
0140	603.169 15 INCH CULVERT PIPE OPTION III	105.000 LF	_____	 _____	_____	 _____
0150	603.17 18 INCH CULVERT PIPE OPTION I	144.000 LF	_____	 _____	_____	 _____
0160	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	362.000 LF	_____	 _____	_____	 _____
0170	603.179 18 INCH CULVERT PIPE OPTION III	130.000 LF	_____	 _____	_____	 _____
0180	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	189.000 LF	_____	 _____	_____	 _____
0190	603.199 24 INCH CULVERT PIPE OPTION III	100.000 LF	_____	 _____	_____	 _____
0200	603.37 64 INCH SPAN 43 INCH RISE PIPE ARCH	88.000 LF	_____	 _____	_____	 _____
0210	603.55 CONCRETE PIPE TIES	16.000 GP	_____	 _____	_____	 _____
0220	604.161 ALTERING CATCH BASIN	2.000 EA	_____	 _____	_____	 _____
0230	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	5.000 EA	_____	 _____	_____	 _____
0240	604.248 CATCH BASIN TYPE F6	5.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	604.249 CATCH BASIN TYPE F6-C	5.000 EA	_____	 _____	_____	 _____
0260	604.262 CATCH BASIN TYPE B5-C	38.000 EA	_____	 _____	_____	 _____
0270	604.2621 60 " CATCH BASIN TYPE B5-C	3.000 EA	_____	 _____	_____	 _____
0280	604.2622 72 " CATCH BASIN TYPE B5-C	3.000 EA	_____	 _____	_____	 _____
0290	605.09 6 INCH UNDERDRAIN TYPE B	2,011.000 LF	_____	 _____	_____	 _____
0300	605.11 12 INCH UNDERDRAIN TYPE C	1,007.000 LF	_____	 _____	_____	 _____
0310	605.12 15 INCH UNDERDRAIN TYPE C	297.000 LF	_____	 _____	_____	 _____
0320	605.13 18 INCH UNDERDRAIN TYPE C	389.000 LF	_____	 _____	_____	 _____
0330	605.15 24 INCH UNDERDRAIN TYPE C	395.000 LF	_____	 _____	_____	 _____
0340	606.356 UNDERDRAIN DELINEATOR POST	4.000 EA	_____	 _____	_____	 _____
0350	608.26 CURB RAMP DETECTABLE WARNING FIELD	40.000 SF	_____	 _____	_____	 _____
0360	609.21 CONCRETE SLIPFORM CURB	8,225.000 LF	_____	 _____	_____	 _____
0370	609.214 CONCRETE SLIPFORM CURB - 4' TERMINAL END	8.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0380	609.218 CONCRETE SLIPFORM CURB - 8' TERMINAL END	5.000 EA	_____	 _____	_____	 _____
0390	609.341 CURB TYPE 5 - TRUCK APRON	535.000 LF	_____	 _____	_____	 _____
0400	610.08 PLAIN RIPRAP	25.000 CY	_____	 _____	_____	 _____
0410	613.319 EROSION CONTROL BLANKET	135.000 SY	_____	 _____	_____	 _____
0420	615.07 LOAM	600.000 CY	_____	 _____	_____	 _____
0430	615.081 COMPOST BLANKET	385.000 CY	_____	 _____	_____	 _____
0440	618.13 SEEDING METHOD NUMBER 1	51.000 UN	_____	 _____	_____	 _____
0450	619.12 MULCH	51.000 UN	_____	 _____	_____	 _____
0460	620.58 EROSION CONTROL GEOTEXTILE	80.000 SY	_____	 _____	_____	 _____
0470	621.031 EVERGREEN TREES (4 FOOT - 5 FOOT) GROUP A	3.000 EA	_____	 _____	_____	 _____
0480	621.037 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP A	3.000 EA	_____	 _____	_____	 _____
0490	621.043 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP A	3.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0500	621.101 PLUG/ STARTER PLANT	750.000 EA	_____	 _____	_____	 _____
0510	621.102 GROUNDCOVER PLUGS - PEAT POTS 2 1/2 INCH	700.000 EA	_____	 _____	_____	 _____
0520	621.395 EVERGREENS (18 INCH - 24 INCH) GROUP A	60.000 EA	_____	 _____	_____	 _____
0530	621.5351 DECIDUOUS SHRUBS (15 INCH - 18 INCH) GROUP A	72.000 EA	_____	 _____	_____	 _____
0540	621.54 DECIDUOUS SHRUBS (18 INCH - 24 INCH) GROUP A	72.000 EA	_____	 _____	_____	 _____
0550	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	24.000 EA	_____	 _____	_____	 _____
0560	621.552 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP A	12.000 EA	_____	 _____	_____	 _____
0570	621.708 HERBACEOUS PERENNIALS - CONT. (3") GROUP A	900.000 EA	_____	 _____	_____	 _____
0580	621.71 HERBACEOUS PERENNIALS GROUP A	200.000 EA	_____	 _____	_____	 _____
0590	621.80 ESTABLISHMENT PERIOD	LUMP SUM		 LUMP SUM	_____	 _____
0600	626.11 PRECAST CONCRETE JUNCTION BOX	28.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0610	626.21 METALLIC CONDUIT	50.000 LF	_____	 _____	_____	 _____
0620	626.22 NON-METALLIC CONDUIT	1,360.000 LF	_____	 _____	_____	 _____
0630	626.251 NON-METALLIC UNDER PAVEMENT CONDUIT (SCHEDULE 80 OR GREATER RATING)	500.000 LF	_____	 _____	_____	 _____
0640	626.35 CONTROLLER CABINET FOUNDATION	1.000 EA	_____	 _____	_____	 _____
0650	626.421 24 INCH DIAMETER FOUNDATION	28.000 LF	_____	 _____	_____	 _____
0660	626.43 30 INCH DIAMETER FOUNDATION	128.000 LF	_____	 _____	_____	 _____
0670	626.501 SPREAD FOOTING FOUNDATION	14.000 CY	_____	 _____	_____	 _____
0680	627.18 12 " SOLID WHITE PAVEMENT MARKING	450.000 LF	_____	 _____	_____	 _____
0690	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	14,350.000 LF	_____	 _____	_____	 _____
0700	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1,100.000 SF	_____	 _____	_____	 _____
0710	627.752 TEMPORARY WHITE OR YELLOW PAVEMENT & CURB MARKING	600.000 SF	_____	 _____	_____	 _____
0720	627.77 REMOVING PAVEMENT MARKINGS	500.000 SF	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0730	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	30,525.000 LF	_____	 _____	_____	 _____
0740	627.94 PREFORMED THERMOPLASTIC PAVEMENT MARKING	200.000 SF	_____	 _____	_____	 _____
0750	629.05 HAND LABOR, STRAIGHT TIME	30.000 HR	_____	 _____	_____	 _____
0760	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	30.000 HR	_____	 _____	_____	 _____
0770	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	50.000 HR	_____	 _____	_____	 _____
0780	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0790	634.160 HIGHWAY LIGHTING	LUMP SUM		 LUMP SUM	_____	 _____
0800	634.210 CONVENTIONAL LIGHT STANDARD	21.000 EA	_____	 _____	_____	 _____
0810	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0820	643.62 RECTANGULAR RAPID FLASHING BEACON	4.000 EA	_____	 _____	_____	 _____
0830	643.72 TEMPORARY TRAFFIC SIGNAL MOOSEHEAD TRL AT BANKS RD	LUMP SUM		 LUMP SUM	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0840	643.72 TEMPORARY TRAFFIC SIGNAL MOOSEHEAD TRL AT HIGH ST	LUMP SUM				
0850	645.103 DEMOUNT GUIDE SIGN	6.000 EA				
0860	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	72.000 EA				
0870	645.108 DEMOUNT POLE	34.000 EA				
0880	645.113 REINSTALL GUIDE SIGN	1.000 EA				
0890	645.118 REINSTALL POLE	1.000 EA				
0900	645.162 BREAKAWAY DEVICES MULTI-POLE	8.000 EA				
0910	645.251 ROADSIDE GUIDE SIGNS, TYPE I	400.000 SF				
0920	645.289 STEEL H-BEAM POLES	2,750.000 LB				
0930	645.291 ROADSIDE GUIDE SIGNS TYPE II	60.000 SF				
0940	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	450.000 SF				
0950	652.33 DRUM	210.000 EA				

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023689.00

Project(s): 023689.00, 026924.00

SECTION: 1 23689 ESTIMATE

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0960	652.34 CONE	225.000 EA	_____	 _____	_____	 _____
0970	652.35 CONSTRUCTION SIGNS	1,705.000 SF	_____	 _____	_____	 _____
0980	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	410.000 CD	_____	 _____	_____	 _____
0990	652.38 FLAGGER	10,300.000 HR	_____	 _____	_____	 _____
1000	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	 _____	_____	 _____
1010	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		 LUMP SUM	_____	 _____
1020	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	3,275.000 SY	_____	 _____	_____	 _____
1030	659.10 MOBILIZATION	LUMP SUM		 LUMP SUM	_____	 _____
Section: 1			Total:		_____	 _____
			Total Bid:		_____	 _____