



STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 16 STATE HOUSE STATION
 AUGUSTA, MAINE 04333-0016

Paul R. LePage
 GOVERNOR

David Bernhardt
 COMMISSIONER

November 15, 2018
 Subject: Culvert Replacements &
 Ditching
 State WIN: 023972.00
 Location: **Waldoboro & Friendship
 Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 13-15, "PROPOSAL SCHEDULE OF ITEMS", 3 pages, dated 10/26/2018, and **REPLACE** with the attached, revised "PROPOSAL SCHEDULE OF ITEMS", 3 pages, dated 11/15/2018.

On page 34, in "CONSTRUCTION NOTES", **DELETE** the Item 603.1790 18 INCH CULVERT PIPE OPTION III – PIPE 5. Make this change in pen and ink.

On page 34, in "CONSTRUCTION NOTES", **CHANGE** Item 603.1790 18 INCH CULVERT PIPE OPTION III – PIPE 5 to read as follows:

"ITEM 603.1690 15 INCH CULVERT PIPE OPTION III - PIPE 6

Located in Friendship at GPS coordinates N 44.00227, W -69.34175

Existing: 15" x 32' CMP Centerline Elevation = 100.00

Proposed: 15" x 36' Option III HDPE PIPE IS NOT ALLOWED

| | |
|---|--|
| East Side Existing | West Side Existing |
| Inlet 14' East of Centerline at Elev. 97.92 | Outlet 18' West of Centerline at Elev.96.99 |
| East Side Proposed | West Side Proposed |
| Inlet 16' East of Centerline at Elev. 97.00 | Outlet 20' West of Centerline at Elev. 96.00 |

- Ditching: Clean and realign existing ditch on Inlet and Outlet as directed and no more than 25' in either direction."

Make this change in pen and ink.



PRINTED ON RECYCLED PAPER

The following questions have been received:

Question: On the proposal schedule of items, proposal line numbers 0070 & 0080 (pipes 5 & 6 respectively), the items are listed as 18" culvert pipes option III. The headers for these two items on page 34 also state 18" pipe but in the notes under each item it has pipes 5 & 6 listed as having the proposed new pipes being 15" option III in the notes. Please clarify

Response: Pipe 6 is 15". See above changes.

Question: It appears as though pipe 5 may have been recently replaced. The GPS coordinates listed bring you to a new culvert. Is this pipe (pipe 5) still part of the bid?

Response: Pipe 5 has been deleted. See above changes.

Consider these changes and information prior to submitting your bid on **November 21, 2018**.

Sincerely,

A handwritten signature in black ink, appearing to read "George M. A. Macdougall" followed by the initials "GMA".

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

11/15/2018

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 023972.00

Project(s): 023972.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

| Proposal Line Number | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
| | | | Dollars | Cents | Dollars | Cents |
| 0010 | 211.30 DITCH EXCAVATION | 27,000.000 LF | _____ | _____ | _____ | _____ |
| 0020 | 304.16 AGGREGATE BASE COURSE - TYPE C | 200.000 CY | _____ | _____ | _____ | _____ |
| 0030 | 603.16 15 INCH CULVERT PIPE OPTION I | 840.000 LF | _____ | _____ | _____ | _____ |
| 0040 | 603.17 18 INCH CULVERT PIPE OPTION I | 360.000 LF | _____ | _____ | _____ | _____ |
| 0050 | 603.1790 18 INCH CULVERT PIPE OPTION III - PIPE 2 | 1.000 EA | _____ | _____ | _____ | _____ |
| 0060 | 603.1790 18 INCH CULVERT PIPE OPTION III - PIPE 3 | 1.000 EA | _____ | _____ | _____ | _____ |
| 0080 | 603.1690 15 INCH CULVERT PIPE OPTION III - PIPE 6 | 1.000 EA | _____ | _____ | _____ | _____ |
| 0090 | 603.21 36 INCH CULVERT PIPE OPTION I | 40.000 LF | _____ | _____ | _____ | _____ |
| 0100 | 603.2190 36 INCH CULVERT PIPE OPTION III - PIPE 1 | 1.000 EA | _____ | _____ | _____ | _____ |
| 0110 | 603.55 CONCRETE PIPE TIES | 3.000 GP | _____ | _____ | _____ | _____ |
| 0120 | 603.7424 REMOVE & RELAY 24 INCH CONCRETE PIPE - PIPE 4 | 12.000 LF | _____ | _____ | _____ | _____ |
| 0130 | 610.08 PLAIN RIPRAP | 100.000 CY | _____ | _____ | _____ | _____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 023972.00

Project(s): 023972.00

SECTION: 1 PROJECT ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

| Proposal Line Number | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|--|--------------------------------|---------------|--------------|------------|-----------|
| | | | Dollars | Cents | Dollars | Cents |
| 0140 | 610.18 STONE DITCH PROTECTION | 575.000 CY | _____ | _____ | _____ | _____ |
| 0150 | 613.319 EROSION CONTROL BLANKET | 11,750.000 SY | _____ | _____ | _____ | _____ |
| 0160 | 618.14 SEEDING METHOD NUMBER 2 | 240.000 UN | _____ | _____ | _____ | _____ |
| 0170 | 619.12 MULCH | 240.000 UN | _____ | _____ | _____ | _____ |
| 0180 | 629.05 HAND LABOR, STRAIGHT TIME | 75.000 HR | _____ | _____ | _____ | _____ |
| 0190 | 631.111 TRACTOR MOUNTED HYDRAULIC HAMMER | 50.000 HR | _____ | _____ | _____ | _____ |
| 0200 | 631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR) | 50.000 HR | _____ | _____ | _____ | _____ |
| 0210 | 631.172 TRUCK - LARGE (INCLUDING OPERATOR) | 100.000 HR | _____ | _____ | _____ | _____ |
| 0220 | 652.39 WORK ZONE TRAFFIC CONTROL | LUMP SUM | | LUMP SUM | _____ | _____ |
| 0230 | 656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL | LUMP SUM | | LUMP SUM | _____ | _____ |
| 0240 | 659.10 MOBILIZATION | LUMP SUM | | LUMP SUM | _____ | _____ |
| Section: 1 | | | Total: | | _____ | _____ |

Total Bid: _____!