



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Janet T. Mills  
GOVERNOR

Bruce A. Van Note  
COMMISSIONER

February 11, 2021  
Subject: Pavement Milling, HMA Overlay  
With Drainage & Safety Improvements  
State WINs: 023977.00, 024581.00 &  
024583.00  
Location: **Biddeford & Saco**  
**Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

**ADD** the attached "Construction Notes, Saco - 24581.00 – North Street – January 26, 2021", 3 pages.

The following question has been received:

**Question:** It appears that the constructions notes for WIN 024581.00-North Street, have been left out of the spec's. Please supply the notes for this WIN as soon as possible.

**Response:** See above changes.

Consider these changes and information prior to submitting your bid on **March 3, 2021**.

Sincerely,

A handwritten signature in blue ink that reads "George Macdougall".

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

**CONSTRUCTION NOTES**

**202.202 REMOVING PAVEMENT SURFACE**

<u>Station</u>	<u>To</u>	<u>Station</u>	<u>Side</u>
10+00		10+60	Full Width
10+60		19+70	Full Width

**202.203 PAVEMENT BUTT JOINTS**

<u>Description</u>	<u>Qty</u>
Paved Drives	12
Commercial Drives	3
Side Roads	1
Project End	1

**403.211 HOT MIX ASPHALT(SHIMMING)**

<u>Station</u>	<u>To</u>	<u>Station</u>	<u>Side</u>
10+00		19+70	Full Width
19+70		29+00	Mainline Only

**604.167 CHANGE CATCH BASIN GRATE TO CASCADE**

<u>Station</u>	<u>Side</u>	<u>Comment</u>
15+14	RT	Catch Basin
19+42	LT	Catch Basin

Additional and/or undetermined catch basins locations to be determined by Resident.

**608.26 CURB RAMP DETECTABLE WARNING FIELD**

<u>Station</u>	<u>Side</u>	<u>Comment</u>
14+25	LT	Garfield Street
14+95	LT	Garfield Street

Additional and/or undetermined curb ramp detectable warning field locations to be determined by Resident.

**CONSTRUCTION NOTES**

**627.733 4" WHITE OR YELLOW PAVEMENT MARKING LINE**

Final striping will not commence until 10 days have elapsed from the completion of surface pavement and must be completed within 20 days of the completion of surface pavement. Unless otherwise directed, failure to comply will result in a Traffic Control Violation.

Once Construction is Complete, Maintenance of Traffic Control Devices (652.36) will not be paid while waiting to final stripe.

Once Construction is Complete, Liquidated Damages will not be charged while waiting to final stripe.

**627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING**

**Crosswalk:**

<b><u>Station</u></b>	<b><u>Side</u></b>
14+25	LT

**Stop Bar:**

<b><u>Station</u></b>	<b><u>Side</u></b>
10+35	LT

**Arrows**

<b><u>Description</u></b>	<b><u>Qty</u></b>
Turn	6
Straight	8
Combination	0
Only	6

**627.78 TEMPORARY 4" PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW**

Temporary center lines and edge lines shall be painted on all matched pavement within one week.

Multilane sections, truck lanes, and milled surfaces must be striped daily on all matched pavement layers.

Temporary lines will require one coat on the milled surface and one coat on the shim layer.

**CONSTRUCTION NOTES**

**629.05 HAND LABOR, STRAIGHT TIME**

**631.12 ALL PURPOSE EXCAVATOR, (INCLUDING OPERATOR)**

**631.172 TRUCK LARGE, (INCLUDING OPERATOR)**

Hourly items to be used on ADA locations and as directed by the Resident.

**652.41 PORTABLE CHANGEABLE MESSAGE SIGN.**

North Street to Buxton  
North Street to Portland through Industrial Park Road  
North Street through Industrial Park Road to Biddeford.

**812.162 ADJUST SEWER MANHOLE TO GRADE**

<b><u>Station</u></b>	<b><u>Side</u></b>
12+50	LT
14+53	LT
16+33	RT
17+94	LT
19+59	LT
21+30	LT
23+15	RT
26+00	RT

Additional locations to be determined by Resident.