



Janet Mills
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Bruce A. Van Note
COMMISSIONER

March 8, 2019
Subject: ADA Sidewalk Safety
Improvements
State WIN: 024099.00
Location: **Waterville**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE page 11, Proposal Schedule of Items, 1 page, dated 2/12/2019, and **REPLACE** with the attached, revised Proposal Schedule of Items, 1 page, dated 2/28/2019.

The following questions have been received:

Question: On the Pedestrian Ramp Report, Prospect St, Brook St, Roosevelt St, Kelsey St, Johnson Heights, Oak St and Eustis Parkway, are the detectables supposed to radius detectables or are they straight?

Response: Please see details on pages 4 through 6 of Special Provision 608 Reconstruct Existing and Construct New Pedestrian Ramp to determine if Curb Ramp Detectable Warning Fields are radial or straight.

Question: On Beth Israel Synagogue there is 15' of new granite shown, is this figured as part of the curb ramp detectable quantities or what item should this be bid under?

Response: This work entails removing the existing ramp and constructing new sidewalk. Work will be paid for under Item 609.11 Vertical Curb Type I and 608.45 Construct Sidewalk.

Question: On Hillside Ave. it shows granite curb as well as the detectable. Is this new granite or reset and what pay item should it go under?

Response: Special Provision 608 Reconstruct Existing and Construct New Pedestrian Ramp allows for resetting of existing Curb Type 1 per the requirements specified in the Section 609 of the Standard Specifications and Standard Details. New Type 1 curb will be required if the existing curb does not

meet the requirements specified in the Section 609 of the Standard Specifications and Standard Details. New or reset curb shall be paid under Item 608.461.

Consider these changes and information prior to submitting your bid on **March 13, 2019**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

2/28/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 1

Proposal ID: 024099.00

Project(s): 024099.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	403.210 HOT MIX ASPHALT 9.5 MM	12.000 T	_____	 _____	_____	 _____
0020	608.26 CURB RAMP DETECTABLE WARNING FIELD	370.000 SF	_____	 _____	_____	 _____
0030	608.45 CONSTRUCT SIDEWALK	9.000 SY	_____	 _____	_____	 _____
0040	608.461 RECONSTRUCT PEDESTRIAN RAMP	10.000 EA	_____	 _____	_____	 _____
0050	609.11 VERTICAL CURB TYPE 1	15.000 LF	_____	 _____	_____	 _____
0060	652.33 DRUM	15.000 EA	_____	 _____	_____	 _____
0070	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0080	652.35 CONSTRUCTION SIGNS	350.000 SF	_____	 _____	_____	 _____
0090	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	30.000 CD	_____	 _____	_____	 _____
0100	652.38 FLAGGER	600.000 HR	_____	 _____	_____	 _____
0110	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM	 _____	_____	 _____
0120	659.10 MOBILIZATION	LUMP SUM	LUMP SUM	 _____	_____	 _____

Section: 1

Total:

Total Bid: