



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Janet T. Mills  
GOVERNOR

Bruce A. Van Note  
COMMISSIONER

April 20, 2022  
Subject: Pavement Milling & HMA Overlay  
With Drainage & Safety Improvements  
State WIN: 024131.00  
Location: **Bangor**  
**Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

**REMOVE** pages 17 – 19, Proposal Schedule of Items, 3 pages, dated 3/31/2022 and **REPLACE** with the attached, revised Proposal Schedule of Items, 3 pages, dated 4/19/2022.

The following question has been received:

**Question:** When reviewing this project I notice the bid item ‘627.73 4” Yellow Pavement marking line’ And then double checking on google maps there seems to be a good deal of White edge line with additional lane lines, Is this an error or is only double yellow being put back?

**Response:** Both yellow and white striping will be required. Please see the revised Proposal Schedule of Items, dated 4/19/2022

Consider these changes and information prior to submitting your bid on **April 27, 2022**.

Sincerely,

  
*for* George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

## Maine Department of Transportation

## Proposal Schedule of Items

Proposal ID: 024131.00

Project(s): 024131.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.2023 REMOVING PAVEMENT SURFACE - MEDIUM CUT DRUM	6,370.000 SY	_____	 _____	_____	 _____
0020	202.203 PAVEMENT BUTT JOINTS	460.000 SY	_____	 _____	_____	 _____
0030	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	50.000 T	_____	 _____	_____	 _____
0040	403.2101 9.5 MM POLYMER MODIFIED HMA	1,200.000 T	_____	 _____	_____	 _____
0050	403.211 HOT MIX ASPHALT (SHIMMING)	830.000 T	_____	 _____	_____	 _____
0060	409.15 BITUMINOUS TACK COAT - APPLIED	1,200.000 G	_____	 _____	_____	 _____
0070	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	10.000 CY	_____	 _____	_____	 _____
0080	604.161 ALTERING CATCH BASIN	3.000 EA	_____	 _____	_____	 _____
0090	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	2.000 EA	_____	 _____	_____	 _____
0100	606.356 UNDERDRAIN DELINEATOR POST	3.000 EA	_____	 _____	_____	 _____
0110	609.21 CONCRETE SLIPFORM CURB	950.000 LF	_____	 _____	_____	 _____
0120	613.319 EROSION CONTROL BLANKET	170.000 SY	_____	 _____	_____	 _____

## Maine Department of Transportation

## Proposal Schedule of Items

Proposal ID: 024131.00

Project(s): 024131.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	618.14 SEEDING METHOD NUMBER 2	11.000 UN	_____	 _____	_____	 _____
0140	619.12 MULCH	11.000 UN	_____	 _____	_____	 _____
0150	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	12,000.000 LF	_____	 _____	_____	 _____
0160	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	448.000 SF	_____	 _____	_____	 _____
0170	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	12,000.000 LF	_____	 _____	_____	 _____
0180	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0190	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0200	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR	_____	 _____	_____	 _____
0210	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0220	631.28 BRUSH CHIPPER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0230	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024131.00

Project(s): 024131.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	10.000 SF	_____	 _____	_____	 _____
0250	652.33 DRUM	20.000 EA	_____	 _____	_____	 _____
0260	652.34 CONE	50.000 EA	_____	 _____	_____	 _____
0270	652.35 CONSTRUCTION SIGNS	390.000 SF	_____	 _____	_____	 _____
0280	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	24.000 CD	_____	 _____	_____	 _____
0290	652.38 FLAGGER	400.000 HR	_____	 _____	_____	 _____
0300	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	_____	 LUMP SUM	_____	 _____
0310	659.10 MOBILIZATION	LUMP SUM	_____	 LUMP SUM	_____	 _____
<b>Section: 1</b>			<b>Total:</b>		_____	 _____
			<b>Total Bid:</b>		_____	 _____