



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

April 20, 2021
Subject: Pavement Milling, HMA Overlay
with Drainage & Safety Improvements
State WIN: 024161.00
Location: **Nobleboro & Waldoboro**
Amendment No. 1

Dear Sir/Ms.:

The following questions have been received:

Question: The typical section on Sheet 38 indicates removing material to 6" below finished grade. Does the department know how thick the existing pavement is in the turning lane at station 803+25 to 810+50?

Response: Cores were taken at Station 807+00 in the turn lane that show approximately 4 inches of existing pavement.

Question: For item 603.7418 Remove and Relay 18" Concrete Pipe and 603.743 Remove and Relay 30" Concrete Pipe. Based on the quantities in the schedule of items is it the departments intent to dispose of the last section of pipe when in the construction notes it calls out remove and relay second to last section, 8' for these two items?

Response: Yes, when listed as "Second to last section" under the Remove and Relay items, it is the intent of the Department to shorten the length of the pipe by removing and disposing of the last section of pipe.

Consider these changes and information prior to submitting your bid on **April 21, 2021**.

Sincerely,

A handwritten signature in blue ink that reads "George Macdougall".

George M. A. Macdougall P.E.
Contracts & Specifications Engineer