



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

January 13, 2025
Subject: Large Culvert Replacement
State WIN: 024279.00
Location: **Etna**
Amendment No. 2

Dear Sir/Ms.:

In the Bid Book:

REMOVE pages 12 – 14 titled Proposal Schedule of Items dated December 17, 2024, and **REPLACE** with the attached Proposal Schedule of Items dated January 13, 2025.

In the Plan Set:

REMOVE ALL REFERENCES to “Item 603.4073 128” Span by 83” Rise Steel Plate Pipe Arch and **REPLACE** with “Item 509.11 128” span by 83” rise Steel Structural Steel Plate Pipe” throughout the entire Contract Plan Set. Make these changes in Pen and Ink.

The following questions have been received:

Question: On the 128” x 83” pipe arch culvert. This is a factory made squashed pipe arch size. Note on plan states 8 ga min. If that is the case, this structure needs to be steel structural plate and that closest size is 129” x 82” (10’-9” x 6’-10”) and field bolted together at the site. If you want Polymer coated galv corrugated steel factory made pipe arch (like MEDOT usually uses), the min gauge is 10 (0.138”) which would be supplied in 4 ea 23’ lengths and 3 gasketed joints.

Response: As stated in the notes on the plans the plate thickness shall be 8 gauge or thicker. The Schedule of Items has been changed to remove Item 603.4073 128” span by 83” rise Polymer Coated Steel Plate Pipe Arch and replace with Item 509.11 128” span by 83” rise Steel Structural Plate Pipe.

Consider these changes and information prior to submitting your bid on **January 15, 2025**

Sincerely,

A handwritten signature in blue ink, appearing to read "George Macdougall". The signature is fluid and cursive, with the first name "George" and last name "Macdougall" clearly distinguishable.

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

1/13/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 024279.00

Project(s): 024279.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	203.20 COMMON EXCAVATION	510.000 CY	_____	 _____	_____	 _____
0020	203.25 GRANULAR BORROW	300.000 CY	_____	 _____	_____	 _____
0030	203.33 SPECIAL FILL	100.000 CY	_____	 _____	_____	 _____
0040	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	460.000 CY	_____	 _____	_____	 _____
0050	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	60.000 T	_____	 _____	_____	 _____
0060	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	1.000 T	_____	 _____	_____	 _____
0070	403.213 HOT MIX ASPHALT 12.5 MM BASE	120.000 T	_____	 _____	_____	 _____
0080	409.15 BITUMINOUS TACK COAT - APPLIED	50.000 G	_____	 _____	_____	 _____
0090	509.11 STEEL STRUCTURAL PLATE PIPE: 26,404 lbs.	LUMP SUM		LUMP SUM	_____	 _____
0100	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM		LUMP SUM	_____	 _____
0110	511.07 COFFERDAM: UPSTREAM	LUMP SUM		LUMP SUM	_____	 _____
0120	603.16 15 INCH CULVERT PIPE OPTION I	30.000 LF	_____	 _____	_____	 _____

1/13/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 3

Proposal ID: 024279.00

Project(s): 024279.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	606.363 GUARDRAIL REMOVE AND DISPOSE	288.000 LF	_____	_____	_____	_____
0140	610.08 PLAIN RIPRAP	30.000 CY	_____	_____	_____	_____
0150	610.212 STREAMBED ROCK FEATURES	5.000 CY	_____	_____	_____	_____
0160	610.213 VOID FILLED RIPRAP	20.000 CY	_____	_____	_____	_____
0170	613.319 EROSION CONTROL BLANKET	20.000 SY	_____	_____	_____	_____
0180	615.07 LOAM	55.000 CY	_____	_____	_____	_____
0190	618.14 SEEDING METHOD NUMBER 2	9.000 UN	_____	_____	_____	_____
0200	619.12 MULCH	9.000 UN	_____	_____	_____	_____
0210	620.58 EROSION CONTROL GEOTEXTILE	50.000 SY	_____	_____	_____	_____
0220	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	600.000 LF	_____	_____	_____	_____
0230	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	_____	_____	_____
0240	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____

1/13/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 024279.00

Project(s): 024279.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0260	652.312 TYPE III BARRICADE	4.000 EA	_____	_____	_____	_____
0270	652.33 DRUM	30.000 EA	_____	_____	_____	_____
0280	652.34 CONE	30.000 EA	_____	_____	_____	_____
0290	652.35 CONSTRUCTION SIGNS	482.000 SF	_____	_____	_____	_____
0300	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	35.000 CD	_____	_____	_____	_____
0310	652.38 FLAGGER	300.000 HR	_____	_____	_____	_____
0320	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0330	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0340	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____