



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

February 12, 2018
Subject: Guardrail Repair
State WINs: 024302.00 & 024304.00
Location: **Rangeley, Adamstown
Township & Lincoln Plantation
Amendment No. 1**

Dear Sir/Ms.:

The following questions have been received:

Question: The guardrail on this project is being attached to bridges, however, there is no item for a Type II Bridge Transition.

Response: The guardrail does attach to bridges on this project. The first section is to be double nested on each transition and the first 3 posts will need to be placed like a type II.

Question: A Type II Bridge Transition uses a Michigan Shoe and the first 12 1/2' of guardrail is double nested. Will we be using a Michigan shoe and core-drilling the concrete end posts or replacing in kind attaching the guardrail in the recesses in the concrete, reusing the existing anchor bolts?

Response: Michigan shoes will not be needed. The bridges have recesses poured into the bridge ends & anchors are already in place. So, replacement will be in kind.

Consider these changes and information prior to submitting your bid on **February 14, 2018**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer



PRINTED ON RECYCLED PAPER