STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

January 18, 2018
Subject: Slope Stabilization
State WIN: 024408.04
Location: **Carrabasset Valley**
Amendment No. 1

Dear Sir/Ms.:

The following question has been received:

Question: When this project was originally done, half of the road was gone and this was used as a side cut to the bottom. A large excavator was used to construct from the bottom up. The photo of this project shows the repair work just below the road surface. The cross-section plan shows this work 40 feet below the road surface. Do you anticipate this project being done with a large excavator? If any work is done at the toe, it would appear it would have to be done with a crane.

Response: It is anticipated that the contractor would need to use a crane to place the stone fill at the toe of the slope.

Consider these changes and information prior to submitting your bid on **January 24, 2018**.

Sincerely,

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

PRINTED ON RECYCLED PAPER

THE MAINE DEPARTMENT OF TRANSPORTATION IS AN AFFIRMATIVE ACTION - EQUAL OPPORTUNITY EMPLOYER
PHONE: (207) 624-3000 TTY USERS CALL MAINE RELAY 711 FAX: (207) 624-3001