



Janet T. Mills  
GOVERNOR

STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Bruce A. Van Note  
COMMISSIONER

March 12, 2020  
Subject: Pavement Milling &  
Cyclical Pavement Resurfacing with  
Safety Improvements  
State WINs: 024533.00 & 024535.00  
Location: **Carroll Plantation,  
Kossuth Township & Topsfield  
Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

**REMOVE** pages 17 – 18, Proposal Schedule of Items, 2 pages, dated 3/2/2020, and  
**REPLACE** with the attached, revised Proposal Schedule of Items, 2 pages, dated 3/10/2020.

**REMOVE** pages 39 - 41, Construction Notes, 3 pages, dated January 31, 2020, and **REPLACE**  
with the attached, revised Construction Notes, 3 pages, dated March 9, 2020.

The following questions have been received:

**Question:** The Wage Rates given in the General Decision for Equipment Operators seem high for this region. Will these wages be changed to wages more representative of what is paid in the area?

**Response:** The Contractors' bids need to be based on the wage rate decision in the Contract Bid Book. However, the Department is aware of the situation and is working to get the wage rates amended. For this to happen in a timelier manner, Contractors should voice their concerns to Jeff Fisher, National Survey Coordinator, DOL at [fisher.jeff@dol.gov](mailto:fisher.jeff@dol.gov) or by phone at # 202-500-5649. If a new wage rate is available before bid opening, the Department will issue an amendment. If not, the Department will include the revised wage rates by contract modification if they are available during construction. No change to the contract's wage rates can occur except by Amendment or Contract Modification by the Department.

**Question:** The Construction Notes, page 39 address item 403.209 HMA 9.5mm Incidentals. There is not a bid item for 403.209 in the schedule of items. Please Advise.

**Response:** See above changes.

Consider these changes and information prior to submitting your bid on **March 25, 2020**.

Sincerely,

A handwritten signature in black ink, appearing to read "Geo M A Macdougall". The signature is fluid and cursive, with the first name "Geo" being the most prominent.

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

3/10/2020

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 2

Proposal ID: 024533.00

Project(s): 024533.00, 024535.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	200.000 SY	_____	 _____	_____	 _____
0020	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	10.000 T	_____	 _____	_____	 _____
0030	409.15 BITUMINOUS TACK COAT - APPLIED	7,460.000 G	_____	 _____	_____	 _____
0040	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	150.000 CY	_____	 _____	_____	 _____
0050	461.210 9.5 MM HMA - CYCLICAL PAVEMENT RESURFACING	5,120.000 T	_____	 _____	_____	 _____
0060	461.216 HOT MIX ASPHALT (SHIMMING)	3,740.000 T	_____	 _____	_____	 _____
0070	608.26 CURB RAMP DETECTABLE WARNING FIELD	20.000 SF	_____	 _____	_____	 _____
0080	608.46 REGRADE SIDEWALK	24.000 SY	_____	 _____	_____	 _____
0090	609.31 CURB TYPE 3	50.000 LF	_____	 _____	_____	 _____
0100	615.10 DIRTY BORROW	140.000 CY	_____	 _____	_____	 _____
0110	618.14 SEEDING METHOD NUMBER 2	59.000 UN	_____	 _____	_____	 _____
0120	619.12 MULCH	59.000 UN	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024533.00

Project(s): 024533.00, 024535.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	150.000 SF	_____	 _____	_____	 _____
0140	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	157,120.000 LF	_____	 _____	_____	 _____
0150	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	45.000 HR	_____	 _____	_____	 _____
0160	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	90.000 HR	_____	 _____	_____	 _____
0170	652.34 CONE	150.000 EA	_____	 _____	_____	 _____
0180	652.35 CONSTRUCTION SIGNS	870.000 SF	_____	 _____	_____	 _____
0190	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	71.000 CD	_____	 _____	_____	 _____
0200	652.38 FLAGGER	920.000 HR	_____	 _____	_____	 _____
0210	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM	_____	 _____
0220	659.10 MOBILIZATION	LUMP SUM		LUMP SUM	_____	 _____
<b>Section: 1</b>			<b>Total:</b>		_____	 _____
			<b>Total Bid:</b>		_____	 _____

## Construction Notes

### 202.202 Removing Pavement Surface

<u>Station</u>	<u>to</u>	<u>Station</u>	<u>Width</u>	<u>Side</u>	<u>Description</u>
10+00	-	10+25	28'	RT/LT	Begin Mainline

Notes:

- All generated millings are to become the property of the Contractor.
- These stations are approximate. Actual locations will be located in the field, as directed by the Resident.

### 403.209 Hot Mix Asphalt 9.5 mm – Incidentals

- Item to be used to pave the ADA landing and sidewalk at a depth of 2” on Winn Road, Route 168 and Lee Road, Route 6 intersection.
- Lat 45.36011, Long -68.286238, Actual locations will be determined in the field by the Resident.

### 461.216 Hot Mix Asphalt – Spot Shim Treatment

<u>Side</u>	<u>Station</u>	<u>Station</u>
RT	16+00	18+00
RT	23+50	25+50
RT	196+00	198+00
RT	300+00	307+00
RT	330+00	336+00
LT	331+00	336+00

- These stations are approximate. Actual locations will be located in the field, as directed by the Resident. Approximate 155 Tons.

### 411.10 Untreated Aggregate Surface Course - Truck Measure

- Item will be used in driveways and entrances, as directed by the Resident.
- Material meeting the gradation requirements of item #204.20.

### 608.26 Curb Ramp Detectable Warning Field

- Item to be installed at the ADA landing on Winn Road, Route 168 and Lee Road, Route 6 intersection.
- Lat 45.36011, Long -68.286238, Actual locations will be determined in the field by the Resident.
- 2 locations, each location will be 2’W and the length will be determined in the field by the Resident

## **Construction Notes**

### **608.46 Regrade Sidewalk**

- Item to be used to regrade the ADA landing and sidewalk on Winn Road, Route 168 and Lee Road, Route 6 intersection.
- Lat 45.36011, Long -68.286238, Actual locations will be determined in the field by the Resident.

### **609.31 Curb Type 3**

- Item to be used to place curb at the ADA landing and sidewalk on Winn Road, Route 168 and Lee Road, Route 6 intersection.
- Lat 45.36011, Long -68.286238, Actual locations will be determined in the field by the Resident.

### **627.75 White or Yellow Pavement & Curb Marking**

- Item to be used for painting the crosswalk at the intersection of Winn Road, Route 168 and Lee Road, Route 6
- Lat 45.36011, Long -68.286238, Actual locations will be determined in the field by the Resident

### **627.78 Temporary 4" Painted Pavement Marking Line, White or Yellow**

- Temporary center lines shall be painted on all matched pavement within one week.
- Temporary edge lines shall be painted on all pavement layers within four weeks.
- All temporary lines shall be painted prior to final striping.
- Multilane sections, truck lanes, and milled surfaces must be striped daily on all matched pavement layers.
- TOMs must be used on all pavement layers until temporary paint is applied.
- TOMs will be removed before final striping.
- TOM removal will be addressed in the Traffic Control Plan.
- Only painted temporary line will be paid under this item. TOMs will be considered incidental to the contract.

## **Construction Notes**

### **629 & 631 Hourly Items**

Primary use of the 631.12 All Purpose Excavator and 631.172 Truck-Large will be for removal of excess material from in-slopes, ditches, and ends of pipes. Actual locations will be located in the field, as directed by the Resident. Cleaning of pavement following rental work will be considered incidental to the rental items and will be done daily to the satisfaction of the Resident.

### **652.35 Construction Signs**

“ROAD WORK NEXT 9 MILES” signs are to be used on each end of the project as part of the approach sign package.