



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

March 29, 2021
Subject: Pavement Milling & HMA
Overlay with Safety Improvements
State WIN: 024579.00
Location: **Westbrook**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

REMOVE pages 17 – 19, Proposal Schedule of Items, 3 pages, dated 3/11/2021, and **REPLACE** with the attached, revised Proposal Schedule of Items, 3 pages, dated 3/18/2021.

REMOVE pages 36 – 38, CONSTRUCTION NOTES, 3 pages, February 19, 2021, and **REPLACE** with the attached, revised CONSTRUCTION NOTES, 3 pages, March 18, 2021.

The following questions have been received:

Question: Please clarify where Item 204.50 and 403.102 are to be used (location and limits)?

Response: Used as directed if gravel is exposed during milling. Undetermined locations.

Question: Item 608.462 "Construct New Ped Ramp" has a quantity of 4 listed in the schedule of values but there are only 2 locations called out in the construction notes. Please clarify which quantity is correct and the locations of the newly constructed ramps.

Response: See above changes.

Consider these changes and information prior to submitting your bid on **April 7, 2021**.

Sincerely,

A handwritten signature in blue ink that reads "George M. A. Macdougall".

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

3/18/2021

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 024579.00

Project(s): 024579.00

SECTION: 1 Highway Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.202 REMOVING PAVEMENT SURFACE	8,100.000 SY	_____	 _____	_____	 _____
0020	202.203 PAVEMENT BUTT JOINTS	240.000 SY	_____	 _____	_____	 _____
0030	204.50 ROAD BASE REPAIR AREAS	70.000 SY	_____	 _____	_____	 _____
0040	403.102 HOT MIX ASPHALT PAVEMENT - SPECIAL AREAS	25.000 T	_____	 _____	_____	 _____
0050	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	50.000 T	_____	 _____	_____	 _____
0060	403.210 HOT MIX ASPHALT 9.5 MM	660.000 T	_____	 _____	_____	 _____
0070	403.211 HOT MIX ASPHALT (SHIMMING)	220.000 T	_____	 _____	_____	 _____
0080	409.15 BITUMINOUS TACK COAT - APPLIED	700.000 G	_____	 _____	_____	 _____
0090	424.22 ASPHALT RUBBER CRACK SEALER TYPE 2, APPLIED	1,100.000 LB	_____	 _____	_____	 _____
0100	608.26 CURB RAMP DETECTABLE WARNING FIELD	96.000 SF	_____	 _____	_____	 _____
0110	608.461 RECONSTRUCT PEDESTRIAN RAMP	1.000 EA	_____	 _____	_____	 _____
0120	608.462 CONSTRUCT NEW PEDESTRIAN RAMP	2.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024579.00

Project(s): 024579.00

SECTION: 1 Highway Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	615.07 LOAM	3.000 CY	_____	 _____	_____	 _____
0140	618.14 SEEDING METHOD NUMBER 2	1.000 UN	_____	 _____	_____	 _____
0150	619.12 MULCH	1.000 UN	_____	 _____	_____	 _____
0160	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	6,700.000 LF	_____	 _____	_____	 _____
0170	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	230.000 SF	_____	 _____	_____	 _____
0180	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	6,700.000 LF	_____	 _____	_____	 _____
0190	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____
0200	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0210	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0220	639.21 FIELD OFFICE TYPE D	1.000 EA	_____	 _____	_____	 _____
0230	652.33 DRUM	10.000 EA	_____	 _____	_____	 _____
0240	652.34 CONE	70.000 EA	_____	 _____	_____	 _____

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 024579.00

Project(s): 024579.00

SECTION: 1 Highway Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	652.35 CONSTRUCTION SIGNS	720.000 SF	_____	 _____	_____	 _____
0260	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	19.000 CD	_____	 _____	_____	 _____
0270	652.38 FLAGGER	600.000 HR	_____	 _____	_____	 _____
0280	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
0290	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____
Section: 1			Total:		_____	 _____

SECTION: 2 City Of Westbrook

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0300	812.162 ADJUSTING SEWER MANHOLE TO GRADE	9.000 EA	_____	 _____	_____	 _____
Section: 2			Total:		_____	 _____
			Total Bid:		_____	 _____

CONSTRUCTION NOTES

202.202 REMOVING PAVEMENT SURFACE

<u>Station</u>	<u>To</u>	<u>Station</u>	<u>Comment</u>	<u>Offset</u>
10+00		33+50	Full Width	
19+80		20+25	Graham Road	22'
26+25		26+75	Lugrin Street	25'

202.203 PAVEMENT BUTT JOINTS

<u>Description</u>	<u>Qty</u>
Paved Drives	24
Commercial Drives	7

403.211 HOT MIX ASPHALT (SHIMMING)

<u>Station</u>	<u>To</u>	<u>Station</u>	<u>Side</u>
10+00		33+50	LT/RT

After milling, spot shim locations to be determined by Resident.

608.26 CURB RAMP DETECTABLE WARNING FIELDS

<u>Station</u>	<u>Side</u>
11+85	LT
12+25	LT
15+43	LT
26+89	RT
33+35	RT
33+50	LT

608.461 RECONSTRUCT PEDESTRIAN RAMP

<u>Station</u>	<u>Side</u>	<u>Ramp Material</u>	<u>Curb</u>
26+89	RT	Asphalt	Bituminous

608.462 CONSTRUCT NEW PEDESTRIAN RAMP

<u>Station</u>	<u>Side</u>	<u>Ramp Material</u>	<u>Curb</u>
33+35	LT	Asphalt	Bituminous
33+50	RT	Asphalt	Bituminous

CONSTRUCTION NOTES

615.07 LOAM

618.14 SEEDING METHOD NUMBER 2

619.12 MULCH

<u>Station</u>	<u>To</u>	<u>Station</u>	<u>Side</u>
15+43		15+53	LT
20+00		20+10	LT
20+15		20+25	RT

Additional locations to be determined by Resident.

627.733 4 INCH WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE

Center lines and edge lines shall be painted on all matched pavement within one week.

Center line TOMs may be utilized until final striping and will be considered incidental to the contract.

Multilane sections and truck lanes must be striped daily on all matched pavement layers.

627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING

Crosswalks

<u>Station</u>	<u>To</u>	<u>Station</u>
15+43		15+43
33+35		33+50

627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW

Temporary center lines and edge lines shall be painted on all matched pavement within one week.

Multilane sections, truck lanes, and milled surfaces must be striped daily on all matched pavement layers.

Temporary lines will require one coat on the milled surface and one coat on the shim layer.

CONSTRUCTION NOTES

812.162 ADJUSTING SEWER MANHOLE TO GRADE

<u>Station</u>	<u>Qty</u>	<u>Side</u>
11+56	1	LT
14+27	1	RT
16+00	1	CL
18+01	1	CL
20+00	1	LT
24+30	1	LT
26+52	1	LT
29+57	1	LT
33+10	1	LT

Additional locations to be determined by Resident.