



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

February 24, 2025
Subject: Puddle Dock Bridge Replacement
State WIN: 025453.00
Location: **Fort Fairfield**
Amendment No. 1

Dear Sir/Ms.:

The following questions have been received:

Question: Please supply available CADD files.

Response: CADD files have been posted to the MaineDOT website.

Question: What are the requirements for the (2) Conventional Light Standard Poles and Luminaries?

Response: Conventional Light Standards shall be 30' tall, round tapered aluminum poles with a minimum wall thickness of 0.188". Conventional Light Standards shall meet the requirements of Standard Specifications Sections 634 and 720. LED Luminaires shall be Autobahn ATB0 P204 R3 4K fixtures, or approved equivalent.

Question: Section 105 Environmental Requirements states 6/1-9/30 water window dates, but the ACOE permit states 7/15-9/30 water window dates. What are the correct water window dates?

Response: 6/1/- 9/30 – this is specified in Section 105 and in the ACOE permit see page 238 of the contract bid book).

Question: What type of reinforcing in the NEXT Beam do we use for the rebar that protrudes up into the CIP Deck? (black, low chromium, etc...)

Response: All reinforcement in the NEXT Beams shall be plain steel (black).

Consider these changes and information prior to submitting your bid on **February 26, 2025**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer