



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

January 21, 2025
Subject: Large Culvert Replacement &
Jewett Bridge Replacement
State WIN: 025513.00 & 026158.00
Location: **Whitefield**
Amendment No. 1

Dear Sir/Ms.:

Make the following changes to the bid documents

Remove Pages Sixteen through twenty titled Proposal Schedule of items dated 12/17/2024 and **Replace** with the attached Proposal Schedule of Items 1/21/2025

The following questions have been received:

Question: Re the proposed 103" x 71" metal pipe
Would RCP (reinforced concrete pipe) of 96" ID be an acceptable alternative.

Response: Due to cover and permitting restraints, the Department will proceed with the Pipe Arch option.

Question: We have gone through the "Bid Items" on the Bid Form in the Contract Specification Book and then tried to breakdown the quantities into the two different projects from the "Estimated Quantities" table on Sheet 2 of each of the projects. Some of the quantities on the Bid Form do not add up to the estimated quantities of their respective items. There is also an estimated quantity (Item 610.213) that isn't shown on the Bid Form. We can provide each specific item that doesn't match if needed.

Response: Please replace the Proposal Schedule of Items dated 12/17/2024 with the revised Proposal Schedule of Items dated – 1/21/2025.

Consider these changes and information prior to submitting your bid on **January 29, 2025**

Sincerely,

A handwritten signature in blue ink, reading "George Macdougall". The signature is fluid and cursive, with the first name "George" and last name "Macdougall" clearly legible.

George M. A. Macdougall P.E.
Contracts & Specifications Engineer

1/21/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 5

Proposal ID: 025513.00

Project(s): 025513.00, 026158.00

SECTION: 1 REGIONAL ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	5.000 EA	_____	_____	_____	_____
0020	201.24 REMOVING STUMP	5.000 EA	_____	_____	_____	_____
0030	202.202 REMOVING PAVEMENT SURFACE	185.000 SY	_____	_____	_____	_____
0040	203.20 COMMON EXCAVATION	937.000 CY	_____	_____	_____	_____
0050	203.2318 DISPOSAL OF SPECIAL WASTE	40.000 T	_____	_____	_____	_____
0060	203.24 COMMON BORROW	50.000 CY	_____	_____	_____	_____
0070	203.25 GRANULAR BORROW	247.000 CY	_____	_____	_____	_____
0080	203.33 SPECIAL FILL	107.000 CY	_____	_____	_____	_____
0090	203.55 CULVERT BEDDING STONE	130.000 CY	_____	_____	_____	_____
0100	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	35.000 CY	_____	_____	_____	_____
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	825.000 CY	_____	_____	_____	_____
0120	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	123.000 T	_____	_____	_____	_____

1/21/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 5

Proposal ID: 025513.00

Project(s): 025513.00, 026158.00

SECTION: 1 REGIONAL ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	5.000 T	_____	 _____	_____	 _____
0140	403.213 HOT MIX ASPHALT 12.5 MM BASE	179.000 T	_____	 _____	_____	 _____
0150	409.15 BITUMINOUS TACK COAT - APPLIED	51.000 G	_____	 _____	_____	 _____
0160	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP SUM	 _____	_____	 _____
0170	509.12 STEEL STRUCTURAL PLATE PIPE ARCH: 103" X 77"	LUMP SUM	LUMP SUM	 _____	_____	 _____
0180	511.07 COFFERDAM: DOWNSTREAM - WIN 025513.00	LUMP SUM	LUMP SUM	 _____	_____	 _____
0190	511.07 COFFERDAM: DOWNSTREAM - WIN 026158.00	LUMP SUM	LUMP SUM	 _____	_____	 _____
0200	511.07 COFFERDAM: UPSTREAM - WIN 025513.00	LUMP SUM	LUMP SUM	 _____	_____	 _____
0210	511.07 COFFERDAM: UPSTREAM - WIN 026158.00	LUMP SUM	LUMP SUM	 _____	_____	 _____
0220	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP SUM	 _____	_____	 _____
0230	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP SUM	 _____	_____	 _____

1/21/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 5

Proposal ID: 025513.00

Project(s): 025513.00, 026158.00

SECTION: 1 REGIONAL ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	534.71 PRECAST CONCRETE BOX CULVERT	LUMP SUM				
0250	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	147.000 LF				
0260	606.1304 31" W-BM GR, MID-WAY SPLICE-OVER 15' RAD	25.000 LF				
0270	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA				
0280	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	1.000 EA				
0290	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA				
0300	606.743 GUARDRAIL - SINGLE RAIL CULVERT MOUNTED	44.000 LF				
0310	610.08 PLAIN RIPRAP	155.000 CY				
0320	610.212 STREAMBED ROCK FEATURES	5.000 CY				
0330	610.213 VOID FILLED RIPRAP	87.000 CY				
0340	613.319 EROSION CONTROL BLANKET	100.000 SY				
0350	615.07 LOAM	85.000 CY				

1/21/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 5

Proposal ID: 025513.00

Project(s): 025513.00, 026158.00

SECTION: 1 REGIONAL ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	618.14 SEEDING METHOD NUMBER 2	10.000 UN	_____	_____	_____	_____
0370	619.12 MULCH	10.000 UN	_____	_____	_____	_____
0380	619.14 EROSION CONTROL MIX	70.000 CY	_____	_____	_____	_____
0390	620.54 STABILIZATION/REINFORCEMENT GEOTEXTILE	320.000 SY	_____	_____	_____	_____
0400	620.58 EROSION CONTROL GEOTEXTILE	220.000 SY	_____	_____	_____	_____
0410	620.65 REINFORCEMENT GEOGRID	105.000 SY	_____	_____	_____	_____
0420	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,350.000 LF	_____	_____	_____	_____
0430	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR	_____	_____	_____	_____
0440	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	30.000 HR	_____	_____	_____	_____
0450	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	_____	_____	_____
0460	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	_____	_____	_____
0470	652.312 TYPE III BARRICADE	8.000 EA	_____	_____	_____	_____

1/21/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 5

Proposal ID: 025513.00

Project(s): 025513.00, 026158.00

SECTION: 1 REGIONAL ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	652.33 DRUM	75.000 EA	_____	_____	_____	_____
0490	652.34 CONE	150.000 EA	_____	_____	_____	_____
0500	652.35 CONSTRUCTION SIGNS	650.000 SF	_____	_____	_____	_____
0510	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	_____
0520	652.38 FLAGGER	370.000 HR	_____	_____	_____	_____
0530	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	4.000 EA	_____	_____	_____	_____
0540	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	_____
0550	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____