



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Janet T. Mills  
GOVERNOR

Bruce A. Van Note  
COMMISSIONER

March 27, 2023  
Subject: Large Culvert Replacement  
State WIN: 025515.00  
Location: Saint George  
**Amendment No. 2**

Dear Sir/Ms.:

The following question has been received:

**Question:** This project has a state supplied culvert and the bid form indicates that the pipe is 120" (10' diameter) and the drawings are indicating a 12' diameter pipe. Can you please clarify. The correct dimension will assist with the calculation of the incidental excavation

**Response:** The pipe is 144" in diameter. See attached Proposal Schedule of Items, dated 3/27/2023.

Consider these changes and information prior to submitting your bid on **March 29, 2023**.

Sincerely,

A handwritten signature in blue ink that reads 'George Macdougall'.

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

3/27/2023

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 025515.00

Project(s): 025515.00

SECTION: 1 HIGHWAY

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |              | Bid Amount |           |
|----------------------|---|--------------------------------|------------|--------------|------------|-----------|
|                      |   |                                | Dollars    | Cents        | Dollars    | Cents     |
| 0010                 | 203.20<br>COMMON EXCAVATION   | 1,640.000<br>CY                | _____      | <br>_____    | _____      | <br>_____ |
| 0020                 | 203.25<br>GRANULAR BORROW   | 640.000<br>CY                  | _____      | <br>_____    | _____      | <br>_____ |
| 0030                 | 203.55<br>CULVERT BEDDING STONE   | 190.000<br>CY                  | _____      | <br>_____    | _____      | <br>_____ |
| 0040                 | 304.10<br>AGGREGATE SUBBASE COURSE - GRAVEL                                   | 820.000<br>CY                  | _____      | <br>_____    | _____      | <br>_____ |
| 0050                 | 403.213<br>HOT MIX ASPHALT 12.5 MM BASE                                       | 200.000<br>T                   | _____      | <br>_____    | _____      | <br>_____ |
| 0060                 | 409.15<br>BITUMINOUS TACK COAT - APPLIED                                      | 40.000<br>G                    | _____      | <br>_____    | _____      | <br>_____ |
| 0070                 | 511.07<br>COFFERDAM: DOWNSTREAM   | LUMP SUM                       |            | <br>LUMP SUM | _____      | <br>_____ |
| 0080                 | 511.07<br>COFFERDAM: UPSTREAM   | LUMP SUM                       |            | <br>LUMP SUM | _____      | <br>_____ |
| 0090                 | 603.10<br>CORRUGATED METAL PIPE 144"<br>POLYMER COATED STEEL - STATE SUPPLIED | 140.000<br>LF                  | _____      | <br>_____    | _____      | <br>_____ |
| 0100                 | 610.08<br>PLAIN RIPRAP  | 110.000<br>CY                  | _____      | <br>_____    | _____      | <br>_____ |
| 0110                 | 615.10<br>DIRTY BORROW  | 100.000<br>CY                  | _____      | <br>_____    | _____      | <br>_____ |
| 0120                 | 618.14<br>SEEDING METHOD NUMBER 2   | 3.000<br>UN                    | _____      | <br>_____    | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025515.00

Project(s): 025515.00

SECTION: 1 HIGHWAY

Alt Set ID: Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description   | Approximate Quantity and Units | Unit Price |           | Bid Amount |           |
|----------------------|---|--------------------------------|------------|-----------|------------|-----------|
|                      |   |                                | Dollars    | Cents     | Dollars    | Cents     |
| 0130                 | 619.12<br>MULCH   | 3.000<br>UN                    | _____      | <br>_____ | _____      | <br>_____ |
| 0140                 | 620.58<br>EROSION CONTROL GEOTEXTILE                        | 160.000<br>SY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0150                 | 620.65<br>REINFORCEMENT GEOGRID                             | 330.000<br>SY                  | _____      | <br>_____ | _____      | <br>_____ |
| 0160                 | 627.733<br>4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE | 1,300.000<br>LF                | _____      | <br>_____ | _____      | <br>_____ |
| 0170                 | 629.05<br>HAND LABOR, STRAIGHT TIME                         | 40.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0180                 | 631.12<br>ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)        | 40.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0190                 | 631.172<br>TRUCK - LARGE (INCLUDING OPERATOR)               | 40.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0200                 | 631.18<br>CHAIN SAW RENTAL (INCLUDING OPERATOR)             | 10.000<br>HR                   | _____      | <br>_____ | _____      | <br>_____ |
| 0210                 | 639.19<br>FIELD OFFICE TYPE B                               | 1.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0220                 | 652.312<br>TYPE III BARRICADE                               | 6.000<br>EA                    | _____      | <br>_____ | _____      | <br>_____ |
| 0230                 | 652.33<br>DRUM  | 30.000<br>EA                   | _____      | <br>_____ | _____      | <br>_____ |
| 0240                 | 652.34<br>CONE  | 100.000<br>EA                  | _____      | <br>_____ | _____      | <br>_____ |

Maine Department of Transportation

Proposal Schedule of Items

Proposal ID: 025515.00

Project(s): 025515.00

SECTION: 1 HIGHWAY

Alt Set ID:

Alt Mbr ID:

Contractor: \_\_\_\_\_

| Proposal Line Number | Item ID Description  | Approximate Quantity and Units | Unit Price        |              | Bid Amount |           |
|----------------------|--|--------------------------------|-------------------|--------------|------------|-----------|
|                      |  |                                | Dollars           | Cents        | Dollars    | Cents     |
| 0250                 | 652.35<br>CONSTRUCTION SIGNS                                 | 320.000<br>SF                  | _____             | <br>_____    | _____      | <br>_____ |
| 0260                 | 652.36<br>MAINTENANCE OF TRAFFIC CONTROL DEVICES             | 30.000<br>CD                   | _____             | <br>_____    | _____      | <br>_____ |
| 0270                 | 652.38<br>FLAGGER  | 250.000<br>HR                  | _____             | <br>_____    | _____      | <br>_____ |
| 0280                 | 652.41<br>PORTABLE CHANGEABLE MESSAGE SIGN                   | 2.000<br>EA                    | _____             | <br>_____    | _____      | <br>_____ |
| 0290                 | 656.75<br>TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL | LUMP SUM                       |                   | <br>LUMP SUM | _____      | <br>_____ |
| 0300                 | 659.10<br>MOBILIZATION                                       | LUMP SUM                       |                   | <br>LUMP SUM | _____      | <br>_____ |
| <b>Section: 1</b>    |  |                                | <b>Total:</b>     |              | _____      | <br>_____ |
|                      |  |                                | <b>Total Bid:</b> |              | _____      | <br>_____ |