



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Janet T. Mills  
GOVERNOR

Bruce A. Van Note  
COMMISSIONER

September 10, 2020  
Subject: Salt Storage Building  
State WIN: 026231.00  
Location: **Randolph**  
**Amendment No. 2**

Dear Sir/Ms.:

The following questions have been received:

**Question:** The attached Sheet 2 – General Plan states that the Resident Engineer will have final say on building location, moreover how the grades will be set. The site location shows a grade change of 2’-3’ over 50’ as an existing condition. Can any more direction be given at this time relating on whether or not it will be a cut or fill site?

**Response:** Fill Site with Gravel.

**Question:** Can you please confirm whether removed pavement is defined as an excavation Material in the statement below?

6.) During Construction, if it is Determined that there is excavation Material Suitable for Reuse, The Contractor may use Excavated Material For Backfill as Approved by the Resident. All excavated Material Unsuitable for Reuse Shall be Stock Piled on Site for Future use. Exact Location of Stock Pile Shall be Determined in the Field by the Resident.

**Response:** Pavement is an excavated material.

Consider these changes and information prior to submitting your bid on **September 16, 2020**.

Sincerely,

A handwritten signature in blue ink that reads "George Macdougall".

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer