



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

December 30, 2024
Subject: Casey Road/ I-95 Bridge Deck
Replacement
State WIN: 026238.00
Location: Benedicta
Amendment No. 1

Dear Sir/Ms.:

REMOVE pages 16 to 22 titled Proposal Schedule of Items dated 11/21/2024 and **REPLACE** with the attached Proposal Schedule of Items dated 12/30/2024 (7 pages).

The following questions have been received:

Question: Per line item 508.13, can we get clarification on "Sheet Waterproofing Membrane"? Is this High-Performance torch applied, or is Standard Hot Applied per the qualification products list?

Response: See Standard Specifications 508.01 Description and 508.02 Materials. Pay Item 508.13 Sheet Waterproofing Membrane is for standard waterproofing membrane systems.

Question: The Special Provisions Proposal Schedule of Items includes one pay item for 524.301 Temporary Structural Support but the Special Provisions also includes three separate Special Provisions Section 524 for different types of structural support. The item list on Plan page 2 includes three different items for 524.301. Should the Proposal Schedule of Items be changed to include 3 bid items for 524.301?

Response: Three separate 524.301 items is correct. See the attached updated Proposal Schedule of Items.

Consider these changes and information prior to submitting your bid on **January 8, 2025**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

12/30/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 7

Proposal ID: 026238.00

Project(s): 026238.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP SUM	LUMP	SUM	_____	_____
0020	202.121 REMOVING EXISTING CONCRETE	LUMP SUM	LUMP	SUM	_____	_____
0030	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	910.000 LF	_____	_____	_____	_____
0040	202.202 REMOVING PAVEMENT SURFACE	1,100.000 SY	_____	_____	_____	_____
0050	203.20 COMMON EXCAVATION	250.000 CY	_____	_____	_____	_____
0060	203.25 GRANULAR BORROW	55.000 CY	_____	_____	_____	_____
0070	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	73.000 CY	_____	_____	_____	_____
0080	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	130.000 CY	_____	_____	_____	_____
0090	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	110.000 T	_____	_____	_____	_____
0100	403.213 HOT MIX ASPHALT 12.5 MM BASE	23.000 T	_____	_____	_____	_____
0110	409.15 BITUMINOUS TACK COAT - APPLIED	71.000 G	_____	_____	_____	_____

12/30/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 7

Proposal ID: 026238.00

Project(s): 026238.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP	SUM	_____	_____
0130	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP	SUM	_____	_____
0140	502.291 SAW CUT GROOVING	LUMP SUM	LUMP	SUM	_____	_____
0150	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0160	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0170	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE:	4.000 EA	_____	_____	_____	_____
0180	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	142,100.000 LB	_____	_____	_____	_____
0190	503.13 REINFORCING STEEL, PLACING	142,100.000 LB	_____	_____	_____	_____
0200	503.17 MECHANICAL WELDED SPLICE	1,850.000 EA	_____	_____	_____	_____
0210	504.70 STRUCTURAL STEEL FABRICATED AND DELIVERED	LUMP SUM	LUMP	SUM	_____	_____
0220	504.71 STRUCTURAL STEEL ERECTION	LUMP SUM	LUMP	SUM	_____	_____

12/30/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 7

Proposal ID: 026238.00

Project(s): 026238.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP	SUM	_____	_____
0240	506.1775 FIELD PAINTING	LUMP SUM	LUMP	SUM	_____	_____
0250	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0260	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	_____	_____	_____
0270	507.131 TEMPORARY BRIDGE RAIL	LUMP SUM	LUMP	SUM	_____	_____
0280	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM	LUMP	SUM	_____	_____
0290	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM	_____	_____
0300	520.21 EXPANSION DEVICE - GLAND SEAL	2.000 EA	_____	_____	_____	_____
0310	523.52 BEARING INSTALLATION	8.000 EA	_____	_____	_____	_____
0320	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	8.000 EA	_____	_____	_____	_____
0330	524.301 TEMPORARY STRUCTURAL SUPPORT Approaches	LUMP SUM	LUMP	SUM	_____	_____
0340	524.301 TEMPORARY STRUCTURAL SUPPORT Bearing Replacement	LUMP SUM	LUMP	SUM	_____	_____

12/30/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 7

Proposal ID: 026238.00

Project(s): 026238.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	524.301 TEMPORARY STRUCTURAL SUPPORT Temporary Bracing	LUMP SUM	LUMP	SUM	_____	_____
0360	524.40 PROTECTIVE SHIELD	LUMP SUM	LUMP	SUM	_____	_____
0370	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0380	526.305 PORTABLE CONCRETE BARRIER, BRACED TYPE 1	LUMP SUM	LUMP	SUM	_____	_____
0390	527.33 TRUCK MOUNTED ATTENUATOR	2.000 EA	_____	_____	_____	_____
0400	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN	_____	_____	_____	_____
0410	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	370.000 LF	_____	_____	_____	_____
0420	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	3.000 EA	_____	_____	_____	_____
0430	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA	_____	_____	_____	_____
0440	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	20.000 EA	_____	_____	_____	_____
0450	607.183 CHAIN LINK SNOW FENCE 33 INCH	LUMP SUM	LUMP	SUM	_____	_____
0460	610.08 PLAIN RIPRAP	120.000 CY	_____	_____	_____	_____

12/30/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 7

Proposal ID: 026238.00

Project(s): 026238.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0470	613.319 EROSION CONTROL BLANKET	85.000 SY	_____	_____	_____	_____
0480	615.07 LOAM	5.000 CY	_____	_____	_____	_____
0490	618.14 SEEDING METHOD NUMBER 2	1.000 UN	_____	_____	_____	_____
0500	619.12 MULCH	1.000 UN	_____	_____	_____	_____
0510	619.14 EROSION CONTROL MIX	10.000 CY	_____	_____	_____	_____
0520	620.58 EROSION CONTROL GEOTEXTILE	180.000 SY	_____	_____	_____	_____
0530	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3,150.000 LF	_____	_____	_____	_____
0540	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	44.000 SF	_____	_____	_____	_____
0550	627.77 REMOVING PAVEMENT MARKINGS	440.000 SF	_____	_____	_____	_____
0560	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,150.000 LF	_____	_____	_____	_____
0570	629.05 HAND LABOR, STRAIGHT TIME	25.000 HR	_____	_____	_____	_____
0580	631.10 AIR COMPRESSOR (INCLUDING OPERATOR)	5.000 HR	_____	_____	_____	_____

12/30/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 7

Proposal ID: 026238.00

Project(s): 026238.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0590	631.11 AIR TOOL (INCLUDING OPERATOR)	5.000 HR				
0600	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	25.000 HR				
0610	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	25.000 HR				
0620	631.22 FRONT END LOADER (INCLUDING OPERATOR)	25.000 HR				
0630	639.19 FIELD OFFICE TYPE B	1.000 EA				
0640	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM				
0650	652.30 FLASHING ARROW BOARD	2.000 EA				
0660	652.312 TYPE III BARRICADE	4.000 EA				
0670	652.33 DRUM	70.000 EA				
0680	652.34 CONE	10.000 EA				
0690	652.35 CONSTRUCTION SIGNS	690.000 SF				
0700	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM				

Maine Department of Transportation

Page 7 of 7

Project(s): 026238.00

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0710	652.38 FLAGGER	320.000 HR				
0720	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA				
0730	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM		
0740	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM		
Section: 1			Total:			
			Total Bid:			