



Janet T. Mills
GOVERNOR

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Dale F. Doughty
COMMISSIONER

July 13, 2026
Subject: Large Culvert Replacement
WIN:027496.00
Location: Etna
Amendment No. 1

Dear Sir/Ms.:

Make the following changes to the Bid Documents:

In the Bid Book:

Remove pages seventeen through twenty one titled Proposal Schedule of items dated 6/26/2026 and **Replace** with the attached Schedule of items dated 7/7/2026

Remove page 59 titled SPECIAL PROVISION SECTION 107 Prosecution and Progress (Contract Time) dated 6/15/2026 and **Replace** with the attached SPECIAL PROVISION SECTION 107 Prosecution and Progress (Contract Time) dated 7/13/2026.

In the Plan Sheet:

Make the following Pen and Ink Changes to the Title Sheet:

Change State Road to Stage Road

Change Project Location to Route 2, located 0.43 of a mile west of Route 143

Remove page three titled ESTIMATED QUANTITIES dated 6/16/2026 and **Replace** with the attached ESTIAMTED QUANTITIES dated 7/7/2026

The following questions have been received:

Question: Plans show pavement removal (milling) beyond the full depth construction limits. There are no 202 items in the schedule if items. Is the milling incidental to some other work it will an item(s) be added?

Response: Item 202.202 is being added to the Estimated Quantities and Schedule of Items. Please replace page 3 with attached updated Estimated Quantity Sheet and replace Schedule of Items with attached.

Question: Is removal of the existing structure incidental to a pay item?

Response: Yes, the removal is incidental to pay item 534.7101

Question: The project calls for 3" milling and overlay in portions, but there is no pavement removal item. Please clarify.

Response: Item 202.202 is being added to the Estimated Quantities and Schedule of Items. Please replace page 3 with attached updated Estimated Quantity Sheet and replace Schedule of Items with attached.

Consider these changes and information prior to submitting your bid on **July 15, 2026.**

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

7/7/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 5

Proposal ID: 027496.00

Project(s): 027496.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.23 REMOVING SINGLE TREE TOP ONLY	4.000 EA				
0020	201.24 REMOVING STUMP	4.000 EA				
0025	202.202 REMOVING PAVEMENT SURFACE	950.000 SY				
0030	203.20 COMMON EXCAVATION	755.000 CY				
0040	203.2318 DISPOSAL OF SPECIAL WASTE	88.000 T				
0050	203.25 GRANULAR BORROW	217.000 CY				
0060	203.33 SPECIAL FILL	59.000 CY				
0070	304.16 AGGREGATE BASE COURSE - TYPE C	627.000 CY				
0080	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	160.000 T				
0090	403.213 HOT MIX ASPHALT 12.5 MM BASE	232.000 T				
0100	409.15 BITUMINOUS TACK COAT - APPLIED	50.000 G				
0110	461.131 TEMPORARY PAVEMENT	141.000 T				
0120	508.13 SHEET WATERPROOFING MEMBRANE	LUMP SUM		LUMP SUM		

7/7/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 5

Proposal ID: 027496.00

Project(s): 027496.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	510.10 SPECIAL DETOUR _____ ROADWAY WIDTH VEHICULAR & PEDESTRIAN TRAFFIC NOT SEPARATED - 14'	LUMP SUM	LUMP	SUM	_____	_____
0140	511.07 COFFERDAM: DOWNSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0150	511.07 COFFERDAM: UPSTREAM	LUMP SUM	LUMP	SUM	_____	_____
0160	534.7101 PRECAST CONCRETE BOX CULVERT - STATE SUPPLIED	LUMP SUM	LUMP	SUM	_____	_____
0170	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	375.000 LF	_____	_____	_____	_____
0180	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	50.000 LF	_____	_____	_____	_____
0190	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	2.000 EA	_____	_____	_____	_____
0200	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	2.000 EA	_____	_____	_____	_____
0210	606.277 TERMINAL END - ANCHORED END	1.000 EA	_____	_____	_____	_____
0220	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	8.000 EA	_____	_____	_____	_____
0230	606.52 MAILBOX REMOVE & RESET	1.000 EA	_____	_____	_____	_____

7/7/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 5

Proposal ID: 027496.00

Project(s): 027496.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	606.744 GUARDRAIL SYSTEM - LONG SPAN CULVERT	87.500 LF	_____	 _____	_____	 _____
0250	610.08 PLAIN RIPRAP	57.000 CY	_____	 _____	_____	 _____
0260	610.212 STREAMBED ROCK FEATURES	2.000 CY	_____	 _____	_____	 _____
0270	610.213 VOID FILLED RIPRAP	14.000 CY	_____	 _____	_____	 _____
0280	613.319 EROSION CONTROL BLANKET	134.000 SY	_____	 _____	_____	 _____
0290	615.10 DIRTY BORROW	60.000 CY	_____	 _____	_____	 _____
0300	618.14 SEEDING METHOD NUMBER 2	2.000 UN	_____	 _____	_____	 _____
0310	619.12 MULCH	2.000 UN	_____	 _____	_____	 _____
0320	620.58 EROSION CONTROL GEOTEXTILE	86.000 SY	_____	 _____	_____	 _____
0330	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	1,520.000 LF	_____	 _____	_____	 _____
0340	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	1,520.000 LF	_____	 _____	_____	 _____
0350	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	 _____	_____	 _____

7/7/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 5

Proposal ID: 027496.00

Project(s): 027496.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0360	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0370	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0380	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0390	639.19 FIELD OFFICE TYPE B	1.000 EA	_____	 _____	_____	 _____
0400	643.66 RESIDENTIAL DRIVEWAY TEMPORARY SIGNAL	1.000 EA	_____	 _____	_____	 _____
0410	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM	LUMP SUM		_____	 _____
0420	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
0430	652.33 DRUM	25.000 EA	_____	 _____	_____	 _____
0440	652.34 CONE	40.000 EA	_____	 _____	_____	 _____
0450	652.35 CONSTRUCTION SIGNS	400.000 SF	_____	 _____	_____	 _____
0460	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	140.000 CD	_____	 _____	_____	 _____
0470	652.38 FLAGGER	300.000 HR	_____	 _____	_____	 _____

7/7/2026

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 5

Proposal ID: 027496.00

Project(s): 027496.00

SECTION: 1 INITIAL GROUP

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0480	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
0490	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
0500	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____

SPECIAL PROVISION
SECTION 107
Prosecution and Progress
(Contract Time)

1. Contract Completion date is June 26, 2027.
2. The box culvert shall be installed and operational in 2026 prior to a winter suspension of work.

