



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Janet T. Mills  
GOVERNOR

Bruce A. Van Note  
COMMISSIONER

April 23, 2025  
Subject: Highway Rehabilitation  
WIN: 027676.00 & 027676.10  
Location: **Ellsworth & Hancock**  
**Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to the Bid Book:

Make the following change on page 47 titled **CONSTRUCTION NOTES** dated March 19, 2025 in pen and ink. **CHANGE** 609.111 Special Granite Curb – 24" to 609.1102 Special Granite Curb – 36".

**REMOVE** page 112 titled SPECIAL PROVISION, SECTION 609, CURB, (Special Granite Curb) dated March 31, 2025 and **REPLACE** with the attached revised SPECIAL PROVISION, SECTION 609, Curb (Special Granite Curb) dated April 21, 2025.

The following questions have been received:

**Question:** In the specification section 609.02, the description does not give enough information to quote the product. Can you provide a detail showing the curb, its location and the chamfered area? The standard curb width for 36" tall granite curb is 10".

**Response:** Please see the revised Special Provision 609.

Consider these changes and information prior to submitting your bid on **April 23, 2025**.

Sincerely,

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

SPECIAL PROVISION  
SECTION 609  
CURB  
(Special Granite Curb)

The provisions of Section 609 of the 2020 Standard Specifications with the following additions shall apply:

609.01 Description

This work shall consist of construction special granite curb, 36” in height, as shown on the plans and as directed by the Resident. The maximum reveal shall not exceed 12 inches.

609.02 Materials

Except as provided below, materials shall meet the requirements specified in the following section of Division 700 – Materials:

Stone Curbing and Edging

712.04

Backfill for one foot behind the Special Granite Curb shall meet the requirements of sections 703.19.

Installation

Curb shall be set to follow the shoulder profile grade. All other sections of Section 609 shall apply to this item. Special Granite Curb shall be set in flowable concrete fill which shall be incidental to the Special Granite Curb Item. Cutting and fitting necessary to install the curb shall be done by the Contractor as needed. The tops of adjacent curb sections shall be level, and each end of the curb run shall match into the existing ground. Geotextile shall be placed behind the joints between curb sections to retain the backfill material.

609.09 Method of Measurement

Special Granite Curb – 36 Inch will be measured by the foot along the front face of the curb at the finished grade elevation, including end curbing units/terminal sections, complete in place and accepted.

609.10 Basis of Payment

Payment will be made under:

Pay Item

Pay Unit

609.1102

Special Granite Curb – 36 Inch

Linear Foot