



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

March 14, 2025

Subject: Cyclical Pavement
Resurfacing
WIN: 028204.00
Location: **Unity**
Amendment No. 1

Dear Sir/Ms.:

Please make the following changes to the bid book:

REMOVE Pages 17 to 19 "Schedule of Items" dated 02/21/2025 and **REPLACE** with the attached revised "Schedule of Items" dated 3/14/2025, three pages.

In response to the following questions which have been received:

Question: Page 42 of the construction notes mentions item 629.05 Hand Labor but there is no item or Quantity in the schedule of items.

Response: Please see updated Schedule of Items

Question: Would the department consider adding an item for skid-steer with operator to clean guardrail sections?

Response: Please see updated Schedule of Items

Question: Was is the intent with regards to paving around the truck turnout/weigh stations on the project? Are these receiving pavement or a joint ground and paved by?

Response: The project intends to mill a joint in the shoulder and pave a consistent shoulder width only

Question: Is any more detailed information available for the construction notes such as detailing stationing and number of drives, sideroads, etc. how far back into these work is being performed?

Response: The Department does not analyze or correct cross slopes for CPR projects. It is anticipated that work to match existing conditions will be minimal.

Consider these changes and information prior to submitting your bid on **March 19, 2025.**

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer

3/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 3

Proposal ID: 028204.00

Project(s): 028204.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.2023 REMOVING PAVEMENT SURFACE - MEDIUM CUT DRUM	9,600.000 SY	_____	 _____	_____	 _____
0020	202.203 PAVEMENT BUTT JOINTS	330.000 SY	_____	 _____	_____	 _____
0030	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	70.000 T	_____	 _____	_____	 _____
0040	409.15 BITUMINOUS TACK COAT - APPLIED	6,400.000 G	_____	 _____	_____	 _____
0050	410.153 EMULSIFIED ASPHALT SEALCOAT WITH GRIT, APPLIED	5,011.000 SY	_____	 _____	_____	 _____
0060	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	20.000 CY	_____	 _____	_____	 _____
0070	461.210 9.5 MM HMA - CYCLICAL PAVEMENT RESURFACING	4,900.000 T	_____	 _____	_____	 _____
0080	461.216 HOT MIX ASPHALT (SHIMMING)	2,930.000 T	_____	 _____	_____	 _____
0090	615.07 LOAM	2.000 CY	_____	 _____	_____	 _____
0100	618.14 SEEDING METHOD NUMBER 2	37.000 UN	_____	 _____	_____	 _____
0110	619.12 MULCH	37.000 UN	_____	 _____	_____	 _____
0120	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	92,790.000 LF	_____	 _____	_____	 _____

3/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 3

Proposal ID: 028204.00

Project(s): 028204.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	530.000 SF	_____	_____	_____	_____
0140	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	94,930.000 LF	_____	_____	_____	_____
0145	629.05 HAND LABOR, STRAIGHT TIME	10.000 HR	_____	_____	_____	_____
0150	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	30.000 HR	_____	_____	_____	_____
0155	631.133 SKID STEER (INCLUDING OPERATOR)	10.000 HR	_____	_____	_____	_____
0160	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	60.000 HR	_____	_____	_____	_____
0170	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	5.000 SF	_____	_____	_____	_____
0180	652.34 CONE	110.000 EA	_____	_____	_____	_____
0190	652.35 CONSTRUCTION SIGNS	600.000 SF	_____	_____	_____	_____
0200	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	54.000 CD	_____	_____	_____	_____
0210	652.38 FLAGGER	2,400.000 HR	_____	_____	_____	_____

3/14/2025

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 3

Proposal ID: 028204.00

Project(s): 028204.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0220	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM		LUMP SUM		
0230	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	150.000 SY				
0240	659.10 MOBILIZATION	LUMP SUM		LUMP SUM		
Section: 1			Total:			

SECTION: 2 SEWER ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0250	812.162 ADJUSTING SEWER MANHOLE TO GRADE	11.000 EA				
Section: 2			Total:			
			Total Bid:			