



STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Janet T. Mills  
GOVERNOR

Bruce A. Van Note  
COMMISSIONER

May 1, 2025  
Subject: Bridge Replacement  
WIN: 028246.00  
Location: **Litchfield**  
**Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to the Bid Book:

**INSERT** attached "SPECIAL PROVISION, SECTION 203, EXCAVATION AND EMBANKMENT", 1 page, dated March 18, 2025 after page 41.

Consider these changes and information prior to submitting your bid on **May 14, 2025**.

Sincerely,

A handwritten signature in blue ink, reading "George Macdougall".

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer

SPECIAL PROVISION  
SECTION 203  
EXCAVATION AND EMBANKMENT  
(Culvert Bedding Stone)

Description This work shall consist of constructing a foundation pad of Culvert Bedding Stone in accordance with these specifications and in reasonably close conformity with the width, length, grade and thickness shown on the Plans or established by the Resident.

Materials Culvert Bedding Stone shall meet the requirements of Standard Specification Section 703.22, Underdrain Backfill Material, Type C.

Construction Requirements The Culvert Bedding Stone shall be placed and graded as shown on the Plans or as directed by the Resident, and shall be compacted as required to ensure that all voids in the stone are filled, as approved by the Resident.

Method of Measurement Culvert Bedding Stone will be measured by the cubic yard, complete, in place.

Basis of Payment The accepted quantity of Culvert Bedding Stone will be paid for at the Contract unit price per cubic yard, complete, in place.

Payment will be made under:

<u>Pay Item</u>	<u>Pay Unit</u>
203.55 Culvert Bedding Stone	Cubic Yard