



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

January 26, 2024

Subject: Emergency Highway Rehabilitation
State WIN: 028702.00
Location: **Bristol**
Amendment No. 1

Dear Sir/Ms.:

The following questions have been received:

Question: Can you provide approximate limits, footage and size (of grout bags) for the areas receiving the grout bag and concrete fill treatment?

Response: The Department has ordered 30 each 7' x 5" bags and 80 each 4'x2' bags. There are several different areas consisting of 350 lineal feet.

Question: Can you provide the approximate limits of the pavement saw cutting, removal, graveling and re-paving?

Response: There are two areas of pavement saw cutting, removal, graveling and repaving of consist of 110' by 9' and 20' by 9'.

Question: Can you provide a rough idea of which areas along the project will be receiving the heavy rip rap? Is it long consistent sections, or broken up?

Response: There 3 areas consisting of 1100 lineal feet.

Question: Is the Department concerned with leakage of the concrete fill around the grout bags?

Response: The Contractor will lay fabric against the interior wall of the grout bags before the placement of the concrete fill. The fabric will be incidental to item 502.565 CONCRETE FILL.

Consider these changes and information prior to submitting your bid on **January 31, 2024**.

Sincerely,

George M. A. Macdougall P.E. Contracts
& Specifications Engineer