



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Janet T. Mills
GOVERNOR

Bruce A. Van Note
COMMISSIONER

June 25, 2021
Subject: Swans Island Ferry Vessel
Construction
State WIN: PH022194.00
Location: **Rockland**
Amendment No. 3

Dear Sir/Ms.:

Make the following changes to the Bid Documents:

In the Bid Book:

On page 175, page 37 of 115 in "Contract Specifications", Section 171.1, **CHANGE** "transverse yardarm for flag hoists and day shapes" to "transverse yardarm for flag hoists, day shapes, and anemometer." Make this change in pen and ink.

On page 175, page 37 of 115 in "Contract Specifications", Section 171.1, **ADD** "a mast shall support satellite compass on the pilothouse top, port side." Make this change in pen and ink.

On page 175, page 37 of 115 in "Contract Specifications", **ADD** "Section 191, Fixed Ballast. Contractor shall provide and install fixed heeling ballast in the hold, on port side, between frames 20 and 24, on a raised steel flat, as shown on Plans D358A-A1, and D358A-S2-2. Ballast shall consist of 10 long tons of concrete. Ballast shall be secured to steel flat using steel reinforcing bars welded in place before concrete is poured." Make this change in pen and ink.

On page 210, page 72 of 115 in "Contract Specifications", Section 511.1.3.4, and Plan D358A-M9, Sheet 1 "Material List" **CHANGE** "Fans shall be Broan Nutone model 682 with charcoal filters, or approved equal." to "Fans shall be Broan Nutone model 670, or approved equal. Fans shall be arranged to exhaust to weather through louvers in deckhouse bulkheads outboard. Fans shall be provided with ductwork, fire dampers, and weather closures as required." Make this change in pen and ink.

On page 213, page 75 of 115 in "Contract Specifications", Section 521.1.2, **ADD** "Contractor shall provide and install two automatic, float-actuated, self-priming shaft gland pumps. Pumps shall be mounted in the shaft gland sumps port and starboard, and be piped with 1 1/4" galvanized steel schedule 80 pipe directly to the overboard discharge with stop-check valves. Pumps shall be Dayton-Grainger 3YU71C, 1/2 HP, 115 VAC, or approved equal." Make this change in pen and ink.

On page 215, page 77 of 115 in "Contract Specifications", Section 555.1.2, **ADD** "Contractor shall provide and install a wheeled, semi-portable, 125-pound capacity dry chemical fire extinguisher on

Main Deck, located as directed by the MaineDOT OREP. Extinguisher shall be Amerex 488, or approved equal, with 50 ft. hose.” Make this change in pen and ink.

On page 226, page 88 of 115 in “Contract Specifications”, Section 612.1.1, **ADD** “Contractor shall provide and install 2 ea. removable stanchions, 30” high, 1 1/2” schedule 40 pipe, outboard of each inflatable buoyant apparatus on 02 Deck. ”. Make this change in pen and ink.

On page 234, page 96 of 115 in “Contract Specifications”, Section 631.2 A.10.1, **CHANGE** “PSX 700 color per OREP 5 mils DFT” to read “gray shop primer only”. Make this change in pen and ink.

On page 236, page 97 of 115 in “Contract Specifications”, **ADD** the following section in pen and ink:

A.14 CREW SPACE FLAT BELOW MAIN DECK, INTERIOR 01 DECK PUBLIC SPACES INCLUDING HEADS, CREW SPACE HEADS, INTERIOR PILOTHOUSE DECK AND PILOTHOUSE LOBBY

A.14.1.1: AREAS OF COMMERCIAL BLAST AND NEW STEEL

- Dimetcoat 302H 3-4 mils DFT
- Amerlock 2 white 5 mils DFT
- PSX 700 pearl gray with color chip flakes 3-4 mils DFT
- PSX 700 clear top coat 3-4 mils DFT

On page 237, page 98 of 115 in “Contract Specifications”, Section 634.1.2, **CHANGE** “Poured epoxy covering with broadcast flake pattern. Covering will be installed with turned-up cove base 4 inches on the bulkheads.” to “Paint in accordance with schedule”. Make this change in pen and ink.

On page 237, page 98 of 115 in “Contract Specifications”, Section 634.1.4, **CHANGE** “Poured epoxy floor covering, color to be approved by the MaineDOT OREP.” to read “Paint in accordance with schedule. Color and pattern to be approved by the MaineDOT OREP.”. Make this change in pen and ink.

On page 238, page 100 of 115 in “Contract Specifications”, Section 645.1.2, **CHANGE** “a fixed lookout chair to port” to read “2 portable lookout chairs, one port and one starboard”. Make this change in pen and ink.

On page 238, page 100 of 115 in “Contract Specifications”, Section 645.1.2, **CHANGE** “raised settee” to read “raised settee with folding step”. Make this change in pen and ink.

In the Plan Set:

On Sheet D358A-P13, Sheet 1, “List of Hot Water Heaters”, **CHANGE** “Pilot House 02 Deck Heater B24.32 ECO” to “Pilot House 02 Deck Heater B16.16 ECO”. Make this change in pen and ink.

The following questions have been received:

Question: Which of the plans specifies the coating system? In Section 506 of the MaineDOT Standard Specifications it says ‘The protective coating system shall be as specified on the Plans’.

Answer: The protective coating system shall be as specified in Bid Book, pages 229 to 235, pages 91 to 97 of 115 of the “Contract Specifications”, Sections 631.1 and 631.2.

Question: What other coating certification would be acceptable for 631.1.2 General Scope of Work, Page 229 of the bid book)?

Answer: Another coatings certification such as American Institute of Steel Construction (AISC) certification would be considered acceptable to meet this requirement.

Consider these changes and information prior to submitting your bid on **July 28, 2021**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer