



STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
16 STATE HOUSE STATION
AUGUSTA, MAINE 04333-0016

Paul R. LePage
GOVERNOR

David Bernhardt
COMMISSIONER

September 27, 2018
Subject: Safety Patrol for
Interstate 95
WIN: PH025228.18
Location: **Freeport to Scarborough
Amendment No. 1**

Dear Sir/Ms.:

Please make the following changes to the Bid Documents:

In the Bid Book:

CHANGE on page 35, APPENDIX A, REQUEST FOR PROPOSAL, SPECIFICATIONS OF WORK TO BE PERFORMED, PART III – VEHICLE SPECIFICATIONS, in Section 2, Vehicle Components, f) Forward and backward Camera: to read:

“f) 360-degree Pan Tilt Zoom (PTZ) Camera: The PTZ shall have an environmental rating of at least IP66 with temperature rating of -40~+65 degree C. The network camera shall have at least a 1920 x 1080 Progressive Scan CMOS day/night with a 30 x Optical 4.5-135 mm HD IR Corrective Continuous Zoom Lens, Optical Field View from 67.8 to 2.4 degrees. The communication between vehicle and TMC will be 4G Cellular Transmission with a TMC operating software that allows full PTZ Control, including tours and presets, digital zoom with Picture in Picture (PIP), on up to 64 channels per monitor. Software will also give device status and real time system health monitoring. The Contractor will provide the PTZ Camera and Software for communicating between the vehicle and the TMC and the Department will provide the Cellular Service.”

Make this change in pen and ink.

On page 44, PART VII – PROPOSALS SUBMISSION REQUIREMENTS, Section 2. Proposal Content, **REMOVE** the first paragraph which begins with “At a minimum, your Proposal package...” and **REPLACE** with:

“At a minimum, your Proposal package should include **three copies** of all items listed in the Bidding Instructions along with the following:”

Make this change in pen and ink.



PRINTED ON RECYCLED PAPER


The following question has been received:

Question: In reference to the RFP for Safety Patrols on I-295 from Freeport to Scarborough, in addition to our original proposal, how many copies are required to be submitted?

Response: See above changes to PART VII – PROPOSALS SUBMISSION REQUIREMENTS, Section 2. Proposal Content.

Consider these changes and information prior to submitting your bid on **October 3, 2018**.

Sincerely,



George M. A. Macdougall P.E.
Contracts & Specifications Engineer