



Janet T. Mills  
GOVERNOR

STATE OF MAINE  
DEPARTMENT OF TRANSPORTATION  
16 STATE HOUSE STATION  
AUGUSTA, MAINE 04333-0016

Bruce A. Van Note  
COMMISSIONER

May 8, 2024  
Subject: UV Cured in Place Pipe Liner  
State WIN: 026368.00  
Location: **Lexington**  
**Amendment No. 1**

Dear Sir/Ms.:

The following questions have been received:

Question: Please confirm the contractor is allowed to release filtered water removed during the pipe vacuuming process (known as “decant water”) into the sanitary or storm system.

- a. If the decant water is to be released to the sanitary system, please confirm the sanitary sewer operator has granted permission.
- b. If the decant water is to be released to the storm system, please provide a copy of the MS4 permit.

Response: There is no sanitary or storm drainage located at the site. This site will require coffer dams to be installed at the inlet and outlet of the pipe to prevent water from flowing through during work. Any water located between the cofferdams from the natural system or introduced from any work on the project shall be removed. The water removed from between cofferdams should be pumped to a dirt bag or sediment basin located in a well-draining upland area on site.

Question: Please confirm that the water introduced for the pipe jetting process is allowed to remain in the storm system.

Response: There is no sanitary or storm drainage located at the site. Any water located between the cofferdams from the natural system or introduced from any work on the project shall be removed. The water removed shall be pumped to a dirt bag or sediment basin located in a well-draining upland area on site.

Consider these changes and information prior to submitting your bid on **May 15, 2024**.

Sincerely,

George M. A. Macdougall P.E.  
Contracts & Specifications Engineer