



ELEVATION OF SPLAY CASTING

4 REQUIRED CAST STEEL ANNEALED

COMPLETE WITH HIGH TENSION BOLTS

WEIGHT OF ONE SPLAY CASTING = 450<sup>LB</sup> TOTAL FOR BRIDGE = 1800<sup>LB</sup>

WEIGHT OF HIGH TENSION BOLTS FOR ONE CASTING = 90<sup>LB</sup> TOTAL FOR BRIDGE = 360<sup>LB</sup>

11-153

SUPERSTRUCTURE

P.W.A. PROJECT NO. ME 1010 D

DEER ISLE SEDGWICK BRIDGE DISTRICT

BRIDGE OVER EGGEMOGGIN REACH

FROM LITTLE DEER ISLE TO SEDGWICK

HANCOCK COUNTY, MAINE

SPLAY CASTINGS

ROBINSON AND STEINMAN  
ENGINEERS  
NEW YORK CITY

SCALE 3" = 1'-0"

DRAWING NUMBER  
RS 3310-3109

SEPTEMBER 4, 1937

