



MATERIAL REQUIRED					
DESCRIPTION	REQUIRED NET	EXTRA FOR LOSS & WASTE	TOTAL REQUIRED	ON HAND	REQUIRED THIS ORDER
CLIP C1	124	8	132	50	110
CLIP C2	124	8	132	40	55
3/4" U-Bolt with 2 nuts	124	8	132	—	130
1/2" U-Bolt with 2 nuts	24	3	27	—	25
Wire Rope Wires	92	3	95	—	95

NOTES:
 Clips - Drop Forgings } Galvanized
 Bolts - Mild Steel }
 Nuts - Mild Steel }
 U-Bolts - Mild Steel }
 Wire - Iron Fillet Rope }

DEER ISLE SEDGWICK BRIDGE
 HANCOCK COUNTY - MAINE
 CABLE STAY SUPPORTS
 AT
 EACH SUSPENDER

SCALE - FULL SIZE

ROBINSON & STEINMAN
 CONSULTING ENGINEERS
 NEW YORK CITY

DRAWING No.
 RS 4109-1
 DEC. 6, 1941

