



MATERIAL REQUIRED					
DESCRIPTION	REQUIRED NET	EXTRA FOR LOSS & WASTE	TOTAL REQUIRED	ON HAND	THIS ORDER
CLIP C1	184	3	190	190	190
CLIP C2	72	3	75	75	75
3/8" D-Bolt with 2 Nuts	184	6	190	190	190
3/8" D-Bolt with 2 Nuts	72	3	75	75	75
Wire Rope Slings	3	3	6	6	6

NOTES:-

- Clips - Drop Forgings
- Bolts - Mild Steel
- Sling - 3/8" dia, 6 x 19, Pretreated Blue Center Wire Rope with Independent Wire Rope Center, both ends served.

All material galvanized.

Field Note:-

- Wind sling around upper U-Bolt for a few turns to act as a snub.
- found to be practicable.

DEER ISLE - SEDGWICK BRIDGE
HANCOCK COUNTY - MAINE
CABLE STAY SUPPORTS
TAT
EACH SUSPENDER
SCALE - FULL SIZE

ROBINSON & STEINMAN CONSULTING ENGINEERS NEW YORK CITY	DRAWING NO. RS-4109-11 DEC. 6, 1941
--	---