

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION



HERMON
PENOBSCOT COUNTY

COLDBROOK RD / ODLIN RD / EMERSON MILL RD

2287700



PROJECT LENGTH : 0.00 MILES

PLAN LEGEND

Town, County, State	_____	Catch Basins	▣ Existing	■ Proposed
Property Lines	-----	Manholes	○ Existing	● Proposed
R/W Lines-Existing	-----	Proposed Underdrain	-----	
R/W Lines-Proposed	-----	Proposed Ditch	-----	
Culvert-Existing	-----	Existing Ditch	-----	
Culvert Proposed	-----	Utility Poles	⊕ Existing	◆ Proposed
Curbing	Existing Proposed	Fire Hydrants	⊙ Existing	⊙ Proposed
Type 1	-----	Existing Water Line	-----	
Type 3	-----	Existing San. Sewer	-----	
Type 5	-----	Existing San. Sewer Manhole	⊙	
Outline of Bodies of Water	-----	Guardrail-Existing	-----	
Exposed Bedrock	-----	Guardrail-Proposed	-----	
Buildings	-----	Guardrail-Cable, Other	-----	
Trees	Conifer Deciduous	Centerline-Existing	-----	
Tree Line	-----	Centerline-Proposed	-----	
Clearing Limit Line	-----	Travelway-Existing	-----	
Railroad	-----	Travelway-Proposed	-----	
Boring	HB-XXX-###	Probe	P-#.X	
Pavement Core	PC-#	#. # = Depth		
Test Pit	TP-XXX-###	X = W (Weathered Rock)		
		R (Refusal)		
		NR (No Refusal)		

INDEX OF SHEETS

Description	Sheet No.
Title Sheet	1
Plan	2
Signal Detail	3
Geoplan	4



PROJECT LOCATION:	INTERSECTION OF COLDBROOK RD/ODLIN RD/EMERSON MILL RD IN HERMON
PROGRAM AREA:	MULTIMODAL
SCOPE OF WORK:	TRAFFIC SAFETY IMPROVEMENTS

WIN 22877.00 2287700

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION

APPROVED
COMMISSIONER: *[Signature]*
CHIEF ENGINEER: *[Signature]*

DATE
11-15-18
11-15-18

PROJECT INFORMATION

PROGRAM	MULTIMODAL
PROJECT MANAGER	DANIEL LORNE
DESIGNER	AL GODFREY, JR.
CONSULTANT	TERRA MAGNA SERVICES, INC.
PROJECT RESIDENT	
CONTRACTOR	
PROJECT COMPLETION DATE	


HERMON
COLDBROOK RD/ODLIN RD/EMERSON MILL RD

TITLE SHEET



SHEET NUMBER
1
OF 4

4. FOUNDATIONS SHALL CONSIST OF CAST-IN-PLACE REINFORCED CONCRETE DRILLED SHAFTS; ONE NEW DRILLED SHAFT PER MAST ARM OR DUAL PURPOSE POLE AS SET FORTH IN SPECIAL PROVISION 643. FOUNDATION SIZES SHALL BE SELECTED BY THE CONTRACTOR BASED UPON ACTUAL COMPUTED BENDING MOMENTS AND TORSION IN ACCORDANCE WITH SPECIAL PROVISION 643. ACTUAL DESIGN LOADS AT THE TOP OF THE FOUNDATION THAT ARE PROVIDED BY THE CONTRACTOR AS PART OF THEIR STRUCTURAL SUBMITTAL WILL BE USED BY THE DEPARTMENT TO CHECK THE SPECIFIED SIZE OF THE DRILLED SHAFTS. DRILLED SHAFTS SHALL NOT BE PERMANENTLY CASED, EXCEPT FOR THE TOP 3 FEET; CONCRETE SHALL BE CAST DIRECTLY AGAINST THE SURROUNDING SOIL. PRECAST FOUNDATIONS WILL NOT BE ACCEPTED.


Filename: ... \002_HDPlan1.dgn



OF 4



INITIAL SIGNAL TIMING								
PHASE	1	2	3	4	5	6	7	8
MIN. INITIAL	5.0	10.0	-	10.0	-	10.0	-	10.0
VEH. EXT.	3.0	5.0	-	3.0	-	5.0	-	3.0
MAX. GREEN	17	22	-	23.5	-	45	-	23.5
YELLOW	3.5	3.5	-	3.5	-	3.5	-	3.5
ALL RED	2.5	2.5	-	2.0	-	2.5	-	2.0
FLASH	R	Y	-	R	-	Y	-	R
RECALL	-	SOFT	-	-	-	SOFT	-	-



TRAFFIC SIGNAL NOTES

1. TRAFFIC SIGNAL WORK FOR THIS PROJECT WILL INCLUDE, BUT NOT BE LIMITED TO, FURNISHING AND INSTALLING A COMPLETE NEW NEMA TS-2 TYPE 2 PEDESTAL-MOUNTED TRAFFIC SIGNAL CABINET AND FOUNDATION, CONTROLLER, MMU, FLASHER UNIT, DETECTOR RACK, AND OTHER NECESSARY COMPONENTS; TRAFFIC SIGNAL ASSEMBLIES; RADAR FOR ADVANCE DETECTION FOR DILEMMA ZONE PROTECTION AND SECONDARY STOP LINE PRESENCE DETECTION; INTERSECTION LIGHTING; AND RELATED INCIDENTAL WORK AND MATERIALS.
2. ALL WORK SHALL BE COMPLETED IN CONFORMANCE WITH THE LATEST REVISIONS OF THE STATE OF MAINE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES, THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE NATIONAL ELECTRICAL CODE, AND ANY REQUIREMENTS OF THE POWER COMPANY.
3. AN EXTERNAL, STANDALONE BREAKER TO DISCONNECT POWER TO THE NEW CONTROL CABINETS SHALL BE INSTALLED IN A LOCKABLE NEMA 3R ENCLOSURE BETWEEN THE METER AND THE CABINET.
4. THE CONTROL CABINETS AND THE POWER DISCONNECT ENCLOSURE EACH SHALL BE MARKED WITH ARC HAZARD TYPE 2, 3 OR 4 AND THE APPROPRIATE PPE REQUIRED. SEE SECTION 643.09 FOR OTHER REQUIREMENTS.
5. WIRING AND CONTROL HARDWARE FOR INTERSECTION LIGHTING SHALL BE INSTALLED IN A LOCKABLE NEMA 3R ENCLOSURE SEPARATE FROM THE TRAFFIC SIGNAL CABINET.
6. SIGNAL ASSEMBLIES SHALL BE POLYCARBONATE WITH DOUBLE SPANWIRE SUPPORT. ALL SIGNAL ASSEMBLIES AND OVERHEAD SIGNAGE ATTACHED TO SPANWIRES SHALL BE STABILIZED WITH A BOTTOM TETHER.
7. RADAR DETECTION SHALL PROVIDE BOTH DILEMMA ZONE PROTECTION AND SECONDARY STOP BAR PRESENCE DETECTION. DETECTORS SHALL BE INDIVIDUALLY SURGE PROTECTED AND FUSED. MOUNT DETECTORS AT 20' TO 26' ABOVE ROADWAY ELEVATION.
8. LOCATIONS OF ANY EXISTING UNDERGROUND UTILITIES SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE PRESENCE OF UNDERGROUND UTILITY FACILITIES PRIOR TO COMMENCING ANY EXCAVATION WORK OR INSTALLATION OF POLES, FOUNDATIONS, JUNCTION BOXES, CONDUIT OR GROUND-MOUNTED SIGNAGE AND SHALL NOTIFY UTILITIES OF PROPOSED WORK IN ACCORDANCE WITH MRSA TITLE 23 SECTION 3360-A, MAINE "DIG SAFE" SYSTEM. CONTRACTOR SHALL CONTACT DIG SAFE AT LEAST THREE WORKING DAYS PRIOR TO THE BEGINNING OF EXCAVATION. ALL UTILITIES SHALL BE LOCATED BEFORE BEGINNING EXCAVATION.
9. THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES AT LEAST 48 HOURS BEFORE ANY OPERATIONS ARE CONDUCTED THAT POTENTIALLY COULD CONFLICT WITH AERIAL UTILITIES.
10. NEW CONDUIT NOT UNDER PAVEMENT SHALL BE 3 INCH MINIMUM, PVC SCHEDULE 40. MINIMUM BURIAL DEPTH FOR CONDUIT SHALL BE 36". TOP 3 INCHES OF CONDUIT SHALL BE SEALED TO PREVENT ENTRY BY RODENTS. CONDUIT BETWEEN THE POWER SOURCE AND THE CABINET SHALL BE CONCRETE ENCASED.
11. THERE SHALL BE NO SPLICES OR JUNCTION BOXES EXCEPT AS NOTED ON THE PROJECT PLANS OR APPROVED BY THE RESIDENT.
12. JUNCTION BOX COVERS SHALL BE LABELED "TRAFFIC".
13. SPECIFIED TRAFFIC SIGNAL POLE LOCATIONS ARE MEASURED TO THE CENTER OF THE POLES. SPECIFIED LOCATION FOR THE CONTROLLER IS MEASURED TO THE CENTER OF THE CONTROLLER FOUNDATION.
14. ALL FIELD WIRING SHALL BE NEATLY BUNDLED AND CLEARLY IDENTIFIED WITH PERMANENT, LEGIBLE, WEATHERPROOF TAGS SECURELY ATTACHED TO EACH CABLE.
15. AT THE TIME OF FINAL PROJECT INSPECTION, THE CONTRACTOR SHALL FURNISH TO THE RESIDENT THREE COMPLETE SETS OF AS-BUILT TRAFFIC SIGNAL PLANS. ONE ADDITIONAL SET SHALL REMAIN IN EACH CABINET.
16. THE MAINTENANCE OF TRAFFIC SIGNALS SHALL REMAIN THE RESPONSIBILITY OF THE CONTRACTOR UNTIL FINAL ACCEPTANCE BY MAINEDOT.

17. PAYMENT UNDER ITEM 643.80 SHALL INCLUDE, BUT NOT BE LIMITED TO, POWER SERVICE AND METER, METER DISCONNECT AND ENCLOSURE, BRACKET ARMS, SPANWIRES, TETHER WIRES, SIGNAL ASSEMBLIES AND LED LAMPS, BACKPLATES, VISORS, GUY LEADS AND ANCHORS, CONTROLLER AND CABINETS, LUMINAIRES, RADAR TRAFFIC DETECTORS, WIRING, CABLE, POLE RISERS, AND ALL APPURTENANCES AND INCIDENTALS NECESSARY FOR A COMPLETELY FUNCTIONING TRAFFIC SIGNAL INSTALLATION, OTHER THAN RELATED LABOR, MATERIALS AND EQUIPMENT INCLUDED IN OTHER PAY ITEMS OF THE CONTRACT.

LUMINAIRE NOTES

1. PROPOSED LIGHTING SHALL BE PHOTOCELL ACTIVATED BY A PHOTOCELL ON THE CONTROL CABINET.
2. LIGHTING FIXTURE VOLTAGE SHALL BE 240 VOLTS.
3. LIGHTING FIXTURE SHALL BE AN IES FULL CUTOFF LIGHT EMITTING DIODE (LED) FIXTURE, IES DISTRIBUTION TYPE 3. LED COLOR TEMPERATURE SHALL BE 4000K.
4. FIXTURE SHALL BE GASKETED AND HAVE SURGE PROTECTION AND A DOUBLE FUSE KIT. FIXTURE SHALL BE GRAY.
5. LUMINAIRE ON POLE 'B' SHALL BE AN AMERICAN ELECTRIC LIGHTING 'AUTOBAHN' ATB2 SERIES, 91WATT 700 MA LED FIXTURE, CATALOG NUMBER ATB2 40BLEDE70 R3 4K.
6. LUMINAIRE SHALL BE ATTACHED TO SIGNAL STRAIN POLE 'B' WITH A 2-INCH DIAMETER MINIMUM LENGTH GALVANIZED STEEL HORIZONTAL PIPE TENON MOUNT. MOUNT AT 30' ABOVE ROADWAY ELEVATION.
7. LUMINAIRE SHALL OPERATE ON THE SAME METER AS THE TRAFFIC SIGNALS.

GENERAL NOTE

A MAINE DEPARTMENT OF TRANSPORTATION (MAINEDOT) ENVIRONMENTAL OFFICE INVESTIGATION SPECIFIC WITH THIS PROJECT ENCOUNTERED DATA SUGGESTING PETROLEUM RELATED CONTAMINATION WAS PRESENT AT ROUGHLY MAINEDOT STATION 26+40 RIGHT OF CENTER. SUBSEQUENT ON-SITE ENVIRONMENTAL BORING WORK FAILED TO UNEARTH ANY ISSUES WITHIN THIS AREA. HOWEVER, IN LIGHT OF THE AVAILABLE ENVIRONMENTAL DATA, THE CONTRACTOR SHALL EMPLOY APPROPRIATE HEALTH AND SAFETY MEASURES TO PROTECT ITS WORKERS AGAINST HAZARDS ASSOCIATED WITH WORKING NEAR PETROLEUM-IMPACTED SOILS. FURTHERMORE, THE CONTRACTOR SHALL REMAIN ALERT FOR ANY ADDITIONALLY EVIDENCE OF CONTAMINATION. IF THE CONTRACTOR ENCOUNTERS EVIDENCE OF SOIL OR GROUNDWATER CONTAMINATION, THE CONTRACTOR SHALL SECURE THE EXCAVATION, STOP WORK IN THE CONTAMINATED AREA, AND IMMEDIATELY NOTIFY THE RESIDENT. THE RESIDENT SHALL CONTACT THE SENIOR GEOLOGIST IN MAINEDOT'S ENVIRONMENTAL OFFICE AT 207-624-3100 AND THE MAINE DEPARTMENT OF ENVIRONMENTAL PROTECTION (MDEP) AT 800-482-0777. WORK MAY ONLY CONTINUE WITH AUTHORIZATION FROM THE RESIDENT.

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION

2287700

WIN
22877.00

HIGHWAY PLANS

STATE OF MAINE
DEPARTMENT OF TRANSPORTATION
No. 423

SIGNATURE
4226

P.E. NUMBER
11/12/18

DATE

PROJ. MANAGER: DANIEL LORING
DESIGN-DETAILED
CHECKED-REVIEWED
DESIGN-DETAILED
REVISIONS 1
REVISIONS 2
REVISIONS 3
REVISIONS 4
FIELD CHANGES

DATE
8/2018
11/2018

BY
MSM
ALC

HERMON
COLDBROOK RD\ODLIN RD\EMERSON MILL RD

SIGNAL DETAILS

SHEET NUMBER
3
OF 4

