

**STATE OF MAINE**  
**MAINE DEPARTMENT OF TRANSPORTATION**  
Letter of Transmittal

**To:** Eytayo Andande, Highway Program  
Terry White, Geotechnical Highway Program  
Kate Maguire, Geotechnical Highway Program  
Cody Russell, Geotechnical Highway Program  
Audie Arbo, Environmental Office (Electronic Copy Only)  
Project Resident, Highway Program (Unknown as of 5/6/2019)

**Author:** Cody Russell, Geotechnical Highway Program

**Subject:** Geotechnical Design Report, Large Culvert, Waterford, Maine

**Document Type:** 24

**Date:** 5/6/2019

**Soils Report:** 2019-06

**Bridge #:** N/A

**Route:** 118

**WIN:** 021838.00

**Town:** Waterford

---

Attached is one (1) copy of Soils Report 2019-06, "GEOTECHNICAL DESIGN REPORT: For the Replacement of: LARGE CULVERT #940780, ROUTE 118, WATERFORD, MAINE" dated: April 30, 2019.

This report is available in TEDOCS as Document # 1787360.

att: 1 of 2019-06

**MAINE DEPARTMENT OF TRANSPORTATION  
HIGHWAY PROGRAM  
GEOTECHNICAL SECTION  
AUGUSTA, MAINE**

**GEOTECHNICAL DESIGN REPORT**

*For the Replacement of:*

**LARGE CULVERT #940780  
ROUTE 118  
WATERFORD, MAINE**

*Prepared by:*

Cody Russell, E.I.  
Assistant Geotechnical Engineer



*Reviewed by:*

Kathleen Maguire, P.E.  
Senior Geotechnical Engineer.

Oxford County

WIN 21838.00  
April 30, 2019

Soils Report 2019-06

## **PROJECT DETAILS**

The purpose of this Geotechnical Design Report is to present subsurface information and make geotechnical design and construction recommendations for the replacement of an existing approximately 41-foot long, 60-inch diameter corrugated metal pipe (CMP) large culvert (#940780) on Route 118 in Waterford. The existing culvert is in poor condition, with rust along the invert and seams. The culvert is located approximately 0.25 of a mile west of Hunt's Corner Road as shown in the attached Location Map. Route 118 is a Highway Corridor Priority 3 road.

The proposed replacement structure will be a 8-foot span by 6-foot rise by 84-foot long precast concrete box culvert on a skew of approximately 21 degrees to the roadway centerline. The invert of the proposed culvert is approximately 12 feet below the existing road grade at the roadway centerline. The invert of the proposed culvert will be lined with approximately 2 feet of Special Fill with rock bands to facilitate fish passage. The roadway embankment slopes at the proposed culvert inlet and outlet shall be no steeper than 2H:1V to protect against erosion.

## **SUBSURFACE INVESTIGATION**

One (1) boring (HB-WATF-101) and one (1) probe (HB-WATF-102) were drilled for this project by the MaineDOT drill crew using a trailer mounted drill rig. Exploration locations are shown on the attached Boring Location Plan & Interpretive Subsurface Profile with Boring Logs sheet. Details and sampling methods used, field data obtained, and soil and groundwater conditions encountered are shown on the attached boring logs.

The boring was drilled using solid stem auger, driven casing and open hole techniques. The probe was drilled using solid stem auger techniques. Soil samples were obtained in boring HB-WATF-101 at 5-foot intervals using Standard Penetration Test (SPT) methods. The MaineDOT drill rig is equipped with an automatic hammer to drive the split spoon. The MaineDOT calibrated automatic hammer delivers approximately 42 percent more energy during driving than the standard rope and cathead system. All N-values discussed in this report are corrected values ( $N_{60}$ ) computed by applying an average energy transfer factor of 0.854 to the raw field N-values. No soil samples were obtained in the probe.

The MaineDOT Geotechnical Team member selected the boring and probe locations, drilling methods, designated type and depth of sampling, reviewed field logs for accuracy and identified field and laboratory testing requirements. A NorthEast Transportation Training and Certification (NETTCP) certified Subsurface Investigator logged the subsurface conditions encountered. The boring and probe were located in the field by taping to surveyed site features after completion of the drilling program.

## **LABORATORY TESTING**

A laboratory testing program was conducted to assist in soil classification, evaluation of engineering properties of the soils and geologic assessment of the project site. Laboratory testing consisted of five (5) standard grain size analyses with natural water content. The results of the

laboratory testing program are discussed in the following section and are shown on the attached boring logs, Laboratory Testing Summary Sheet, and Grain Size Distribution Curve sheet.

**SUBSURFACE CONDITIONS**

Subsurface conditions encountered at the test boring generally consisted of fill overlying native sand. An interpretive subsurface profile depicting the generalized soil stratigraphy at the boring location is shown on the attached Boring Location Plan & Interpretive Subsurface Profile with Boring Logs sheet.

Boring HB-WATF-101 was drilled to a depth of approximately 22.0 feet below ground surface (bgs) and did not encounter a refusal surface. Probe HB-WATF-102 was drilled to a depth of approximately 20.5 feet bgs and did not encounter a refusal surface.

The table below summarizes the field and laboratory information obtained in boring HB-WATF-101:

Approx. Depth BGS <sup>1</sup> (feet)	Soil Description	AASHTO <sup>2</sup> Classification	USCS <sup>3</sup>	WC% <sup>4</sup>
0 – 0.3	Pavement	--	--	--
0.3 – 13.0	Fill: Brown, black, and grey-brown, moist to wet, fine to coarse sand, little gravel, trace to some silt, (Fill). Cobbles from 6.5 to 7.1 feet bgs. Wood from 10.5 to 11.4 feet bgs.	A-1-b	SP-SM, SM, or SP	7.7 to 34.5
13.0 – 22.0	Grey, wet, fine to coarse sand, trace to some gravel, trace silt.	A-1-b	SP	17.3 to 21.1

<sup>1</sup>BGS = below ground surface

<sup>2</sup>AASHTO = American Association of State Highway and Transportation Officials

<sup>3</sup>USCS = Unified Soil Classification System

<sup>4</sup>WC% = Water content in percent

Two (2) corrected N-values obtained in the fill sand ranged from 11 to 97 blows per foot (bpf) indicating that the fill sand medium dense to very dense in consistency. The N-values obtained in the fill sand were influenced by the presence of cobbles. Two (2) corrected N-values obtained in the native sand ranged from 10 to 17 bpf indicating that the native sand is loose to medium dense in consistency.

Groundwater was observed at a depth of approximately 7.5 feet bgs in boring HB-WATF-101 and approximately 8.1 feet bgs in probe HB-WATF-102. Groundwater levels can be expected to fluctuate subject to seasonal variations, local soil conditions, topography, precipitation, and construction activity.

## GEOTECHNICAL DESIGN AND CONSTRUCTION RECOMMENDATIONS

**Precast Concrete Box Culvert Construction** – The proposed replacement structure will be 8-foot span by 6-foot rise by 84-foot long precast concrete box culvert on a skew of approximately 21 degrees to the roadway centerline. The proposed box culvert shall be designed and constructed in accordance with MaineDOT Standard Specification 534. The proposed structure inlet and outlet slopes shall be riprapped with slopes no steeper than 2H:1V to protect against erosion.

The invert of the proposed box culvert ranges from approximately 479.62 feet at the inlet end to approximately 478.46 feet at the outlet end with a 1.4% slope. The culvert will be lined with approximately 2 feet of Special Fill with rock bands to facilitate fish passage.

The full nature of the proposed culvert bearing surface will not become evident until the culvert excavation is made. Any cobbles or boulders encountered in excess of 6 inches shall be removed and replaced with compacted Granular Borrow Material for Underwater Backfill or Crushed Stone ¾-Inch. The prepared subgrade shall be proof-rolled using a static roller to visually confirm the prepared subgrade is firm and stable. The exposed subgrade shall be free of ponded water so that bedding material placement and compaction can be completed in the dry.

The proposed structure shall be bedded on a 1-foot thick layer of Granular Borrow, Material for Underwater Backfill meeting the requirements of MaineDOT Standard Specification 703.19. The soil envelope and backfill shall consist of Standard Specification 703.19 - Granular Borrow with a maximum particle size of 4 inches. The granular borrow bedding and backfill material shall be placed in lifts of 6 to 8 inches loose measure and compacted to the manufacturer’s specifications or, in the absence of manufacturer’s specifications the bedding and backfill soil shall be compacted to at least 92 percent of the AASHTO T-180 maximum dry density. All subgrade surfaces should be protected from construction traffic in order to limit disturbance.

**Settlement** – No settlement issues are anticipated at the site. No changes to the existing vertical or horizontal alignment are currently planned for this project. The proposed precast concrete box culvert will be located on a new alignment and will result in a net unloading of the site soils at the proposed structure location. Any settlement due to elastic compression of the bedding material will be immediate and negligible.

**Bearing Resistance** – The factored bearing resistances for the precast concrete box culvert bearing on compacted granular bedding material placed on native soils at the service and strength limit states are presented in the table below. Supporting calculations in accordance with AASHTO LRFD Bridge Design Specifications 8<sup>th</sup> Edition 2017 (LRFD) are attached.

Limit State	Resistance Factor $\phi_b$	AASHTO LRFD Reference	Factored Bearing Resistance (ksf)
Service	1.0	Article 10.5.5.1	5.0
Strength	0.45	Table 10.5.5.2.2-1	5.0

**Modulus of Subgrade Reaction** – A modulus of subgrade reaction ( $k_s$ ) equal to 200 pounds per cubic inch shall be used for the structural design of the box culvert's base slab. Calculations are attached.

**Scour and Riprap** – Both the inlet and outlet of the RCP culvert shall be protected against scour with riprap conforming to MaineDOT Standard Specification Section 703.26 Plain and Hand Laid Riprap. Slopes shall be no steeper than 2H:1V. No specific scour protection recommendations are needed other than armoring with riprap. The riprap on the slopes shall be underlain by a non-woven, Class 1 Erosion Control Geotextile meeting the requirements of MaineDOT Standard Specification 722.03 that is underlain by a 1-foot layer of protective aggregate cushion consisting of Granular Borrow Material for Underwater Backfill (703.19). The toe of the riprap sections shall be keyed into the existing soils 1 foot below the streambed elevation.

**Construction Considerations** – Construction activities will include construction of cofferdams and earth support systems to control stream flow during construction. Construction activities will also include common earth excavation. Construction of the proposed precast concrete box culvert will require soil excavation. Earth support systems shall be implemented if laying back slopes is not feasible. It is likely that the use of complex (four-sided) braced excavations with dewatering will be necessary due to the depth of the excavation. If this is the case, adequate embedment into the native sand will be necessary to allow for the excavation and maintenance of a stable excavation bottom. All earth support systems shall be designed by a Professional Engineer licensed in the State of Maine. Regardless of the method of excavation, all excavations and earth support systems shall meet all applicable OSHA regulations.

Any cobbles or boulders encountered in excess of 6 inches shall be removed and replaced with compacted Granular Borrow Material for Underwater Backfill (MaineDOT 703.19) or Crushed Stone  $\frac{3}{4}$ -Inch (MaineDOT 703.13). All subgrade surfaces shall be proof-rolled using a static roller to provide a firm and stable surface and protected from any unnecessary construction equipment or traffic. If disturbance and rutting occur, the Contractor shall remove and replace disturbed areas with compacted Granular Borrow for Underwater Backfill (703.19) or Crushed Stone  $\frac{3}{4}$ -Inch (703.13).

The Contractor shall control groundwater and surface water infiltration using temporary ditches, sumps, granular drainage blankets, stone ditch protection or hand-laid riprap with geotextile underlayment to divert groundwater and surface water as needed to maintain a stable excavation and allow work in the dry.

Using the excavated native soils as backfill around the culvert shall not be permitted. The native soils may only be used as Common Borrow in accordance with MaineDOT Standard Specifications 203 and 703.

The Contractor will have to excavate the existing subbase and subgrade fill soils in the vicinity of the culvert. These materials should not be used to re-base the roadway. Excavated subbase sand and gravel may be used as fill below roadway subgrade level in fill areas provided all other requirements of MaineDOT Standard Specifications 203 and 703 are met.

## **CLOSURE**

This report has been prepared for the use of the MaineDOT Highway Program for specific application to the proposed replacement of large culvert #940780 under Route 118 in Waterford, Maine in accordance with generally accepted geotechnical and foundation engineering practices. No other intended use or warranty is expressed or implied.

In the event that any changes in the nature, design, or location of the proposed project are planned, this report should be reviewed by a geotechnical engineer to assess the appropriateness of the conclusions and recommendations and to modify the recommendations as appropriate to reflect the changes in design. These analyses and recommendations are based in part upon a limited subsurface investigation at discrete exploratory location completed at the site. If variations from the conditions encountered during the investigation appear evident during construction, it may also become necessary to re-evaluate the recommendations made in this report.


It is recommended that a geotechnical engineer be provided the opportunity for a review of the design and specifications in order that the earthwork and foundation recommendations and construction considerations presented in this report are properly interpreted and implemented in the design and specifications.

### **Attachments:**

Location Map  
Boring Location Plan & Interpretive Subsurface Profile with Boring Logs Sheet  
Key to Soil and Rock Descriptions and Terms  
Boring Logs  
Laboratory Testing Summary Sheet  
Grain Size Distribution Curves  
Calculations



# WATERFORD, MAINE



The Maine Department of Transportation provides this publication for information only. Reliance upon this information is at user risk. It is subject to revision and may be incomplete depending upon changing conditions. The Department assumes no liability if injuries or damages result from this information. This map is not intended to support emergency dispatch.

0.25 Miles  
1 inch = 0.27 miles

Date: 2/22/2019  
Time: 7:40:46 AM

SHEET NUMBER  <b>1</b>  OF 2	WATERFORD  ROUTE 118	STATE OF MAINE DEPARTMENT OF TRANSPORTATION	
		<b>021838.00</b>	
LOCATION MAP		<b>WIN</b> <b>21838.00</b>	HIGHWAY PLANS



UNIFIED SOIL CLASSIFICATION SYSTEM				MODIFIED BURMISTER SYSTEM																											
MAJOR DIVISIONS		GROUP SYMBOLS	TYPICAL NAMES	Descriptive Term	Portion of Total (%)																										
COARSE-GRAINED SOILS  (more than half of material is larger than No. 200 sieve size)	GRAVELS  (more than half of coarse fraction is larger than No. 4 sieve size)	CLEAN GRAVELS	GW Well-graded gravels, gravel-sand mixtures, little or no fines.	trace	0 - 10																										
		(little or no fines)	GP Poorly-graded gravels, gravel sand mixtures, little or no fines.	little	11 - 20																										
	SANDS  (more than half of coarse fraction is smaller than No. 4 sieve size)	GRAVEL WITH FINES (Appreciable amount of fines)	GM Silty gravels, gravel-sand-silt mixtures.	some	21 - 35																										
		CLEAN SANDS	SW Well-graded sands, gravelly sands, little or no fines	adjective (e.g. sandy, clayey)	36 - 50																										
		(little or no fines)	SP Poorly-graded sands, gravelly sand, little or no fines.	<b>TERMS DESCRIBING DENSITY/CONSISTENCY</b> <b>Coarse-grained soils</b> (more than half of material is larger than No. 200 sieve): Includes (1) clean gravels; (2) silty or clayey gravels; and (3) silty, clayey or gravelly sands. Density is rated according to standard penetration resistance (N-value).  <table border="1"> <thead> <tr> <th>Density of Cohesionless Soils</th> <th>Standard Penetration Resistance N-Value (blows per foot)</th> </tr> </thead> <tbody> <tr><td>Very loose</td><td>0 - 4</td></tr> <tr><td>Loose</td><td>5 - 10</td></tr> <tr><td>Medium Dense</td><td>11 - 30</td></tr> <tr><td>Dense</td><td>31 - 50</td></tr> <tr><td>Very Dense</td><td>&gt; 50</td></tr> </tbody> </table>		Density of Cohesionless Soils	Standard Penetration Resistance N-Value (blows per foot)	Very loose	0 - 4	Loose	5 - 10	Medium Dense	11 - 30	Dense	31 - 50	Very Dense	> 50														
		Density of Cohesionless Soils	Standard Penetration Resistance N-Value (blows per foot)																												
Very loose	0 - 4																														
Loose	5 - 10																														
Medium Dense	11 - 30																														
Dense	31 - 50																														
Very Dense	> 50																														
SANDS WITH FINES (Appreciable amount of fines)	SM Silty sands, sand-silt mixtures	<b>Fine-grained soils</b> (more than half of material is smaller than No. 200 sieve): Includes (1) inorganic and organic silts and clays; (2) gravelly, sandy or silty clays; and (3) clayey silts. Consistency is rated according to undrained shear strength as indicated.  <table border="1"> <thead> <tr> <th>Consistency of Cohesive soils</th> <th>SPT N-Value (blows per foot)</th> <th>Approximate Undrained Shear Strength (psf)</th> <th>Field Guidelines</th> </tr> </thead> <tbody> <tr><td>Very Soft</td><td>WOH, WOR, WOP, &lt;2</td><td>0 - 250</td><td>Fist easily penetrates</td></tr> <tr><td>Soft</td><td>2 - 4</td><td>250 - 500</td><td>Thumb easily penetrates</td></tr> <tr><td>Medium Stiff</td><td>5 - 8</td><td>500 - 1000</td><td>Thumb penetrates with moderate effort</td></tr> <tr><td>Stiff</td><td>9 - 15</td><td>1000 - 2000</td><td>Indented by thumb with great effort</td></tr> <tr><td>Very Stiff</td><td>16 - 30</td><td>2000 - 4000</td><td>Indented by thumbnail</td></tr> <tr><td>Hard</td><td>&gt;30</td><td>over 4000</td><td>Indented by thumbnail with difficulty</td></tr> </tbody> </table>		Consistency of Cohesive soils	SPT N-Value (blows per foot)	Approximate Undrained Shear Strength (psf)	Field Guidelines	Very Soft	WOH, WOR, WOP, <2	0 - 250	Fist easily penetrates	Soft	2 - 4	250 - 500	Thumb easily penetrates	Medium Stiff	5 - 8	500 - 1000	Thumb penetrates with moderate effort	Stiff	9 - 15	1000 - 2000	Indented by thumb with great effort	Very Stiff	16 - 30	2000 - 4000	Indented by thumbnail	Hard	>30	over 4000	Indented by thumbnail with difficulty
Consistency of Cohesive soils	SPT N-Value (blows per foot)			Approximate Undrained Shear Strength (psf)	Field Guidelines																										
Very Soft	WOH, WOR, WOP, <2	0 - 250	Fist easily penetrates																												
Soft	2 - 4	250 - 500	Thumb easily penetrates																												
Medium Stiff	5 - 8	500 - 1000	Thumb penetrates with moderate effort																												
Stiff	9 - 15	1000 - 2000	Indented by thumb with great effort																												
Very Stiff	16 - 30	2000 - 4000	Indented by thumbnail																												
Hard	>30	over 4000	Indented by thumbnail with difficulty																												
FINE-GRAINED SOILS  (more than half of material is smaller than No. 200 sieve size)	SILTS AND CLAYS  (liquid limit less than 50)	ML Inorganic silts and very fine sands, rock flour, silty or clayey fine sands, or clayey silts with slight plasticity.	<b>Rock Quality Designation (RQD):</b> RQD (%) = $\frac{\text{sum of the lengths of intact pieces of core} * > 4 \text{ inches}}{\text{length of core advance}}$ *Minimum NQ rock core (1.88 in. OD of core)  Correlation of RQD to Rock Mass Quality <table border="1"> <thead> <tr> <th>Rock Mass Quality</th> <th>RQD (%)</th> </tr> </thead> <tbody> <tr><td>Very Poor</td><td>≤25</td></tr> <tr><td>Poor</td><td>26 - 50</td></tr> <tr><td>Fair</td><td>51 - 75</td></tr> <tr><td>Good</td><td>76 - 90</td></tr> <tr><td>Excellent</td><td>91 - 100</td></tr> </tbody> </table>			Rock Mass Quality	RQD (%)	Very Poor	≤25	Poor	26 - 50	Fair	51 - 75	Good	76 - 90	Excellent	91 - 100														
		Rock Mass Quality				RQD (%)																									
		Very Poor				≤25																									
	Poor	26 - 50																													
Fair	51 - 75																														
Good	76 - 90																														
Excellent	91 - 100																														
CL Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays.																															
OL Organic silts and organic silty clays of low plasticity.																															
SILTS AND CLAYS  (liquid limit greater than 50)	MH Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts.	<b>Desired Rock Observations (in this order, if applicable):</b> Color (Munsell color chart) Texture (aphanitic, fine-grained, etc.) Rock Type (granite, schist, sandstone, etc.) Hardness (very hard, hard, mod. hard, etc.) Weathering (fresh, very slight, slight, moderate, mod. severe, severe, etc.)  Geologic discontinuities/jointing: -dip (horiz - 0-5 deg., low angle - 5-35 deg., mod. dipping - 35-55 deg., steep - 55-85 deg., vertical - 85-90 deg.) -spacing (very close - <2 inch, close - 2-12 inch, mod. close - 1-3 feet, wide - 3-10 feet, very wide >10 feet) -tightness (tight, open, or healed) -infilling (grain size, color, etc.) Formation (Waterville, Ellsworth, Cape Elizabeth, etc.) RQD and correlation to rock mass quality (very poor, poor, etc.) ref: ASTM D6032 and AASHTO Standard Specification for Highway Bridges, 17th Ed. Table 4.4.8.1.2A Recovery (inch/inch and percentage) Rock Core Rate (X.X ft - Y.Y ft (min:sec))																													
	CH Inorganic clays of high plasticity, fat clays.																														
	OH Organic clays of medium to high plasticity, organic silts.																														
HIGHLY ORGANIC SOILS	Pt Peat and other highly organic soils.																														
<b>Desired Soil Observations (in this order, if applicable):</b> Color (Munsell color chart) Moisture (dry, damp, moist, wet) Density/Consistency (from above right hand side) Texture (fine, medium, coarse, etc.) Name (sand, silty sand, clay, etc., including portions - trace, little, etc.) Gradation (well-graded, poorly-graded, uniform, etc.) Plasticity (non-plastic, slightly plastic, moderately plastic, highly plastic) Structure (layering, fractures, cracks, etc.) Bonding (well, moderately, loosely, etc., ) Cementation (weak, moderate, or strong) Geologic Origin (till, marine clay, alluvium, etc.) Groundwater level				<b>Sample Container Labeling Requirements:</b> WIN Blow Counts Bridge Name / Town Sample Recovery Boring Number Date Sample Number Personnel Initials Sample Depth																											
<b>Maine Department of Transportation  Geotechnical Section  Key to Soil and Rock Descriptions and Terms  Field Identification Information</b>																															

<b>Maine Department of Transportation</b> Soil/Rock Exploration Log US CUSTOMARY UNITS				Project: Route 118 Large Culvert Location: Waterford, Maine				Boring No.: HB-WATF-101 WIN: 21838.00							
Driller: MaineDOT				Elevation (ft.): 488.2				Auger ID/OD: 5" Solid Stem							
Operator: Daggett				Datum: NAVD88				Sampler: Standard Split Spoon							
Logged By: B. Wilder				Rig Type: CME 45C				Hammer Wt./Fall: 140#/30"							
Date Start/Finish: 2/28/2018; 08:30-11:30				Drilling Method: Cased Wash Boring				Core Barrel: N/A							
Boring Location: 14+33.2, 8.8 ft Rt.				Casing ID/OD: NW-3"				Water Level*: 7.5 ft bgs.							
Hammer Efficiency Factor: 0.854				Hammer Type: Automatic <input checked="" type="checkbox"/> Hydraulic <input type="checkbox"/> Rope & Cathead <input type="checkbox"/>											
Definitions: D = Split Spoon Sample MD = Unsuccessful Split Spoon Sample Attempt U = Thin Wall Tube Sample MU = Unsuccessful Thin Wall Tube Sample Attempt V = Field Vane Shear Test, PP = Pocket Penetrometer MV = Unsuccessful Field Vane Shear Test Attempt				R = Rock Core Sample SSA = Solid Stem Auger HSA = Hollow Stem Auger RC = Roller Cone WOH = Weight of 140lb. Hammer WOR/C = Weight of Rods or Casing WO1P = Weight of One Person				S <sub>u</sub> = Peak/Remolded Field Vane Undrained Shear Strength (psf) S <sub>u(lab)</sub> = Lab Vane Undrained Shear Strength (psf) q <sub>p</sub> = Unconfined Compressive Strength (ksf) N-uncorrected = Raw Field SPT N-value Hammer Efficiency Factor = Rig Specific Annual Calibration Value N <sub>60</sub> = SPT N-uncorrected Corrected for Hammer Efficiency N <sub>60</sub> = (Hammer Efficiency Factor/60%)*N-uncorrected				T <sub>v</sub> = Pocket Torvane Shear Strength (psf) WC = Water Content, percent LL = Liquid Limit PL = Plastic Limit PI = Plasticity Index G = Grain Size Analysis C = Consolidation Test			
Depth (ft.)	Sample Information								Elevation (ft.)	Graphic Log	Visual Description and Remarks	Laboratory Testing Results/ AASHTO and Unified Class.			
	Sample No.	Pen./Rec. (in.)	Sample Depth (ft.)	Blows (/6 in.) Shear Strength (psf) or RQD (%)	N-uncorrected	N <sub>60</sub>	Casing Blows								
0								SSA	487.9	4" HMA.					
	1D	24/14	1.50 - 3.50	19/39/29/19	68	97				Brown, black, moist, very dense, fine to coarse SAND, little gravel, trace silt, (Fill).	G#303132 A-1-b, SP-SM WC=7.7%				
										Layer of Large Cobbles (3.0-5.0") from 4.0-6.0 ft bgs.					
5	2D	6/6	5.00 - 5.50	50	---					Brown, moist, very dense, fine to coarse SAND, some silt, little gravel, (Fill).	G#303133 A-1-b, SM WC=20.4%				
										Cobble from 6.5-7.1 ft bgs.					
10	3D	24/16	10.00 - 12.00	2/4/4/5	8	11	7		475.2	Grey-brown, wet, medium dense, fine to coarse SAND, little gravel, trace silt, wood from 10.5-11.4 ft bgs), (Fill).	G#303134 A-1-b, SP WC=34.5%				
15	4D	24/15	15.00 - 17.00	3/3/4/4	7	10	OPEN HOLE			Grey, wet, loose, fine to coarse SAND, trace gravel, trace silt.	G#303135 A-1-b, SP WC=21.1%				
20	5D	24/12	20.00 - 22.00	4/5/7/7	12	17			466.2	Grey, wet, medium dense, fine to coarse SAND, some gravel, trace silt.	G#303136 A-1-b, SP WC=17.3%				
25										<b>Bottom of Exploration at 22.0 feet below ground surface.</b> NO REFUSAL					

**Remarks:**


Stratification lines represent approximate boundaries between soil types; transitions may be gradual.

\* Water level readings have been made at times and under conditions stated. Groundwater fluctuations may occur due to conditions other than those present at the time measurements were made.





**State of Maine Department of Transportation**  
**GRAIN SIZE DISTRIBUTION CURVE**



	Boring/Sample No.	Station	Offset, ft	Depth, ft	Description	W, %	LL	PL	PI
+	HB-WATF-101/1D	14+33.2	8.8 RT	1.5-3.5	SAND, little gravel, trace silt.	7.7			
◆	HB-WATF-101/2D	14+33.2	8.8 RT	5.0-5.5	SAND, little gravel, some silt.	20.4			
■	HB-WATF-101/3D	14+33.2	8.8 RT	10.0-12.0	SAND, little gravel, trace silt.	34.5			
●	HB-WATF-101/4D	14+33.2	8.8 RT	15.0-17.0	SAND, trace gravel, trace silt.	21.1			
▲	HB-WATF-101/5D	14+33.2	8.8 RT	20.0-22.0	SAND, some gravel, trace silt.	17.3			
×									

WIN	
021838.00	
Town	
Waterford	
Reported by/Date	
WHITE, TERRY A	4/4/2018

## Bearing Resistance - Existing Soils:

### Part 1 - Service Limit State

#### Nominal and factored Bearing Resistance - Box Culvert on Sand

#### Presumptive Bearing Resistance for Service Limit State ONLY

Reference: AASHTO LRFD Bridge Design Specifications 8th Edition 2017  
Table C10.6.2.6.1-1 Presumptive Bearing Resistances for Spread Footings at the  
Service Limit State Modified after US Department of Navy (1982)

Type of Bearing Material: sand (SP)

Based on N-values, soils are medium dense at the bearing elevation

Density In Place: medium dense

Bearing Resistance: Ordinary Range (ksf) 4 to 8

**Recommended Value of Use:**

$$q_{nom} := 5 \cdot ksf$$

Resistance factor at the **service limit state** = 1.0 (LRFD Article 10.5.5.1)

$$\phi_{service\_bc} := 1.0$$

$$q_{factored\_service\_bc} := q_{nom} \cdot \phi_{service\_bc}$$

$$q_{factored\_service\_bc} = 5 \cdot ksf$$

*Note: This bearing resistance is settlement limited (1 inch) and applies only at the service limit state.*

### Part 2 - Strength Limit State

#### Nominal and factored Bearing Resistance - Box Culvert on Sand

Reference: AASHTO LRFD Bridge Design Specifications 8th Edition 2017 - Article 10.6.3.1

Assumptions:

1. The box will be founded at ~ Elev 479.6 feet to 478.5 feet

Bottom of Construction will be 2 feet below box invert

$$D_{footing} := 2.0 \cdot ft$$

2. Assumed parameters for fill soils:

Saturated unit weight:  $\gamma_s := 125 \cdot pcf$

Internal friction angle:  $\phi_{ns} := 32 \cdot deg$

Undrained shear strength:  $c_{ns} := 0 \cdot psf$

3. Box Culvert parameters

Width of box culvert, B  $B_{box} := 8 \cdot ft$

Length of box culvert, L  $L_{box} := 84 \cdot ft$

Nominal Bearing Resistance per LRFD Equation 10.6.3.1.2a-1

$$q_n = cN_{cm} + \gamma D_f N_{qm} C_{wq} + 0.5\gamma B N_{\gamma m} C_{w\gamma}$$

Bearing Capacity Factors - LRFD Table 10.6.3.1.2a-1

For  $\phi=32$  deg      $N_c := 35.5$                        $N_q := 23.2$                        $N_\gamma := 30.2$

Shape Correction Factors LRFD Table 10.6.3.1.2a-3

for  $\phi=32$  degrees

$$s_c := 1 + \left( \frac{B_{\text{box}}}{L_{\text{box}}} \right) \left( \frac{N_q}{N_c} \right) \quad s_c = 1.06$$

$$s_\gamma := 1 - 0.4 \left( \frac{B_{\text{box}}}{L_{\text{box}}} \right) \quad s_\gamma = 0.9619$$

$$s_q := 1 + \left( \frac{B_{\text{box}}}{L_{\text{box}}} \cdot \tan(\phi_{ns}) \right) \quad s_q = 1.06$$

Load Inclination Factors:

Assume all are 1.0 (LRFD Article C10.6.3.1.2a)

$i_c := 1.0$                        $i_q := 1.0$                        $i_\gamma := 1.0$

Depth Correction Factor LRFD Table 10.6.3.1.2a-4

$$\frac{D_{\text{footing}}}{B_{\text{box}}} = 0.25 \quad \text{for } \phi=32 \text{ degrees} \quad d_q := 1.2$$

$$N_{cm} := N_c \cdot s_c \cdot i_c \quad N_{cm} = 37.7095 \quad \text{LRFD Eq. 10.6.3.1.2a-2}$$

$$N_{qm} := N_q \cdot s_q \cdot d_q \cdot i_q \quad N_{qm} = 29.5 \quad \text{LRFD Eq. 10.6.3.1.2a-3}$$

$$N_{\gamma m} := N_\gamma \cdot s_\gamma \cdot i_\gamma \quad N_{\gamma m} = 29.05 \quad \text{LRFD Eq. 10.6.3.1.2a-4}$$

Coefficients for Groundwater Depths LRFD Table 10.6.3.1.2a-2

Depth the water table:  $D_w := 0 \cdot \text{ft}$                        $C_{wq} := 0.5$                        $C_{w\gamma} := 0.5$

$$q_{\text{nominal}} := c_{ns} \cdot N_{cm} + \gamma_s \cdot D_{\text{footing}} \cdot N_{qm} \cdot C_{wq} + 0.5(\gamma_s) B_{\text{box}} \cdot N_{\gamma m} \cdot C_{w\gamma}$$

$$q_{\text{nominal}} = 10.9 \cdot \text{ksf}$$

**Factored Bearing Resistance for Strength Limit State**

Resistance Factor:      $\phi_b := 0.45$                       LRFD Table 10.5.5.2.2-1

$$q_{\text{factored}} := q_{\text{nominal}} \cdot \phi_b$$

$$q_{\text{factored}} = 4.9 \cdot \text{ksf}$$

Recommend a limiting factored bearing resistance of 5.0 ksf for the Strength Limit State.

## Modulus of Subgrade Reaction:

Reference: Foundation Analysis and Design 5th Edition JE Bowles Section 9-6

Width of box culvert, B  $B_{\text{box}} := 8 \cdot \text{ft}$   
 Length of box culvert, L  $L_{\text{box}} := 84 \cdot \text{ft}$   
 Thickness of box culvert, t  $t_{\text{box}} := 12 \cdot \text{in}$  assumed  
 Depth of box, D  $D_{\text{box}} := 12 \cdot \text{ft}$   
 Bearing Resistance:  $q_{\text{factored\_service\_bc}} = 5 \cdot \text{ksf}$  Calculated above  
 Modulus of Elasticity: Site soils at bearing elevation are Sand (medium dense)  
 From Bowles Table 2-8 Modulus  $E_s$  for sand and gravel, loose ranges from 1000 - 3100 ksf

Use Modulus of Elasticity,  $E_s := 1200 \cdot \text{ksf}$   
 Poisson's Ratio: Site soils are Sand (medium dense)  
 From Bowles Table 2-7 Poisson's Ratio  $\mu$  for Sand/Till ranges from 0.3 - 0.35  
 Use Poisson's Ratio,  $\mu := 0.35$

$$E_{\text{prime\_s}} := \frac{1 - \mu^2}{E_s} \quad E_{\text{prime\_s}} = 0.000731 \cdot \frac{\text{ft}^2}{\text{kip}}$$

Analyze corner:

Take H as 5\*B as recommended in Bowles Chapter 5

$$H_{\text{inf}} := \frac{5 \cdot B_{\text{box}}}{B_{\text{box}}} \quad H_{\text{inf}} = 5 \quad \text{N in Table 5-2} \quad \text{From Table 5-2 for N=5 and M=6.5}$$

$$\frac{L_{\text{box}}}{B_{\text{box}}} = 10.5 \quad \text{M in Table 5-2} \quad I_1 := 0.534$$

$$I_2 := 0.140 \quad \text{by interpolation}$$

Determine Steinbrenner influence factor - Bowles Section 5-6:

$$I_s := I_1 + \left[ \frac{1 - (2 \cdot \mu)}{1 - \mu} \right] \cdot I_2 \quad I_s = 0.5986$$

Determine Influence factor for footing depth - Bowles Figure 5-7

$$\text{Depth ratio: } \frac{D_{\text{box}}}{B_{\text{box}}} = 1.5 \quad \frac{L_{\text{box}}}{B_{\text{box}}} = 10.5 \quad \mu = 0.35 \quad I_F := 0.82$$

Calculate modulus of subgrade reaction - Bowles Eq. 9-7

$$k_s := \frac{1}{B_{\text{box}} \cdot E_{\text{prime\_s}} \cdot I_s \cdot I_F} \quad \text{Bowles Eq. 9-7}$$

$$k_s = 202 \cdot \text{pci}$$

Recommend Modulus of Subgrade Reaction of 200 pci