


**MAINE DEPARTMENT OF TRANSPORTATION
HIGHWAY PROGRAM
GEOTECHNICAL SECTION
AUGUSTA, MAINE**

GEOTECHNICAL DESIGN REPORT

For the Construction of:

**LINDSEY BROOK BRIDGE
ROUTE 6
CARROLL PLANTATION, MAINE**

Prepared by:
Cody Russell, P.E.
Geotechnical Engineer



Reviewed by:
Kathleen Maguire, P.E.
Senior Geotechnical Engineer

Penobscot County
WIN 23581.00

February 26, 2021

Soils Report 2021-09
Bridge No. 6601

Table of Contents

1.0 INTRODUCTION 2

2.0 GEOLOGIC SETTING 2

3.0 SUBSURFACE INVESTIGATION..... 2

4.0 LABORATORY TESTING..... 3

5.0 SUBSURFACE CONDITIONS..... 3

6.0 GEOTECHNICAL DESIGN AND CONSTRUCTION RECOMMENDATIONS ... 4

 6.1 PRECAST CONCRETE BOX CULVERT DESIGN AND CONSTRUCTION 4

 6.2 SETTLEMENT 5

 6.3 BEARING RESISTANCE 5

 6.4 MODULUS OF SUBGRADE REACTION 6

 6.5 SCOUR AND RIPRAP 6

 6.6 SEISMIC DESIGN CONSIDERATIONS 6

 6.7 CONSTRUCTION CONSIDERATIONS 6

7.0 CLOSURE..... 7

Sheets

Sheet 1 - Location Map

Sheet 2 - Boring Location Plan & Interpretive Subsurface Profile with Boring Logs

Appendices

Appendix A - Boring Logs

Appendix B - Laboratory Test Results

Appendix C - Calculations

1.0 INTRODUCTION

The purpose of this Geotechnical Design Report is to present subsurface information and make geotechnical recommendations for the replacement of an existing large culvert (#979262) on Route 6 in Carroll Plantation, Maine. A subsurface investigation has been completed at the site to evaluate subsurface conditions and to develop geotechnical design and construction recommendations for the replacement structure. This report presents the subsurface information obtained during the subsurface investigation and soil laboratory testing programs and provides design and construction recommendations and geotechnical design parameters for the culvert replacement.

The existing structure consists of an approximately 9-foot span by 8-foot rise concrete box culvert with metal plate arch extension on the upstream end with a total length of approximately 58 feet. The metal plate arch portion has experienced rusting and section loss. Route 6 is a Highway Corridor Priority 3 road.

The proposed replacement structure will be a 14-foot span by 7-foot rise by 92-foot long precast concrete box culvert. To facilitate fish passage, Habitat Connectivity Design elements will be used inside the precast concrete box culvert as shown on the Special Details Sheet in the Plans. The invert of the proposed culvert is approximately 14.0 feet below the existing road grade at the roadway centerline. The roadway embankment slopes at the proposed culvert inlet and outlet shall be no steeper than 2H:1V to protect against erosion.

2.0 GEOLOGIC SETTING

The existing culvert carries Lindsey Brook under Route 6 in Carroll Plantation and is located approximately 1.38 miles north of the Kossuth Township town line as shown on Sheet 1 – Location Map.

According to the Maine Geological Survey (MGS) map titled Surficial Geology of the Fredericton 1° x 2° Quadrangle, Maine, Open File 87-13 (1987) the surficial soils at the site consist of Till. Till consists of a mixture of sand, silt, clay, and cobbles with the possible presence of boulders.

According to the map titled Bedrock Geologic Map of Maine (1985) published by the MGS, the bedrock in the vicinity of the site consists of unnamed Rhyolitic volcanic rocks.

3.0 SUBSURFACE INVESTIGATION

One (1) boring (HB-CAR-101) and one (1) probe (HB-CAR-102) were drilled on opposite, diagonal corners of the existing structure on September 10, 2018 by the MaineDOT drill crew using a trailer mounted drill rig. Exploration locations are shown on Sheet 2 – Boring Location Plan & Interpretive Subsurface Profile with Borings Logs. Details and sampling methods used, field data obtained, and soil and groundwater conditions encountered are presented on the Boring Logs in Appendix A.

Boring HB-CAR-101 was drilled using solid stem auger, cased wash boring, and open hole drilling techniques. Soil samples were obtained in boring HB-CAR-101 at 5-foot intervals using Standard Penetration Test (SPT) methods. The MaineDOT drill rig is equipped with an automatic hammer to drive the split spoon. The MaineDOT calibrated automatic hammer delivers approximately 54 percent more energy during driving than the standard rope and cathead system. All N-values discussed in this report are corrected values (N_{60}) computed by applying an average energy transfer factor of 0.928 to the raw field N-values. Probe HB-CAR-102 was drilled using solid stem auger techniques. No soil samples were obtained in the probe.

The MaineDOT Geotechnical Team member selected the boring and probe locations, drilling methods, designated type and depth of sampling, reviewed field logs for accuracy and identified field and laboratory testing requirements. A NorthEast Transportation Training and Certification (NETTCP) certified Subsurface Investigator logged the subsurface conditions encountered in the boring and probe. The boring and probe were located in the field by taping to surveyed site features after completion of the drilling program.

4.0 LABORATORY TESTING

A laboratory testing program was conducted to assist in soil classification, evaluation of engineering properties of the soils and geologic assessment of the project site. Laboratory testing consisted of three (3) standard grain size analysis with natural water content and two (2) standard grain size analyses with hydrometer and natural water content. The results of the laboratory testing program are discussed in the following section and are included in Appendix B – Laboratory Test Results. Laboratory test information is also shown on the Boring Logs in Appendix A.

5.0 SUBSURFACE CONDITIONS

Subsurface conditions encountered at the test boring and probe generally consisted fill sandy gravel and gravelly sand underlain by native sand underlain by native silt till. An interpretive subsurface profile depicting the generalized soil stratigraphy at the boring location is shown on Sheet 2 – Boring Location Plan & Interpretive Subsurface Profile with Boring Logs.

Boring HB-CAR-101 was drilled to a depth of approximately 22.0 feet below ground surface (bgs) and did not encounter a refusal surface. Probe HB-CAR-102 was drilled to a depth of approximately 20.5 feet bgs and did not encounter a refusal surface.

The table below summarizes the field and laboratory information obtained in boring HB-CAR-101:

Approx. Depth BGS ¹ (feet)	Soil Description	AASHTO ² Classification	USCS ³	WC% ⁴
0.0 – 0.8	Pavement	--	--	--
0.8 – 9.5	Fill – Brown, dry, fine to coarse sandy gravel, trace silt.	A-1-a	GW-GM	3.3
	Brown, damp, gravelly fine to coarse sand, little silt.	A-1-a	SM	3.3
9.5 – 12.7	Grey, wet, fine to coarse sand, some gravel, little silt. Cobbles 11.2 to 12.7 feet bgs	A-1-b	SM	12.2
12.7 – 22.0	Till – Olive-grey, wet, silt, little to some clay, little to some fine to coarse sand, trace gravel.	A-4	CL	13.3 to 18.0

¹BGS = below ground surface

²AASHTO = American Association of State Highway and Transportation Officials

³USCS = Unified Soil Classification System

⁴WC% = Water content in percent

Two (2) corrected N-values obtained in the fill were 19 and 45 blows per foot (bpf) indicating that the fill is medium dense to very dense in consistency. No corrected N-values were obtained in the native sand layer due to the presence of cobbles. Two (2) corrected N-values obtained in the till were 29 and 31 bpf indicating that the till is very stiff to hard in consistency.

Groundwater level was recorded at a depth of approximately 6.0 feet bgs in boring HB-CAR-101. Groundwater level was not recorded in the probe. Groundwater levels can be expected to fluctuate subject to seasonal variations, local soil conditions, topography, precipitation, and construction activity.

6.0 GEOTECHNICAL DESIGN AND CONSTRUCTION RECOMMENDATIONS

The proposed replacement structure will consist of a 14-foot span by 7-foot rise by 92-foot long precast concrete box culvert. The proposed structure inlet and outlet slopes shall be riprapped with slopes no steeper than 2H:1V to protect against erosion. The following sections discuss geotechnical recommendations for the design and construction of the proposed culvert.

6.1 Precast Concrete Box Culvert Design and Construction

The proposed replacement structure will consist of a 14-foot span by 7-foot rise by 92-foot long precast concrete box culvert. The proposed box culvert shall be designed and constructed in accordance with MaineDOT Standard Specification 534.

The elevation of the proposed box culvert is set at approximately 501.5 feet. To facilitate fish passage, Habitat Connectivity Design elements will be used inside the precast concrete box culvert as shown on the Streambed Details Sheets in the Plans.

The full nature of the culvert bearing surface will not become evident until the culvert excavation is made. Any cobbles or boulders in excess of 6 inches encountered at the bedding elevation shall be removed and replaced with compacted Granular Borrow Material for Underwater Backfill or Crushed Stone ¾-Inch. Any disturbed soils at the bedding elevation resulting from excavation activities should be removed by hand prior to placement of the bedding material. The prepared subgrade shall be proofrolled using a static roller to visually confirm the prepared subgrade is firm and stable. The exposed subgrade shall be free of ponded water so that bedding material placement and compaction can be completed in the dry.

The proposed structure shall be bedded on a 1-foot thick layer of Granular Borrow, Material for Underwater Backfill meeting the requirements of MaineDOT Standard Specification 703.19. The soil envelope and backfill shall consist of Standard Specification 703.19 - Granular Borrow with a maximum particle size of 4 inches. The Granular Borrow bedding and backfill material shall be placed in lifts of 6 to 8 inches loose measure and compacted to the manufacturer’s specifications or, in the absence of manufacturer’s specifications, the bedding and backfill soil shall be compacted to at least 92 percent of the AASHTO T-180 maximum dry density.

6.2 Settlement

No settlement issues are anticipated at the site. The proposed precast concrete box culvert is larger than the existing culvert and will result in a net unloading of the site soils at the structure location. Placement of fill soils at the location of the existing structure is not anticipated to exceed the past loading condition of the site soils. Any settlement due to elastic compression of the subgrade soils and bedding material will be immediate and negligible.

6.3 Bearing Resistance

The factored bearing resistances for the precast concrete box culvert bearing on compacted granular bedding material placed on native soils at the service and strength limit states are presented in the table below. Supporting calculations in accordance with AASHTO LRFD Bridge Design Specifications 9th Edition 2020 (LRFD) are provided in Appendix C – Calculations.

Limit State	Resistance Factor ϕ_b	AASHTO LRFD Reference	Factored Bearing Resistance (ksf)
Service	1.0	Article 10.5.5.1	8.0
Strength	0.45	Table 10.5.5.2.2-1	10.0

6.4 Modulus of Subgrade Reaction

A modulus of subgrade reaction (k_s) equal to 330 pounds per cubic inch shall be used for the structural design of the box culvert's base slab. Calculations are included in Appendix C – Calculations.

6.5 Scour and Riprap

Both the inlet and outlet of the precast concrete box culvert shall be protected against scour with riprap conforming to MaineDOT Standard Specification Section 703.26 Plain and Hand Laid Riprap. Slopes shall be no steeper than 2H:1V. No specific scour protection recommendations are needed other than armoring with riprap. The riprap on the slopes shall be underlain by a non-woven, Class 1 Erosion Control Geotextile meeting the requirements of MaineDOT Standard Specification 722.03 that is underlain by a 1-foot layer of protective aggregate cushion consisting of Granular Borrow Material for Underwater Backfill (703.19). The toe of the riprap sections shall be keyed into the existing soils 1 foot below the streambed elevation.

6.6 Seismic Design Considerations

In conformance with LRFD Article 3.10.1, seismic analysis is not required for buried structures, except where they cross active faults. There are no known active faults in Maine; therefore, seismic analysis is not required.

6.7 Construction Considerations

Construction activities may include construction of cofferdams and earth support systems to control stream flow during construction. Construction activities will also include common earth excavation. Construction of the proposed precast concrete box culvert will require deep soil excavation. Earth support systems shall be implemented if laying back slopes is not feasible. It is likely that the use of complex (four-sided) braced excavations with dewatering will be necessary due to the depth of the excavation. If this is the case, adequate embedment into native silts will be necessary to allow for the excavation and maintenance of a stable excavation bottom. All earth support systems shall be designed by a Professional Engineer licensed in the State of Maine. Regardless of the method of excavation, all excavations and earth support systems shall meet all applicable OSHA regulations.

The Contractor shall control groundwater and surface water infiltration using temporary ditches, sumps, granular drainage blankets, stone ditch protection or hand-laid riprap with geotextile underlayment to divert groundwater and surface water as needed to maintain a stable excavation and allow work in the dry.

Using the excavated native soils as backfill around the culvert shall not be permitted. The native soils may only be used as common borrow in accordance with MaineDOT Standard Specifications 203 and 703.

The Contractor will have to excavate the existing subbase and subgrade fill soils in the vicinity of the culvert. These materials should not be used to re-base the roadway. Excavated subbase sand and gravel may be used as fill below roadway subgrade level in fill areas provided all other requirements of MaineDOT Standard Specifications 203 and 703 are met.

7.0 CLOSURE

This report has been prepared for the use of the MaineDOT Highway Program for specific application to the proposed replacement of an existing large culvert (#979262) under Route 6 in Carroll Plantation, Maine in accordance with generally accepted geotechnical and foundation engineering practices. No other intended use or warranty is expressed or implied.


In the event that any changes in the nature, design, or location of the proposed project are planned, this report should be reviewed by a geotechnical engineer to assess the appropriateness of the conclusions and recommendations and to modify the recommendations as appropriate to reflect the changes in design. These analyses and recommendations are based in part upon a limited subsurface investigation at discrete exploratory location completed at the site. If variations from the conditions encountered during the investigation appear evident during construction, it may also become necessary to re-evaluate the recommendations made in this report.

It is recommended that a geotechnical engineer be provided the opportunity for a review of the design and specifications in order that the earthwork and foundation recommendations and construction considerations presented in this report are properly interpreted and implemented in the design and specifications.

Sheets



CARROLL PLT., MAINE




The Maine Department of Transportation provides this publication for information only. Reliance upon this information is at user risk. It is subject to revision and may be incomplete depending upon changing conditions. The Department assumes no liability if injuries or damages result from this information. This map is not intended to support emergency dispatch.



0.25 Miles
1 inch = 0.28 miles

Date: 2/12/2021
Time: 9:41:30 AM

SHEET NUMBER 1 OF 2	CARROLL PLT. ROUTE 6	STATE OF MAINE DEPARTMENT OF TRANSPORTATION	
		23581.00	
	LOCATION MAP	WIN 23581.00	



CURVE DATA #1
 PI = 72+44.15
 D = 6°00'00.0"
 Δ = 66°14'00.0" Lt.
 R = 954.93'
 L = 1103.89'
 T = 622.91'
 E = 185.20'



Note: This generalized interpretive soil profile is intended to convey trends in subsurface conditions. The boundaries between strata are approximate and idealized, and have been developed by interpretations of widely spaced explorations and samples. Actual soil and bedrock transitions may vary and are probably more erratic. For more specific information refer to the exploration logs.

Maine Department of Transportation Soil/Rock Exploration Log US CUSTOMER UNITS		Project: Large Culvert Replacement on Route 6 Location: Carroll Plantation, Maine		Boring No.: HB-CAR-101 WIN: 23581.00																																																																	
Drilling Contractor: M&I/NEI	Elevation (ft.): 514.7	Auger (ft/ft): 5" Solid Stem	Operator: Doggett/NEI	Soil: NAVD83	Sampler: Standard Split Spoon																																																																
Logged By: B. W. Fisher	Rig Type: CME 45C	Home: WT, Falls 140R/30"	Date Start/Finish: 9/10/2018 09:00-12:30	Drilling Method: Cased Wash Boring	Core Barrels: N/A																																																																
Boring Location: 74+13.4, 10.6 ft Lt.	Coring (ft/ft): N/A	Water Levels: 6.0 ft bgs.	Home Efficiency Factor: 0.928	Home Type: Automatic	Rope & Catcher: C																																																																
<table border="1"> <thead> <tr> <th>Depth (ft.)</th> <th>Sample No.</th> <th>Pen./Rec. (ft.)</th> <th>Sample Depth (ft.)</th> <th>Blow (1/8 in. Strain) (ft/ft)</th> <th>Soil Description</th> <th>Visual Description and Remarks</th> <th>Laboratory Testing Results (ASHTO and Unified Class)</th> </tr> </thead> <tbody> <tr> <td>0</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>3" S&A</td> <td></td> </tr> <tr> <td>10</td> <td>24/16</td> <td>1.50 - 5.50</td> <td>10/17/12/12</td> <td>29 45</td> <td></td> <td>Brown, dry, very dense, fine to coarse SANDY GRAVEL, trace silt. (FILL).</td> <td>GH29624 A=10, SC=4 UC=15, 35</td> </tr> <tr> <td>5</td> <td>20</td> <td>24/13</td> <td>5.00 - 7.00</td> <td>9/6/9</td> <td>12 19 33</td> <td>Brown, comp. medium dense, gravelly fine to coarse SAND, little silt. (FILL).</td> <td>GH29625 A=10, SC=4 UC=15, 35</td> </tr> <tr> <td>10</td> <td>30</td> <td>14.4/11</td> <td>10.00 - 11.20</td> <td>8/9/10(2,4)'</td> <td>---</td> <td>Grey, wet, dense, fine to coarse SAND, some gravel, little silt. Layer of Cobbles from 11.2-12.7 ft bgs.</td> <td>GH29626 A=10, SC=4 UC=15, 35</td> </tr> <tr> <td>15</td> <td>40</td> <td>24/14</td> <td>15.00 - 17.00</td> <td>7/10/10/12</td> <td>20 31</td> <td>Olive-grey, wet, hard, SILT, some clay, little fine to coarse sand, trace gravel. (TIII).</td> <td>GH29627 A=4, CL UC=10, 05</td> </tr> <tr> <td>20</td> <td>50</td> <td>24/15</td> <td>20.00 - 22.00</td> <td>8/10/9/11</td> <td>19 29</td> <td>Olive-grey, wet, very stiff, SILT, some fine to coarse sand, little clay, trace gravel. (TIII).</td> <td>GH29628 A=4, CL UC=15, 35</td> </tr> <tr> <td>20</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Bottom of Exploration at 22.0 feet below ground surface. NO REFUSAL.</td> <td></td> </tr> </tbody> </table>						Depth (ft.)	Sample No.	Pen./Rec. (ft.)	Sample Depth (ft.)	Blow (1/8 in. Strain) (ft/ft)	Soil Description	Visual Description and Remarks	Laboratory Testing Results (ASHTO and Unified Class)	0						3" S&A		10	24/16	1.50 - 5.50	10/17/12/12	29 45		Brown, dry, very dense, fine to coarse SANDY GRAVEL, trace silt. (FILL).	GH29624 A=10, SC=4 UC=15, 35	5	20	24/13	5.00 - 7.00	9/6/9	12 19 33	Brown, comp. medium dense, gravelly fine to coarse SAND, little silt. (FILL).	GH29625 A=10, SC=4 UC=15, 35	10	30	14.4/11	10.00 - 11.20	8/9/10(2,4)'	---	Grey, wet, dense, fine to coarse SAND, some gravel, little silt. Layer of Cobbles from 11.2-12.7 ft bgs.	GH29626 A=10, SC=4 UC=15, 35	15	40	24/14	15.00 - 17.00	7/10/10/12	20 31	Olive-grey, wet, hard, SILT, some clay, little fine to coarse sand, trace gravel. (TIII).	GH29627 A=4, CL UC=10, 05	20	50	24/15	20.00 - 22.00	8/10/9/11	19 29	Olive-grey, wet, very stiff, SILT, some fine to coarse sand, little clay, trace gravel. (TIII).	GH29628 A=4, CL UC=15, 35	20						Bottom of Exploration at 22.0 feet below ground surface. NO REFUSAL.	
Depth (ft.)	Sample No.	Pen./Rec. (ft.)	Sample Depth (ft.)	Blow (1/8 in. Strain) (ft/ft)	Soil Description	Visual Description and Remarks	Laboratory Testing Results (ASHTO and Unified Class)																																																														
0						3" S&A																																																															
10	24/16	1.50 - 5.50	10/17/12/12	29 45		Brown, dry, very dense, fine to coarse SANDY GRAVEL, trace silt. (FILL).	GH29624 A=10, SC=4 UC=15, 35																																																														
5	20	24/13	5.00 - 7.00	9/6/9	12 19 33	Brown, comp. medium dense, gravelly fine to coarse SAND, little silt. (FILL).	GH29625 A=10, SC=4 UC=15, 35																																																														
10	30	14.4/11	10.00 - 11.20	8/9/10(2,4)'	---	Grey, wet, dense, fine to coarse SAND, some gravel, little silt. Layer of Cobbles from 11.2-12.7 ft bgs.	GH29626 A=10, SC=4 UC=15, 35																																																														
15	40	24/14	15.00 - 17.00	7/10/10/12	20 31	Olive-grey, wet, hard, SILT, some clay, little fine to coarse sand, trace gravel. (TIII).	GH29627 A=4, CL UC=10, 05																																																														
20	50	24/15	20.00 - 22.00	8/10/9/11	19 29	Olive-grey, wet, very stiff, SILT, some fine to coarse sand, little clay, trace gravel. (TIII).	GH29628 A=4, CL UC=15, 35																																																														
20						Bottom of Exploration at 22.0 feet below ground surface. NO REFUSAL.																																																															
<p>Drilling Method: Automatic</p> <p>Home Efficiency Factor: 0.928</p> <p>Home Type: Automatic</p> <p>Home: WT, Falls 140R/30"</p> <p>Home Efficiency Factor: 0.928</p> <p>Home Type: Automatic</p> <p>Home: WT, Falls 140R/30"</p>																																																																					

Maine Department of Transportation Soil/Rock Exploration Log US CUSTOMER UNITS		Project: Large Culvert Replacement on Route 6 Location: Carroll Plantation, Maine		Boring No.: HB-CAR-102 WIN: 23581.00																																																	
Drilling Contractor: M&I/NEI	Elevation (ft.): 515.8	Auger (ft/ft): 5" Dia.	Operator: Doggett/NEI	Soil: NAVD83	Sampler: N/A																																																
Logged By: B. W. Fisher	Rig Type: CME 45C	Home: WT, Falls 140R/30"	Date Start/Finish: 9/10/2018 08:30-09:00	Drilling Method: Solid Stem Auger	Core Barrels: N/A																																																
Boring Location: 74+6.4, 4.8 ft Lt.	Coring (ft/ft): N/A	Water Levels: None Observed	Home Efficiency Factor: 0.928	Home Type: Automatic	Rope & Catcher: C																																																
<table border="1"> <thead> <tr> <th>Depth (ft.)</th> <th>Sample No.</th> <th>Pen./Rec. (ft.)</th> <th>Sample Depth (ft.)</th> <th>Blow (1/8 in. Strain) (ft/ft)</th> <th>Soil Description</th> <th>Visual Description and Remarks</th> <th>Laboratory Testing Results (ASHTO and Unified Class)</th> </tr> </thead> <tbody> <tr> <td>0</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Probe, no samples taken. Silt stiffer to HB-CAR-101.</td> <td></td> </tr> <tr> <td>5</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>10</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>15</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>20</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Bottom of Exploration at 20.5 feet below ground surface. NO REFUSAL.</td> <td></td> </tr> </tbody> </table>						Depth (ft.)	Sample No.	Pen./Rec. (ft.)	Sample Depth (ft.)	Blow (1/8 in. Strain) (ft/ft)	Soil Description	Visual Description and Remarks	Laboratory Testing Results (ASHTO and Unified Class)	0						Probe, no samples taken. Silt stiffer to HB-CAR-101.		5								10								15								20						Bottom of Exploration at 20.5 feet below ground surface. NO REFUSAL.	
Depth (ft.)	Sample No.	Pen./Rec. (ft.)	Sample Depth (ft.)	Blow (1/8 in. Strain) (ft/ft)	Soil Description	Visual Description and Remarks	Laboratory Testing Results (ASHTO and Unified Class)																																														
0						Probe, no samples taken. Silt stiffer to HB-CAR-101.																																															
5																																																					
10																																																					
15																																																					
20						Bottom of Exploration at 20.5 feet below ground surface. NO REFUSAL.																																															
<p>Drilling Method: Automatic</p> <p>Home Efficiency Factor: 0.928</p> <p>Home Type: Automatic</p> <p>Home: WT, Falls 140R/30"</p> <p>Home Efficiency Factor: 0.928</p> <p>Home Type: Automatic</p> <p>Home: WT, Falls 140R/30"</p>																																																					

STATE OF MAINE
 DEPARTMENT OF TRANSPORTATION
 23581.00
 WIN
 23581.00
 HIGHWAY PLANS

CARROLL PLT.
 ROUTE 6
 BORING LOCATION PLAN &
 INTERPRETIVE SUBSURFACE PROFILE
 WITH BORING LOGS

SHEET NUMBER
 2
 OF 2

DATE: FEB 2021
 SIGNATURE: T. WHITE
 P.E. NUMBER: [blank]
 DATE: [blank]


Appendix A

Boring Logs

Appendix B

Laboratory Test Results

Maine Department of Transportation Grain Size Distribution Curve



UNIFIED CLASSIFICATION

	Boring/Sample No.	Station	Offset, ft	Depth, ft	Description	WC, %	LL	PL	PI
○	HB-CAR-101/1D	74+13.4	10.6 LT	1.5-3.5	Sandy GRAVEL, trace silt.	3.3			
◆	HB-CAR-101/2D	74+13.4	10.6 LT	5.0-7.0	Gravelly SAND, little silt.	3.3			
■	HB-CAR-101/3D	74+13.4	10.6 LT	10.0-11.2	SAND, some gravel, little silt.	12.2			
●	HB-CAR-101/4D	74+13.4	10.6 LT	15.0-17.0	SILT, some clay, little sand, trace gravel.	18.0			
▲	HB-CAR-101/5D	74+13.4	10.6 LT	20.0-22.0	SILT, some sand, little clay, trace gravel.	13.3			
X									

WIN
023581.00
Town
Carroll Pit
Reported by/Date
WHITE, TERRY A 1/22/2020

Appendix C

Calculations

Bearing Resistance - Existing Soils:

Part 1 - Service Limit State

Nominal and factored Bearing Resistance - Box Culvert on Till

Presumptive Bearing Resistance for Service Limit State ONLY

Reference: AASHTO LRFD Bridge Design Specifications 9th Edition 2020
Table C10.6.2.6.1-1 Presumptive Bearing Resistances for Spread Footings at the
Service Limit State Modified after US Department of Navy (1982)

Type of Bearing Material: Silt (CL)

Based on N-values, soils are very stiff to hard near the bearing elevation

Density In Place: Hard

Bearing Resistance: Ordinary Range (ksf) 6 to 12

Recommended Value of Use:

$$q_{nom} := 8 \cdot \text{ksf}$$

Resistance factor at the **service limit state** = 1.0 (LRFD Article 10.5.5.1)

$$\phi_{service_bc} := 1.0$$

$$q_{factored_service_bc} := q_{nom} \cdot \phi_{service_bc}$$

$$q_{factored_service_bc} = 8 \cdot \text{ksf}$$

Note: This bearing resistance is settlement limited (1 inch) and applies only at the service limit state.

Part 2 - Strength Limit State

Nominal and factored Bearing Resistance - Box Culvert on Till

Reference: AASHTO LRFD Bridge Design Specifications 9th Edition 2020 - Article 10.6.3.1

Assumptions:

1. The box will be founded at ~ Elev 501.5 feet

Bottom of Construction will be 2 feet below box invert

$$D_{footing} := 2.0 \cdot \text{ft}$$

2. Assumed parameters for fill soils:

Saturated unit weight: $\gamma_s := 125 \cdot \text{pcf}$

Internal friction angle: $\phi_{ns} := 32 \cdot \text{deg}$

Undrained shear strength: $c_{ns} := 0 \cdot \text{psf}$

3. Box Culvert parameters

Width of box culvert, B $B_{box} := 14 \cdot \text{ft}$

Length of box culvert, L $L_{box} := 92 \cdot \text{ft}$

Nominal Bearing Resistance per LRFD Equation 10.6.3.1.2a-1

$$q_n = cN_{cm} + \gamma D_f N_{qm} C_{wq} + 0.5\gamma B N_{\gamma m} C_{w\gamma}$$

Bearing Capacity Factors - LRFD Table 10.6.3.1.2a-1

For $\phi=32$ deg $N_c := 35.5$ $N_q := 23.2$ $N_\gamma := 30.2$

Shape Correction Factors LRFD Table 10.6.3.1.2a-3

for $\phi=32$ degrees

$$s_c := 1 + \left(\frac{B_{\text{box}}}{L_{\text{box}}} \right) \left(\frac{N_q}{N_c} \right) \quad s_c = 1.1$$

$$s_\gamma := 1 - 0.4 \left(\frac{B_{\text{box}}}{L_{\text{box}}} \right) \quad s_\gamma = 0.9391$$

$$s_q := 1 + \left(\frac{B_{\text{box}}}{L_{\text{box}}} \cdot \tan(\phi_{ns}) \right) \quad s_q = 1.1$$

Load Inclination Factors:

Assume all are 1.0 (LRFD Article C10.6.3.1.2a)

$i_c := 1.0$ $i_q := 1.0$ $i_\gamma := 1.0$

Depth Correction
 Factor

$$d_q := 1 + 2 \cdot \tan(\phi_{ns}) \cdot (1 - \sin(\phi_{ns}))^2 \cdot \tan\left(\frac{D_{\text{footing}}}{B_{\text{box}}}\right)^{-1} \quad d_q = 2.92$$

LRFD Eq.
 10.6.3.1.2a-10

$$N_{cm} := N_c \cdot s_c \cdot i_c \quad N_{cm} = 39.0304 \quad \text{LRFD Eq. 10.6.3.1.2a-2}$$

$$N_{qm} := N_q \cdot s_q \cdot d_q \cdot i_q \quad N_{qm} = 74.18 \quad \text{LRFD Eq. 10.6.3.1.2a-3}$$

$$N_{\gamma m} := N_\gamma \cdot s_\gamma \cdot i_\gamma \quad N_{\gamma m} = 28.36 \quad \text{LRFD Eq. 10.6.3.1.2a-4}$$

Coefficients for Groundwater Depths LRFD Table 10.6.3.1.2a-2

Depth the water table: $D_w := 0 \cdot \text{ft}$ $C_{wq} := 0.5$ $C_{w\gamma} := 0.5$

$$q_{\text{nominal}} := c_{ns} \cdot N_{cm} + \gamma_s \cdot D_{\text{footing}} \cdot N_{qm} \cdot C_{wq} + 0.5(\gamma_s) B_{\text{box}} \cdot N_{\gamma m} \cdot C_{w\gamma}$$

$$q_{\text{nominal}} = 21.7 \cdot \text{ksf}$$

Factored Bearing Resistance for Strength Limit State

Resistance Factor: $\phi_b := 0.45$ LRFD Table 10.5.5.2.2-1

$$q_{\text{factored}} := q_{\text{nominal}} \cdot \phi_b$$

$$q_{\text{factored}} = 9.8 \cdot \text{ksf}$$

Recommend a limiting factored bearing resistance of 10.0 ksf for the Strength Limit State.

Modulus of Subgrade Reaction:

Reference: Foundation Analysis and Design 5th Edition JE Bowles Section 9-6

Width of box culvert, B $B_{\text{box}} = 14 \text{ ft}$
 Length of box culvert, L $L_{\text{box}} = 92 \text{ ft}$
 Thickness of box culvert, t $t_{\text{box}} := 12 \cdot \text{in}$ assumed
 Depth of box, D $D_{\text{box}} := 14 \cdot \text{ft}$
 Bearing Resistance: $q_{\text{factored_service_bc}} = 8 \cdot \text{ksf}$ Calculated above
 Modulus of Elasticity: Site soils at bearing elevation are Till (Silt). Use values for Till (dense).
 From Bowles Table 2-8 Modulus E_s for Glacial Till, dense ranges from 3100 - 15000 ksf

Use Modulus of Elasticity, E_s $E_s := 3500 \cdot \text{ksf}$
 Poisson's Ratio: Site conditions at bearing elevation are Silt Till. Use values for Glacial Till (dense).
 From Bowles Table 2-7 Poisson's Ratio μ for Silt ranges from 0.3 - 0.35
 Use Poisson's Ratio, μ $\mu := 0.35$

$$E_{\text{prime_s}} := \frac{1 - \mu^2}{E_s} \quad E_{\text{prime_s}} = 0.000251 \cdot \frac{\text{ft}^2}{\text{kip}}$$

Analyze corner:

Take H as 5*B as recommended in Bowles Chapter 5

$$H_{\text{inf}} := \frac{5 \cdot B_{\text{box}}}{B_{\text{box}}} \quad H_{\text{inf}} = 5 \quad \text{N in Table 5-2} \quad \text{From Table 5-2 for N=5 and M=6.5714}$$

$$\frac{L_{\text{box}}}{B_{\text{box}}} = 6.5714 \quad \text{M in Table 5-2} \quad I_1 := 0.545$$

$$I_2 := 0.125 \quad \text{by interpolation}$$

Determine Steinbrenner influence factor - Bowles Section 5-6:

$$I_s := I_1 + \left[\frac{1 - (2 \cdot \mu)}{1 - \mu} \right] \cdot I_2 \quad I_s = 0.6027$$

Determine Influence factor for footing depth - Bowles Figure 5-7

$$\text{Depth ratio:} \quad \frac{D_{\text{box}}}{B_{\text{box}}} = 1 \quad \frac{L_{\text{box}}}{B_{\text{box}}} = 6.5714 \quad \mu = 0.35 \quad I_F := 0.82$$

Calculate modulus of subgrade reaction - Bowles Eq. 9-7

$$k_s := \frac{1}{B_{\text{box}} \cdot E_{\text{prime_s}} \cdot I_s \cdot I_F} \quad \text{Bowles Eq. 9-7}$$

$$k_s = 334 \cdot \text{pci}$$

Recommend Modulus of Subgrade Reaction of 330 pci