



**GEOTECHNICAL DESIGN MEMORANDUM
TRAFFIC SIGNAL FOUNDATIONS
INTERSECTION OF ROUTE 1 AND WALKER STREET
KITTERY, MAINE
MAINEDOT WIN 12752.00**

PREPARED FOR:

Vanasse Hangen Brustlin, Inc.
Bedford, New Hampshire

PREPARED BY:


Isabel V. (Be) Schonewald, P.E.
Schonewald Engineering Associates, Inc. (SchonewaldEA)
129 Middle Road
Cumberland, Maine 04021
Be@SchonewaldEngineering.com

November 1, 2011

SchonewaldEA Project No. 11-010

VIA EMAIL

TO: Anthony Grande, P.E., Vanasse Hangen Brustlin, Inc. (VHB)
FROM: Isabel V. (Be) Schonewald, P.E., Schonewald Engineering Associates, Inc. (SchonewaldEA)
DATE: November 1, 2011
PROJECT NO.: 11-010
RE: Geotechnical Design Memorandum
Traffic Signal Foundations
Intersection of Route 1 and Walker Street
Kittery, Maine
MaineDOT WIN 12752.00



Schonewald Engineering Associates, Inc. (SchonewaldEA) is pleased to provide Vanasse Hangen Brustlin, Inc. (VHB) with this design memorandum that summarizes the geotechnical evaluation completed to support VHB's design of improvements to the intersection of Route 1 and Walker Street in Kittery, Maine (MaineDOT WIN 12752.00). Specifically, our work focused on the foundations for mast-arm-mounted traffic signals that are proposed to replace existing traffic signals at the intersection. SchonewaldEA's work included evaluating subsurface conditions in the immediate vicinity of the proposed traffic signal poles, completing geotechnical engineering analyses, and preparing this memorandum that summarizes the findings of the work and provides geotechnical recommendations related to the traffic signal foundations.

This work was completed in accordance with the agreement between SchonewaldEA and VHB that was executed on October 5, 2011. This design memorandum is subject to the limitations contained in Attachment A.

PROJECT BACKGROUND

We understand that VHB has been retained by the Maine Department of Transportation (MaineDOT) to design geometric improvements with traffic signal upgrades and to develop plans for the reconstruction of the intersection of Route 1 and Walker Street located in Kittery, Maine. Based upon preliminary project information provided by VHB, we understand that mast-arm-mounted traffic signals are proposed for each of the four quadrants of the intersection. The intersection is located in an urbanized area that is traversed by numerous overhead and underground utilities. A rail line runs east-west along the northerly side of the intersection.

SUBSURFACE EXPLORATION PROGRAM

SchonewaldEA retained Maine Test Borings (MTB) to drill four test borings, designated B-1 through B-4, located in close proximity to the proposed traffic signal mast poles. The locations of numerous underground and above-ground utilities and limitations imposed by existing Right-of-Way restricted accessibility to the actual proposed mast pole locations. The drilling work was completed on October 6, 2011 and was observed and logged by SchonewaldEA. A sketch showing the approximate locations of the test borings is included as Figure 1 and logs of the subsurface explorations are included as Attachment B.

The borings were extended to refusal, which was encountered at between 10.3 and 21.1 feet below ground surface (BGS). Test borings B-1 and B-3, located in the northwest and southeast corners of the intersection, respectively, were completed using hollow-stem augers to avoid using drilling fluids (water).

The remaining two borings, B-2 and B-4, located in the southwest and northeast corners of the intersection, respectively, were completed using cased drive and wash techniques and rock core was obtained. In all four borings, Standard Penetration Tests (SPTs) were completed and split-spoon soil samples obtained near the ground surface and at five-foot intervals to the bottom of each boring. Soft soils (e.g., Presumpscot clay) were not encountered. Groundwater level was measured in the auger borings upon completion of the test boring and removal of the augers. The boreholes were backfilled with drill cuttings and manufactured stone backfill; asphalt pavement disturbed by the work was patched.

SUBSURFACE CONDITIONS

Soil conditions observed in the test borings consisted of the following strata from the ground surface downward:

- GRANULAR FILL MATERIAL Approximately 2.8 to 4.0 feet of good quality granular fill material was encountered beneath surficial loam or asphalt in all of the test borings. The granular fill material typically consisted of dense, gravelly sand with about 5 to 15 percent silt;
- MISCELLANEOUS URBAN FILL Up to approximately 5.5 feet of loose to medium dense, typically fine to medium sand with varying amounts of gravel and silt, with lesser amounts of apparent cinders and crushed brick was encountered in test borings B-3 and B-4 on the easterly side of the intersection; and
- GLACIAL TILL Glacial till consisting of medium dense to very dense, sand and gravel with about 10 to 20 percent silt was encountered in all of the test borings above refusal (rock).

Bedrock: Refusal was encountered at between 10.3 and 21.1 feet BGS in the test borings. In the auger borings, refusal was presumed to be on rock. In the cased borings, rock core was obtained. Rock core was classified as a hard, fresh to slightly weathered, fine-grained metasandstone containing some apparent brecciated zones, which is consistent with bedrock geological maps of the area. The shallow refusals are consistent with observed rock outcrop in the vicinity of the intersection and reports of shallow bedrock encountered during spread footing construction for a building under construction in the southeast corner of the intersection. Rock quality, based upon RQDs ranging from 0 to 47 percent, would be considered very poor to poor.

Groundwater was observed to be at about 8 to 13 feet BGS in test borings B-1 and B-3, respectively, at the time of drilling.

GEOTECHNICAL ENGINEERING EVALUATION

Frost Depth: Methodology set forth in MaineDOT's Bridge Design Guide dated August 2003 (MaineDOT BDG) was used to determine the depth of frost penetration for the project site. The design freezing index of the site was taken as 1250 degree-days. Near-surface soils underlying the project site consist of granular material that was observed to be moist. Based upon Table 5.1 in the MaineDOT BDG, the frost depth would be about 4.5 feet. This is consistent with local geotechnical engineering practice.

Traffic Signal Mast Pole Foundations: The soils underlying the project site are suitable for supporting the proposed traffic signal mast poles on drilled shafts. Rock anchors might be required due to the thin overburden soils. Site soils are also suitable to support the mast poles on shallow spread footings. However, space is limited due to numerous buried utilities. As such, the use of shallow spread footings is not discussed further.

In accordance with Table 3.3 in MaineDOT's BDG and local practice, the structural design of the foundations should be based on the following site-specific soil parameters:

MISCELLANEOUS URBAN FILL: drained friction angle (Φ') equal to 28 degrees; saturated unit weight (γ_{sat}) equal to 0.110 kcf; and interface friction angle between soil and cast-in-place concrete (δ) equal to 19 degrees.

GRANULAR FILL AND GLACIAL TILL: drained friction angle (Φ') equal to 34 degrees; saturated unit weight (γ_{sat}) equal to 0.120 kcf; and interface friction angle between soil and cast-in-place concrete (δ) equal to 22 degrees.

For the design of rock anchors, it should be assumed that the upper portion of the bedrock underlying the project site is of very poor to poor quality based upon drilling behavior, low RQDs determined by coring rock, and visual examination of the rock core retrieved. If rock anchors are utilized, pull-out tests should be completed during construction.

GEOTECHNICAL RECOMMENDATIONS FOR DESIGN AND CONSTRUCTION

The following geotechnical recommendations are provided for the design and construction of the traffic signal foundations specifically and intersection improvements in general.

Design of drilled shafts for supporting proposed traffic signal mast poles:

The soils underlying the project site are suitable for supporting the proposed traffic signal mast poles on drilled shafts. The design of drilled shafts should be in accordance with Section 13 of the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, Fifth Edition, dated 2009 (Traffic Signal Spec) together with Section 4.6 of the AASHTO Standard Specifications for Highway Bridges [ASD methodology] (Bridge Spec) and using site-specific subsurface data and project-specific structural loads. The design should consider both geotechnical lateral capacity and geotechnical axial capacity, though likely the lateral capacity will control.

Brom's method may be used to develop approximate shaft dimensions including embedment depth. In Brom's method a factor of safety of 2.5 to 3.0 should be utilized. A more rigorous analysis, such as L-PILE or COM624, should be used to evaluate lateral capacity and predict deflection of the shaft. The structural design should confirm that the predicted deflections are acceptable. The lateral soil resistance in the upper 4.5 feet of the shaft, equivalent to the frost depth at the site, should be neglected for all soil types, including cohesionless soils such as those encountered at the project site.

Geotechnical axial capacity should be checked utilizing procedures set forth in the Bridge Spec. Both side and tip resistance may be considered. A factor of safety of at least 2.5 should be achieved.

For the design of rock anchors, it should be assumed that the bedrock underlying the project site is of poor quality and would have a relatively low RQD, indicative of fractured rock near the rock surface. If rock anchors are utilized, pull-out tests should be completed on all anchors during construction.

Drilled shafts should be uncased (concrete cast against soil) below the frost zone. Backfill used to repair disturbed areas around the drilled shafts should be a good quality granular material and grading adjacent to the shafts should direct surface water runoff away from the structure.

Site-specific soil parameters for use in designing traffic signal mast pole foundations:

In accordance with Table 3.3 in MaineDOT's BDG and local practice, the structural design of the foundations should be based on the following site-specific soil parameters:

MISCELLANEOUS URBAN FILL: drained friction angle (Φ') equal to 28 degrees; saturated unit weight (γ_{sat}) equal to 0.110 kcf; and interface friction angle between soil and cast-in-place concrete (δ) equal to 19 degrees.

GLACIAL TILL: drained friction angle (Φ') equal to 34 degrees; saturated unit weight (γ_{sat}) equal to 0.120 kcf; and interface friction angle between soil and cast-in-place concrete (δ) equal to 22 degrees. An SPT N-value equal to 30 should be used for the purpose of determining unit tip resistance (q_T) in accordance with Section 4.6.5.1.4 of the Bridge Spec.

The highest anticipated groundwater level should be used in the analyses.

Contractor's foundation design submittal:

The contractor's foundation designer shall prepare detailed site-specific design calculations that demonstrate the adequacy of the foundations. Design calculations that consist of computer program generated output shall be supplemented with at least one hand calculation with graphics demonstrating the design methodology used. MATHCAD-generated calculations are acceptable as hand calculations as long as they are thoroughly documented and annotated. Design calculations shall provide thorough documentation of the sources of equations used, as well as soil and material properties. Design calculations shall only include those foundation elements proposed for the specific project.

Subgrade preparation and earthwork for new travel-way construction:

To limit the disturbance of the subgrade soils, care should be exercised to excavate existing soils to expose suitable subgrade soils consisting of suitable compacted granular borrow or undisturbed inorganic native soil. Unsuitable subgrade soils, including cobbles and boulders in excess of 6 inches, should be overexcavated and replaced using suitable granular borrow. The subgrade soils should be proofrolled using a self-propelled static roller. Loose or yielding areas should be overexcavated and replaced using suitable granular borrow.

Care should be exercised in matching the new (full-depth construction) into the existing road section. To limit future maintenance issues, the prepared subgrade for the new travel-way should blend into similarly prepared and constructed elements of the existing road section.

Excavated existing granular materials shall not be reused as aggregate subbase or base. It may be reused to fill below the top of subgrade elevation, given the gradation of the material is similar to gradation of the surrounding subgrade materials.

Suitable aggregate subbase and base course materials should be placed and compacted to the lines and grades shown on the drawings and in accordance with MaineDOT Standard Specifications. Surface water and groundwater should be controlled to allow fill placement to be completed in the dry.


SchonewaldEA appreciates the opportunity to work with VHB on the improvements to the intersection of Route 1 and Walker Street in Kittery, Maine. If you have any questions regarding this design memorandum or the attachments, please call me at your convenience.

Attachments: Figure 1: Test Boring Location Plan
A: Limitations
B: Subsurface Exploration Logs

FIGURE
TEST BORING LOCATION PLAN

**TEST BORING LOCATION PLAN
INTERSECTION OF ROUTE 1 AND WALKER ST.
KITTERY, MAINE
MaineDOT WIN 12752.00**

Figure No.:



BORING PLAN LEGEND



TEST BORING

**B-1
RC
15.0'
▽ 9.0'**

I.D.
ROCK CORE OBTAINED
DEPTH TO REFUSAL/ TOP OF ROCK
DEPTH TO OBSERVED GROUNDWATER

BORING PLAN NOTES

1. BASE PLAN WAS DEVELOPED FROM SHEET 6 OF THE PDR-LEVEL DRAWINGS PROVIDED BY VHB.
2. LOCATIONS OF THE TEST BORINGS WERE DETERMINED IN THE FIELD BY TAPING FROM PROMINENT SITE FEATURES AND SHOULD BE CONSIDERED APPROXIMATE.
3. TEST BORINGS WERE COMPLETED BY MAINE TEST BORINGS ON OCT. 16, 2011 AND WERE OBSERVED AND LOGGED BY SchonevaldEA. DETAILED DESCRIPTIONS OF THE MATERIALS ENCOUNTERED ARE PROVIDED ON THE BORING LOGS.



ATTACHMENT A

LIMITATIONS

LIMITATIONS

Explorations

The analyses and recommendations submitted in this report are based in part upon the data obtained from subsurface explorations. The nature and extent of variations between these explorations may not become evident until construction. If variations then appear evident, it will be necessary to re-evaluate the recommendations of this report.

The generalized soil profile described in the text is intended to convey trends in subsurface conditions. The boundaries between strata are approximate and idealized and have been developed by interpretations of widely spaced explorations and samples; actual soil transitions are probably more erratic. For specific information, refer to the boring logs.

Water level readings have been made in the drill holes at times and under conditions stated on the boring logs. These data have been reviewed and interpretations have been made in the text of this report. However, it must be noted that fluctuations in the level of the groundwater may occur due to variations in rainfall, temperature, and other factors occurring since the time the measurements were made.

Review

In the event that any changes in the nature, design, or location of the proposed construction are planned, the conclusions and recommendations contained in this report shall not be considered valid unless the changes are reviewed and conclusions of this report modified or verified in writing by SchonewaldEA. It is recommended that this firm be provided the opportunity for a general review of final design and specifications in order that geotechnical design and construction recommendations may be properly interpreted and implemented in the design and specifications.

Construction

It is recommended that this firm be retained to provide geotechnical engineering support services during construction of the work. This is to observe compliance with the design concepts, specifications, and recommendations and to allow design changes in the event that subsurface conditions differ from those anticipated prior to start of construction.

Use of Report

This geotechnical engineering report has been prepared for this project by SchonewaldEA. This report is for design purposes only and is not sufficient to prepare an accurate bid. Contractors wishing a copy of the report may secure it with the understanding that its scope is limited to design considerations only.

This report has been prepared for this project by SchonewaldEA for the exclusive use of Vanasse Hangen Brustlin, Inc. (VHB) for specific application to the proposed traffic signal foundations at the intersection of Route 1 and Walker Street located in Kittery, Maine (MaineDOT WIN 12752.00) in accordance with generally accepted soil and foundation engineering practices. No Warranty, express or implied, is made.



ATTACHMENT B

SUBSURFACE EXPLORATION LOGS

Contractor Maine Test Borings
Foreman Jerry Rudnicki
Logged by Be Schonewald
Date Start/Finish 10/6/11 10/6/11
Boring Location northwest corner
GS Elev. _____ Datum MSL/NGVD

Auger/
Casing
Type HSA
I.D. 2-1/2 in.
Hammer Wt. _____
Hammer Fall _____
Other see notes

Sampler
Split Spoon
_____ 1-3/8 in.
_____ 140 lbs.
_____ 30 inches
_____ safety hammer

Date	Time	Depth	Stabilization
5/6/11	0910	ft. BGS 12.8	open hole at completion

		Sample Information										
Depth BGS (ft.)	Casing Blows	No.	Pen/Rec (In.)	Depth (Ft.)	Blows/ 6"	N Value or % RQD	Sample Description & Classification			Stratum Description	Notes	
5 (1.5 m)							0 to 2 ft.: Brown, Gravelly fine to coarse SAND, little Silt. GRAN FILL			GRANULAR FILL 2.8'	1	
		1D	24/15	2-4	9-19	49	1D: (Appears undisturbed at 2.8 ft. and consists of) Dense, brown, fine to coarse SAND, some Gravel, trace to little Silt; damp. TILL					
					30-25					TILL		
		2D	24/17	5-7	14-17	38	2D: Dense, brown, fine to coarse SAND, some Gravel, trace to little Silt; damp. TILL.					
				21-20								
10 (3.0 m)		3D	24/0	10-12	20-15	28	3D: No recovery; medium dense; tip of spoon wet. Auger cuttings: Brown, fine to coarse SAND, some Gravel, little Silt; damp. TILL					
					13-16							
15 (4.6 m)		4D	24/18	15-17	7-13	33	4D:Dense, brown, Gravelly fine to coarse SAND, little Silt; moist. TILL					
					20-41							
20 (6.1 m)		5D	8/8	20-20.7	50-50/2"	>50	5D: V. dense, brown, Sandy GRAVEL, little Silt; wet. TILL			21.1'		
							Bottom of boring at 21.1 ft. at auger refusal.			PROBABLE ROCK	3, 4	
25 (7.6 m)												
30 (9.1 m)												

R E M A R K S

1. Boring located in northwest corner of intersection and off the outside edge of an asphalt sidewalk.
2. Drilling more difficult below 17 feet, Below Ground Surface (BGS).
3. Auger refusal at 21.1 feet, likely at top of rock. Groundwater measured in open hole at end of drilling.
4. No equipment installed. Borehole backfilled using drill spoils.

D = split-spoon sample (blow counts provided if SPT test conducted); U = thin-wall Shelby tube sample (hydraulic-actuated, fixed piston sampler utilized);
V = in-situ vane shear test (undisturbed and remolded); R = rock core; WH = Weight of hammer; WR = Weight of rods; WC = Weight of casing

Stratification lines represent approximate boundaries between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations may occur due to other factors than those present at the time measurements were made.

Boring No.: **B-1**

Contractor Maine Test Borings
Foreman Jerry Rudnicki
Logged by Be Schonewald
Date Start/Finish 10/6/11 10/6/11
Boring Location southwest corner
GS Elev. _____ Datum MSL/NGVD

Auger/
Casing _____
Sampler _____
Type NW Split Spoon
I.D. 3 in. 1-3/8 in.
Hammer Wt. _____ 140 lbs.
Hammer Fall _____ 30 inches
Other NQ2 core safety hammer

Date	Time	Depth	Stabilization
		ft. BGS	

Depth BGS (ft.)	Casing Blows	Sample Information					N Value or % RQD	Sample Description & Classification	Stratum Description	Notes
		No.	Pen/Rec (In.)	Depth (Ft.)	Blows/ 6"					
5 (1.5 m)								0 to 0.4 ft: ASPHALT	ASPHALT	1
								0.4 to 2 ft.: Brown, Gravelly fine to coarse SAND, little Silt. GRAN FILL	0.4' GRANULAR FILL	
		1D	24/14	2-4	19-17		44	1D: (Appears undisturbed at 2.8 ft. and consists of) Dense, brown, Sandy GRAVEL, trace to little Silt; damp. TILL	2.8'	
					27-27					
10 (3.0 m)		2D	24/13	5-7	35-15		25	2D: M. dense, brown, Sandy GRAVEL, trace to little Silt; damp. TILL.	TILL	
					10-11					
15 (4.6 m)								3D: Poor recovery; medium dense; possibly pushing rock ahead of spoon. TILL	KITTERY FM (META-SANDSTONE)	2, 3
		3D	24/1	10-12	11-11		19			
					8-8					
		R1	9/7	13.6-14.3			0%	R1 and R2: Light gray, fine grained, hard, fresh to slightly weathered, META-SANDSTONE. Some cross-bedding (calcereous feldspathic) veins and possible brecciated zones. No distinct foliation or jointing. R1 consists of gravel-sized pieces of rock (RQD=0"/9"=0%). R2 somewhat more intact (RQD=8"/51"=16%). Core times:		
		R2	51/46	14.3-18.6			16%	13.6 to 14.6 ft. 4:15 min/ft 14.6 to 15.6 ft. 3:45 15.6 to 16.6 ft. 4:15 16.6 to 17.6 ft. 4:55 17.6 to 18.6 ft. 4:45		
20 (6.1 m)								Bottom of boring at 18.6 ft.		
25 (7.6 m)										
30 (9.1 m)										

REMARKS

- Boring located in southwest corner of intersection in Route 1 southbound travelway.
- Boring terminated at 18.6 feet, approximately 5 feet into rock.
- No equipment installed. Borehole backfilled using drill spoils and manufactured sand and gravel; pavement patched.

D = split-spoon sample (blow counts provided if SPT test conducted); U = thin-wall Shelby tube sample (hydraulic-actuated, fixed piston sampler utilized); V = in-situ vane shear test (undisturbed and remolded); R = rock core; WH = Weight of hammer; WR = Weight of rods; WC = Weight of casing

Stratification lines represent approximate boundaries between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations may occur due to other factors than those present at the time measurements were made.

Boring No.: **B-2**

Contractor Maine Test Borings
Foreman Jerry Rudnicki
Logged by Be Schonewald
Date Start/Finish 10/6/11 10/6/11
Boring Location southeast corner
GS Elev. _____ Datum MSL/NGVD

Auger/
Casing HSA
Type 2-1/2 in.
I.D. 1-3/8 in.
Split Spoon
Sampler 140 lbs.
Hammer Wt. 30 inches
Other see notes safety hammer

Date	Time	Depth	Stabilization
5/6/11	1330	ft. BGS 8.0	open hole at completion

Depth BGS (ft.)	Casing Blows	Sample Information					N Value or % RQD	Sample Description & Classification	Stratum Description	Notes
		No.	Pen/Rec (In.)	Depth (Ft.)	Blows/ 6"					
5 (1.5 m)								0 to 2 ft.: Brown, fine to medium SAND, some Gravel, trace Silt. GRAN FILL		1
		1D	24/18	2-4	14-19		33	2.0 to 3.5 ft.: Dense, brown, fine to medium SAND, some Gravel, trace Silt; damp. GRAN FILL	GRANULAR FILL	
					14-9			1D: 3.5 to 4.0 ft.: Black-brown, fine to medium SAND, little Silt, trace Gravel, with cinders and crushed brick; damp. MISC URBAN FILL	3.5'	
		2D	24/15	5-7	2-2		5	2D: Red-brown, fine to medium SAND, trace Silt; damp. Changing at 6.1 ft. to dark grayish brown, fine to coarse SAND, little Silt, with crushed brick; moist. MISC URBAN FILL Undisturbed till in tip of spoon.	MISC URBAN FILL	
					3-5				7.0'	
10 (3.0 m)								3D: No recovery; spoon wet; auger cuttings consist of pieces ground rock.	TILL	2 3, 4
		3D	1/0	10-10.1	50/1"			Bottom of boring at 10.3 ft. at auger refusal.	10.3'	
									PROBABLE ROCK	
15 (4.6 m)										
20 (6.1 m)										
25 (7.6 m)										
30 (9.1 m)										

R E M A R K S

1. Boring located in southeast corner of intersection in grass island.
2. Drilling more difficult below 9.4 feet, Below Ground Surface (BGS).
3. Auger refusal at 10.3 feet, likely at top of rock. Groundwater measured in open hole at end of drilling.
4. No equipment installed. Borehole backfilled using drill spoils.

D = split-spoon sample (blow counts provided if SPT test conducted); U = thin-wall Shelby tube sample (hydraulic-actuated, fixed piston sampler utilized);
V = in-situ vane shear test (undisturbed and remolded); R = rock core; WH = Weight of hammer; WR = Weight of rods; WC = Weight of casing

Stratification lines represent approximate boundaries between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations may occur due to other factors than those present at the time measurements were made.

Boring No.: **B-3**

Contractor Maine Test Borings

Foreman	<u>Jerry Rudnicki</u>
---------	-----------------------

Logged by Be Schonewald

Date Start/Finish 10/6/11

Boring Location	<u>northeast corner</u>
-----------------	-------------------------

GS Elev. D

Auger/

Casing

Sampler

Date	Time	Depth	Stabilization
------	------	-------	---------------

Type

NW

Split Spoon

		ft, BGS	
--	--	---------	--

I.D.

3 in.

1-3/8 in.

--	--	--	--

er Wt.

140 lbs.

--	--	--	--

er Fall

30 inches

--	--	--	--

Other	NQ2 core
-------	----------

safety hammer

--	--	--	--

Depth BGS (ft.)	Casing Blows	Sample Information					N Value or % RQD	Sample Description & Classification	Stratum Description	Notes
		No.	Pen/Rec (In.)	Depth (Ft.)	Blows/ 6"					
5 (1.5 m)							32	0 to 2 ft.: Brown, fine to medium SAND, some Gravel, trace Silt. GRAN FILL	GRANULAR FILL	1
		1D	24/13	2-4	4-9			1D: Dense, brown, fine to medium SAND, little to some Gravel, trace to little Silt. GRAN FILL	4.0'±	
					23-26					
		2D	24/14	5-7	23-17	29	2D: M. dense, reddish brown, fine to medium SAND, little to some fine Gravel, trace Silt, with minor amounts cinders; damp. MISC URBAN FILL.	MISC URBAN FILL		
				12-11			8.5'±			
10 (3.0 m)										
15 (4.6 m)							>104	3D: Poor recovery consisting of pieces ground rock.	TILL	2, 3
		3D	13/1	10-11.1	44-54 50/1"			R1 and R2: Light gray, fine grained, hard, fresh to slightly weathered, META-SANDSTONE. Some cross-bedding (calcereous felspathic) veins and possible brecciated zones consisting of gravel-sized pieces of rock with mud. No distinct foliation or jointing. (R1 RQD=0"/25"=0%; R2 RQD=9"/19"=47%). Core times:		
		R1	25/22	11.2-13.3		0%		11.2 to 12.2 ft. 3:35 min/ft	KITTELY FM (META-SANDSTONE)	
							12.2 to 13.2 ft. 2:50			
		R2	19/19	13.3-14.9		47%	13.2 to 14.2 ft. 3:10			
20 (6.1 m)								Bottom of boring at 14.9 ft.		
25 (7.6 m)										
30 (9.1 m)										

- | | |
|-------------|---|
| R
E
C | 1. Boring located in northeast corner of intersection in grass island. |
| | 2. Boring terminated at 14.9 feet, approximately 3.7 feet into rock. |
| | 3. No equipment installed. Borehole backfilled using drill spoils and manufactured sand and gravel. |

D = split-spoon sample (blow counts provided if SPT test conducted); U = thin-wall Shelby tube sample (hydraulic-actuated, fixed piston sampler utilized); V = in-situ vane shear test (undisturbed and remolded); R = rock core; WH = Weight of hammer; WR = Weight of rods; WC = Weight of casing

Stratification lines represent approximate boundaries between soil types, transitions may be gradual. Water level readings have been made at times and under conditions stated. Fluctuations may occur due to other factors than those present at the time measurements were made.

Boring No.: **B-4**