

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.30

PROJECT(S): HPP-STP-6462(300)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE DOLLARS CTS	BID AMOUNT DOLLARS CTS
SECTION 0001 PROJECT ITEMS				
0010	201.11 CLEARING	1.100 AC		
0020	201.23 REMOVING SINGLE TREE TOP ONLY	48.000 EA		
0030	201.24 REMOVING STUMP	48.000 EA		
0040	202.08 REMOVING BUILDING NO.: 1	LUMP	LUMP	
0050	202.08 REMOVING BUILDING NO.: 2	LUMP	LUMP	
0060	202.08 REMOVING BUILDING NO.: 3	LUMP	LUMP	
0070	202.08 REMOVING BUILDING NO.: 4	LUMP	LUMP	
0080	203.20 COMMON EXCAVATION	39153.000 CY		
0090	203.21 ROCK EXCAVATION	50.000 CY		
0100	203.24 COMMON BORROW	35117.000 CY		

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.30

PROJECT(S): HPP-STP-6462(300)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.242 DIRTY BORROW	2350.000 CY				
0120	203.25 GRANULAR BORROW	1200.000 CY				
0130	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	50.000 CY				
0140	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	50.000 CY				
0150	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	1200.000 CY				
0160	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	110.000 CY				
0170	304.13 DENSE GRADED CRUSHED AGGREGATE SUBBASE	28400.000 CY				
0180	403.207 HOT MIX ASPHALT 19.0 MM HMA	3300.000 T				
0190	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	640.000 T				
0200	403.213 HOT MIX ASPHALT 12.5 MM BASE	2900.000 T				
0210	409.15 BITUMINOUS TACK COAT - APPLIED	2400.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.30

PROJECT(S): HPP-STP-6462(300)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0220	502.21 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	520.000 CY				
0230	502.41 STRUCTURAL CONCRETE SUPERSTRUCTURE SLAB	67.000 CY				
0240	502.56 CONCRETE FILL	210.000 CY				
0250	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	60800.000 LB				
0260	503.13 REINFORCING STEEL, PLACING	60800.000 LB				
0270	508.13 MEMBRANE WATERPROOFING	LUMP	LUMP			
0280	509.60 FIBERGLASS REINFORCED PLASTIC SHEATHING	LUMP	LUMP			
0290	509.74 COMPOSITE ARCH SUPERSTRUCTURE ERECTION, INSTALLATION ONLY	LUMP	LUMP			
0300	512.081 FRENCH DRAINS	LUMP	LUMP			
0310	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0320	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.30

PROJECT(S): HPP-STP-6462(300)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0330	526.30 TEMPORARY CONCRETE BARRIER - TYPE 1	620.000 LF				
0340	603.169 15 INCH CULVERT PIPE OPTION III	174.000 LF				
0350	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	48.000 LF				
0360	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	72.000 LF				
0370	603.215 36 INCH REINFORCED CONCRETE PIPE CLASS III	142.000 LF				
0380	603.225 42 INCH REINFORCED CONCRETE PIPE CLASS III	230.000 LF				
0390	604.097 72 INCH CATCH BASIN TYPE B1-C	1.000 EA				
0400	606.17 GUARDRAIL TYPE 3B - SINGLE RAIL	250.000 LF				
0410	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000 EA				
0420	606.47 SINGLE WOOD POST	4.000 EA				
0430	610.08 PLAIN RIPRAP	80.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.30

PROJECT(S): HPP-STP-6462(300)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0440	610.18 STONE DITCH PROTECTION	110.000 CY				
0450	613.319 EROSION CONTROL BLANKET	2500.000 SY				
0460	615.07 LOAM	94.000 CY				
0470	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	6.500 UN				
0480	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	3050.000 UN				
0490	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	170.000 UN				
0500	619.1201 MULCH - PLAN QUANTITY	3210.000 UN				
0510	620.58 EROSION CONTROL GEOTEXTILE	535.000 SY				
0520	625.01 WATER LINE SYSTEM	LUMP	LUMP			
0530	626.22 NON-METALLIC CONDUIT (MIN. 2 1/2")	80.000 LF				
0540	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	3250.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.30

PROJECT(S): HPP-STP-6462(300)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0550	629.05 HAND LABOR, STRAIGHT TIME	60.000 HR				
0560	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR				
0570	631.13 BULLDOZER (INCLUDING OPERATOR)	20.000 HR				
0580	631.133 SKID STEER (INCLUDING OPERATOR)	20.000 HR				
0590	631.14 GRADER (INCLUDING OPERATOR)	20.000 HR				
0600	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	40.000 HR				
0610	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	20.000 HR				
0620	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR				
0630	636.40 MECHANICALLY STABILIZED EARTH RETAINING WALL	4800.000 SF				
0640	639.18 FIELD OFFICE TYPE A	1.000 EA				
0650	652.33 DRUM	28.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 006462.30

PROJECT(S): HPP-STP-6462(300)

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0660	652.35 CONSTRUCTION SIGNS	170.000 SF				
0670	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES	270.000 CD				
0680	652.38 FLAGGER	200.000 HR				
0690	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0700	659.10 MOBILIZATION	LUMP	LUMP			
0710	803.01 TEST PITS	4.000 EA				
	SECTION 0001 TOTAL					
	TOTAL BID					