

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X

BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.23 REMOVING SINGLE TREE TOP ONLY	8.000 EA				
0020	201.24 REMOVING STUMP	11.000 EA				
0030	202.12 REMOVING EXISTING STRUCTURAL CONCRETE	30.000 CY				
0040	202.128 REMOVING OF EXISTING CONCRETE CURBS & SIDEWALKS	LUMP	LUMP			
0050	202.14 REMOVING EXISTING RAILINGS (PROPERTY OF CONTRACTOR)	120.000 LF				
0060	202.15 REMOVING MANHOLE OR CATCH BASIN	14.000 EA				
0070	202.19 REMOVING EXISTING BRIDGE EAST BRIDGE	LUMP	LUMP			
0080	202.19 REMOVING EXISTING BRIDGE WEST BRIDGE	LUMP	LUMP			
0090	202.202 REMOVING PAVEMENT SURFACE	1925.000 SY				
0100	203.20 COMMON EXCAVATION	1020.000 CY				5

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	203.25 GRANULAR BORROW UNDERWATER BACKFILL	2120.000 CY				
0120	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	3000.000 CY				
0130	206.092 STRUCTURAL ROCK EXCAVATION - MAJOR STRUCTURES	650.000 CY				
0140	304.09 AGGREGATE BASE COURSE - CRUSHED	550.000 CY				
0150	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	590.000 CY				
0160	403.207 HOT MIX ASPHALT 19.0 MM HMA	415.000 T				
0170	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	353.000 T				
0180	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	140.000 T				
0190	403.213 HOT MIX ASPHALT 12.5 MM BASE	274.000 T				
0200	409.15 BITUMINOUS TACK COAT - APPLIED	211.000 G				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP	LUMP			
0220	502.22 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS (PLACED UNDER WATER)	1930.000 CY				
0230	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP	LUMP			
0240	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP	LUMP			
0250	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP	LUMP			
0260	502.56 CONCRETE FILL	25.000 CY				
0270	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	77100.000 LB				
0280	503.13 REINFORCING STEEL, PLACING	77100.000 LB				
0290	504.702 STRUCTURAL STEEL FABRICATED AND DELIVERED, WELDED	LUMP	LUMP			
0300	504.71 STRUCTURAL STEEL ERECTION	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0310	505.08 SHEAR CONNECTORS	LUMP	LUMP			
0320	507.0831 STEEL BRIDGE RAILING, 4 BAR	LUMP	LUMP			
0330	507.0832 STEEL BRIDGE RAILING, 4 BAR, TRAFFIC BICYCLE	LUMP	LUMP			
0340	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP	LUMP			
0350	510.12 SPECIAL DETOUR__FOOT ROADWAY WIDTH, VEHICULAR AND PEDESTRIAN TRAFFIC SEPARATED 24'	LUMP	LUMP			
0360	511.07 COFFERDAM: ABUT NO.1 WINGWALLS & STACKED GRANITE	LUMP	LUMP			
0370	511.07 COFFERDAM: ABUT NO.2 WINGWALLS & STACKED GRANITE	LUMP	LUMP			
0380	511.07 COFFERDAM: ABUT NO.3 WINGWALLS & STACKED GRANITE	LUMP	LUMP			
0390	511.07 COFFERDAM: ABUT NO.4 WINGWALLS & STACKED GRANITE	LUMP	LUMP			
0400	511.07 COFFERDAM: ISLAND RETAINING WALL	LUMP	LUMP			

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0410	512.081 FRENCH DRAINS	LUMP	LUMP			
0420	513.22 CRUSHED STONE SLOPE PROTECTION	250.000 SY				
0430	514.06 CURING BOX FOR CONCRETE CYLINDERS	2.000 EA				
0440	515.20 PROTECTIVE COATING FOR CONCRETE SURFACES	380.000 SY				
0450	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	128.000 LF				
0460	523.52 BEARING INSTALLATION	24.000 EA				
0470	523.5401 LAMINATED ELASTOMERIC BEARINGS, FIXED	12.000 EA				
0480	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	12.000 EA				
0490	525.325 DRY-LAID STONE RETAINING WALL	512.000 SF				
0500	526.34 PERMANENT CONCRETE TRANSITION BARRIER	8.000 EA				
0510	527.3031 ENERGY ABSORBING SYSTEM (ET-PLUS)	1.000 EA				9

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X

BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0520	527.34 WORK ZONE CRASH CUSHIONS	8.000 UN				
0530	603.169 15 INCH CULVERT PIPE OPTION III	208.000 LF				
0540	603.189 21 INCH CULVERT PIPE OPTION III	46.000 LF				
0550	604.072 CATCH BASIN TYPE A1-C	5.300 EA				
0560	604.15 MANHOLE	1.800 EA				
0570	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	2.000 EA				
0580	604.247 CATCH BASIN TYPE F5-C	2.000 EA				
0590	606.1721 BRIDGE TRANSITION - TYPE 1	8.000 EA				
0600	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	177.000 LF				
0610	606.232 GUARDRAIL TYPE 3C - OVER 15 FOOT RADIUS	25.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0620	606.258 CABLE RELEASING TERMINAL ANCHORAGE ASSEMBLY	1.000 EA				
0630	606.259 ANCHORAGE ASSEMBLY	1.000 EA				
0640	606.266 TERMINAL END - SINGLE RAIL - CORROSION RESISTANT STEEL	4.000 EA				
0650	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	2.000 EA				
0660	606.363 GUARDRAIL REMOVE AND DISPOSE	140.000 LF				
0670	607.16 CHAIN LINK FENCE - 4 FOOT	152.000 LF				
0680	607.34 BRACING ASSEMBLY CHAIN LINK FENCE	6.000 EA				
0690	608.26 CURB RAMP DETECTABLE WARNING FIELD	60.000 SF				
0700	609.11 VERTICAL CURB TYPE 1	301.000 LF				
0710	609.237 TERMINAL CURB TYPE 1 - 7 FOOT	4.000 EA				
0720	609.247 TERMINAL CURB TYPE 2 - 7 FOOT	4.000 EA				11

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X

BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0730	609.31 CURB TYPE 3	217.000 LF				
0740	609.441 CURBING REMOVED AND STACKED	320.000 LF				
0750	610.08 PLAIN RIPRAP	105.000 CY				
0760	610.16 HEAVY RIPRAP	54.000 CY				
0770	613.319 EROSION CONTROL BLANKET	80.000 SY				
0780	615.07 LOAM	16.000 CY				
0790	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	2.000 UN				
0800	619.1201 MULCH - PLAN QUANTITY	2.000 UN				
0810	620.58 EROSION CONTROL GEOTEXTILE	460.000 SY				
0820	621.037 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP A	46.000 EA				
0830	621.046 EVERGREEN TR (8' - 10') GP A	5.000 EA				12

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0840	621.285 LARGE DECIDUOUS TREE (3 INCH - 3.50 INCH CALIPER) GROUP A	5.000 EA				
0850	621.287 LARGE DECIDUOUS TREE (3 INCH - 3.50 INCH CALIPER) GROUP C	5.000 EA				
0860	621.401 DWARF EVERGREENS (2 FOOT - 2.50 FOOT) GROUP A	6.000 EA				
0870	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	18.000 EA				
0880	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0890	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	2900.000 LF				
0900	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	336.000 SF				
0910	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0920	627.77 REMOVING PAVEMENT MARKINGS	1000.000 SF				
0930	629.05 HAND LABOR, STRAIGHT TIME	60.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0940	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	100.000 HR				
0950	631.14 GRADER (INCLUDING OPERATOR)	60.000 HR				
0960	631.15 ROLLER, EARTH AND BASE COURSE (INCLUDING OPERATOR)	60.000 HR				
0970	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	140.000 HR				
0980	637.071 DUST CONTROL	LUMP	LUMP			
0990	639.18 FIELD OFFICE TYPE A	1.000 EA				
1000	652.312 TYPE III BARRICADE	6.000 EA				
1010	652.33 DRUM	72.000 EA				
1020	652.34 CONE	32.000 EA				
1030	652.35 CONSTRUCTION SIGNS	250.000 SF				
1040	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			14

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X

BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1050	652.38 FLAGGER	2500.000 HR				
1060	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA				
1070	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
1080	659.10 MOBILIZATION	LUMP	LUMP			
1090	824.304 FIRE HYDRANT SERVICE, ADJUST TO GRADE	1.000 EA				
	SECTION 0001 TOTAL					.

SECTION 0002 UTILITY WORK

1100	202.1913 REMOVE ABANDONED ASBESTOS-CONTAINING PIPE	25.000 LF				
1110	203.25 GRANULAR BORROW	100.000 CY				
1120	603.169 15 INCH CULVERT PIPE OPTION III	170.000 LF				
1130	603.179 18 INCH CULVERT PIPE OPTION III	375.000 LF				15

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X

BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1140	604.1311 4' DIAMETER CATCH BASIN	37.000 VF				
1150	604.1321 5' DIAMETER CATCH BASIN	9.000 VF				
1160	604.1531 60 INCH MANHOLE	9.000 VF				
1170	604.1541 72 INCH MANHOLE	7.000 VF				
1180	608.451 RECONSTRUCT CONCRETE SIDEWALK	35.000 SY				
1190	615.071 LOAM, SEED, MULCH	1.000 SY				
1200	625.01 WATER LINE SYSTEM TEMPORARY	LUMP	LUMP			
1210	625.147 10 INCH PIPE SLEEVE INSTALL ONLY	66.000 LF				
1220	631.231 CRANE, 45 TON CAPACITY (INCLUDING OPERATOR)	40.000 HR				
1230	801.03 TEST PITS	8.000 EA				
1240	801.19 15 INCH PVC SANITARY SEWER (SDR-35)	430.000 LF				16

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1250	801.53 SEWER BEDDING RELIEF DRAIN	50.000 LF				
1260	803.138 CONNECT 4", 6", 8", 12" SEWER SERVICES	260.000 LF				
1270	803.1711 SEWER MANHOLE - 6 FOOT DIAMETER	11.000 VF				
1280	803.1732 SEWER MANHOLE - 4 FOOT DIAMETER	36.000 VF				
1290	822.3213 4 INCH CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT	40.000 EA				
1300	822.3225 6 INCH CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT	20.000 EA				
1310	822.3405 8 INCH CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT	40.000 EA				
1320	822.3605 12" CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT	470.000 EA				
1330	822.3631 12" CLASS 52 DUCTILE IRON PIPE PUSH ON JOINT - PREINSULATED	135.000 EA				
1340	822.3632 12" CLASS 52 DUCTILE IRON PIPE RESTRAINED JOINT - PREINSULATED	260.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X
BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1350	823.31 12 INCH GATE VALVE	4.000 EA				
1360	823.325 8 INCH GATE VALVE	1.000 EA				
1370	823.331 6 INCH GATE VALVE	1.000 EA				
1380	823.335 4 INCH GATE VALVE	1.000 EA				
1390	823.34 BLOW OFF VALVE ASSEMBLY	2.000 EA				
1400	823.341 AIR RELEASE VALVE	2.000 EA				
1410	824.30 FIRE HYDRANT	1.000 EA				
1420	827.30 ROCK EXCAVATION- REMOVE AND REFILL	100.000 CY				
1430	827.31 UNSUITABLE SOIL EXCAVATION, REMOVE AND REFILL- ABOVE GRADE	1000.000 CY				
1440	827.311 UNSUITABLE SOIL EXCAVATION, REMOVE AND REFILL- BELOW GRADE	50.000 CY				
1450	827.33 TRENCH INSULATION	200.000 LF				18

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011063.00

PROJECT(S): BH-1106(300)X

BH-1106(400)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1460	827.362 GAS MAIN TRENCHING	583.000 LF				
1470	845.10 STRUCTURAL STEEL UTILITY SUPPORT GAS MAIN	LUMP	LUMP			
1480	845.10 STRUCTURAL STEEL UTILITY SUPPORT WATER MAIN	LUMP	LUMP			
1490	890.01 SPECIAL WORK #1 TRAFFIC ISLAND - SEWER	LUMP	LUMP			
1500	890.021 SPECIAL WORK #2 GAS MAIN TEMP SUPPORT	LUMP	LUMP			
	SECTION 0002 TOTAL					
	TOTAL BID					