

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS

SECTION 0001 Project Items

0010	201.11 CLEARING	AC	8.000			
0020	201.12 SELECTIVE CLEARING AND THINNING	AC	1.000			
0030	202.15 REMOVING MANHOLE OR CATCH BASIN	EA	5.000			
0040	202.202 REMOVING PAVEMENT SURFACE	SY	7980.000			
0050	202.203 PAVEMENT BUTT JOINTS	SY	150.000			
0060	203.20 COMMON EXCAVATION	CY	55770.000			
0070	203.21 ROCK EXCAVATION	CY	36800.000			
0080	203.212 SPECIAL PERIMETER CONTROL BLASTING	LF	1050.000			
0090	203.213 SHATTER SOLID ROCK SUBGRADE	SY	5880.000			
0100	203.27 ROCK BORROW	CY	1270.000			

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	2954.000 CY				
0120	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	900.000 CY				
0130	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	36510.000 CY				
0140	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	5880.000 T				
0150	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	22.000 T				
0160	403.213 HOT MIX ASPHALT 12.5 MM BASE	13060.000 T				
0170	409.15 BITUMINOUS TACK COAT - APPLIED	3661.000 G				
0180	462.30 ULTRATHIN BONDED WEARING COURSE	3180.000 SY				
0190	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP	LUMP			
0200	527.305 QUADGUARD CRASH CUSHION	1.000 UN				

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	527.34 WORK ZONE CRASH CUSHIONS	2.000 UN				
0220	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	34.000 LF				
0230	603.159 12 INCH CULVERT PIPE OPTION III	78.000 LF				
0240	603.161 15 INCH CORRUGATED METAL PIPE	27.000 LF				
0250	603.169 15 INCH CULVERT PIPE OPTION III	69.000 LF				
0260	603.179 18 INCH CULVERT PIPE OPTION III	912.000 LF				
0270	603.191 24 INCH CORRUGATED METAL PIPE	8.000 LF				
0280	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	74.000 LF				
0290	603.199 24 INCH CULVERT PIPE OPTION III	215.000 LF				
0300	604.09 CATCH BASIN TYPE B1	3.000 EA				
0310	604.092 CATCH BASIN TYPE B1-C	8.000 EA				

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	604.15 MANHOLE	1.000				
		EA				
0330	604.182 CLEAN EXISTING CATCH BASIN AND MANHOLE	12.000				
		EA				
0340	605.09 6 INCH UNDERDRAIN TYPE B	4729.000				
		LF				
0350	605.10 6 INCH UNDERDRAIN OUTLET	298.000				
		LF				
0360	606.1721 BRIDGE TRANSITION - TYPE 1	4.000				
		EA				
0370	606.23 GUARDRAIL TYPE 3C - SINGLE RAIL	6252.000				
		LF				
0380	606.265 TERMINAL END - SINGLE RAIL - GALVANIZED STEEL	4.000				
		EA				
0390	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	30.000				
		EA				
0400	606.356 UNDERDRAIN DELINEATOR POST	8.000				
		EA				
0410	606.79 GUARDRAIL 350 FLARED TERMINAL	11.000				
		EA				
0420	607.22 CEDAR RAIL FENCE	50.000				
		LF				

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	607.421 SCREENING FENCE	475.000				
		LF				
0440	609.34 CURB TYPE 5	3000.000				
		LF				
0450	609.35 CURB TYPE 5 - CIRCULAR	140.000				
		LF				
0460	610.08 PLAIN RIPRAP	140.000				
		CY				
0470	613.319 EROSION CONTROL BLANKET	100.000				
		SY				
0480	615.07 LOAM	2943.000				
		CY				
0490	615.25 BIORETENTION CELLS	LUMP	LUMP			
0500	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	300.000				
		UN				
0510	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	177.000				
		UN				
0520	619.1201 MULCH - PLAN QUANTITY	477.000				
		UN				
0530	619.13 BARK MULCH	2.000				
		UN				

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	620.54 STABILIZATION GEOTEXTILE	7700.000 SY				
0550	621.025 EVERGREEN TREES (3 FOOT - 4 FOOT) GROUP A	20.000 EA				
0560	621.031 EVERGREEN TREES (4 FOOT - 5 FOOT) GROUP A	10.000 EA				
0570	621.037 EVERGREEN TREES (5 FOOT - 6 FOOT) GROUP A	15.000 EA				
0580	621.044 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP B	10.000 EA				
0590	621.045 EVERGREEN TREES (6 FOOT - 8 FOOT) GROUP C	5.000 EA				
0600	621.18 MEDIUM DECIDUOUS TREES (6 FOOT - 8 FOOT) GROUP C	15.000 EA				
0610	621.202 MEDIUM DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP B	8.000 EA				
0620	621.245 LARGE DECIDUOUS TREES (2 FOOT - 3 FOOT) GROUP A	20.000 EA				
0630	621.255 LARGE DECIDUOUS TREES (8 FOOT - 10 FOOT) GROUP A	10.000 EA				

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0640	621.273 LARGE DECIDUOUS TREE (2 INCH - 2.50 INCH CALIPER) GROUP A	16.000 EA				
0650	621.546 DECIDUOUS SHRUBS (2 FOOT - 3 FOOT) GROUP A	100.000 EA				
0660	621.552 DECIDUOUS SHRUBS (3 FOOT - 4 FOOT) GROUP A	40.000 EA				
0670	621.711 HERBACEOUS PERENNIALS GROUP B	650.000 EA				
0680	621.80 ESTABLISHMENT PERIOD	LUMP	LUMP			
0690	626.11 PRECAST CONCRETE JUNCTION BOX	68.000 EA				
0700	626.22 NON-METALLIC CONDUIT	11345.000 LF				
0710	626.31 18 INCH FOUNDATION	6.000 EA				
0720	626.33 30 INCH FOUNDATION	48.000 EA				
0730	627.18 12 " SOLID WHITE PAVEMENT MARKING	3880.000 LF				

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0740	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	45400.000 LF				
0750	627.744 6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	32000.000 LF				
0760	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	1150.000 SF				
0770	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0780	629.05 HAND LABOR, STRAIGHT TIME	50.000 HR				
0790	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR				
0800	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	100.000 HR				
0810	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	20.000 HR				
0820	634.180 RGS CONDUIT	140.000 LF				
0830	634.2042 LED LUMINARIES	54.000 EA				
0840	634.2082 REMOVE EXISTING LIGHT STANDARD	8.000 EA				

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0850	634.2101 TYPE A LIGHT STANDARD	EA 48.000				
0860	634.2102 TYPE B LIGHT STANDARD	EA 6.000				
0870	634.25 SERVICE POLE COMPLETE WITH CABINET AND CONTROLS	EA 1.000				
0880	634.313 # 4 AWG COPPER WIRING	LF 33910.000				
0890	634.316 #10 AWG COPPER WIRE	LF 7500.000				
0900	636.400 SOIL NAIL WALL DESIGN	LUMP	LUMP			
0910	636.411 SOIL NAIL WALL	SF 1590.000				
0920	639.18 FIELD OFFICE TYPE A	EA 1.000				
0930	643.72 TEMPORARY TRAFFIC SIGNAL EXIT 10 NB OFF RAMP	LUMP	LUMP			
0940	643.72 TEMPORARY TRAFFIC SIGNAL EXIT 17 NB RAMP	LUMP	LUMP			
0950	643.97 WOOD POLES WITH GUYS AND SPAN WIRE	EA 1.000				

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0960	645.103 DEMOUNT GUIDE SIGN	EA 6.000				
0970	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	EA 50.000				
0980	645.113 REINSTALL GUIDE SIGN	EA 2.000				
0990	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	EA 20.000				
1000	645.251 ROADSIDE GUIDE SIGNS	SF 350.000				
1010	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	SF 650.000				
1020	645.511 FLASHING WARNING SIGN RIGHT CHEVRON SIGN	EA 3.000				
1030	645.511 FLASHING WARNING SIGN WRONG WAY SIGN	EA 4.000				
1040	652.30 FLASHING ARROW BOARD	EA 2.000				
1050	652.31 TYPE I BARRICADE	EA 70.000				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
1060	652.312 TYPE III BARRICADE	EA 45.000				
1070	652.33 DRUM	EA 260.000				
1080	652.34 CONE	EA 200.000				
1090	652.35 CONSTRUCTION SIGNS	SF 3300.000				
1100	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
1110	652.38 FLAGGER	HR 10000.000				
1120	652.381 TRAFFIC OFFICER	HR 300.000				
1130	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	EA 6.000				
1140	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
1150	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	SY 1310.000				
1160	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					

SCHEDULE OF ITEMS

DATE: 121214

REVISED:

CONTRACT ID: 011086.00

PROJECT(S): IM-1108(600)
CM-1749(000)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
	TOTAL BID					