

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	201.11 CLEARING	1.500 AC	_____	 _____	_____	 _____
0020	201.23 REMOVING SINGLE TREE TOP ONLY	124.000 EA	_____	 _____	_____	 _____
0030	201.24 REMOVING STUMP	141.000 EA	_____	 _____	_____	 _____
0040	202.19 REMOVING EXISTING BRIDGE	LUMP SUM	LUMP SUM		_____	 _____
0050	203.20 COMMON EXCAVATION	41,909.000 CY	_____	 _____	_____	 _____
0060	203.21 ROCK EXCAVATION	2,630.000 CY	_____	 _____	_____	 _____
0070	203.24 COMMON BORROW	280.000 CY	_____	 _____	_____	 _____
0080	203.25 GRANULAR BORROW	273.000 CY	_____	 _____	_____	 _____
0090	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	410.000 CY	_____	 _____	_____	 _____
0100	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	617.000 CY	_____	 _____	_____	 _____
0110	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	30,900.000 CY	_____	 _____	_____	 _____
0120	309.36 FULL DEPTH RECYCLED PAVEMENT W/ FOAM ASPHALT - 6 INCH DEPTH	44,300.000 SY	_____	 _____	_____	 _____

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0130	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	5,250.000 T	_____	_____	_____	_____
0140	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	400.000 T	_____	_____	_____	_____
0150	403.211 HOT MIX ASPHALT (SHIMMING)	160.000 T	_____	_____	_____	_____
0160	403.213 HOT MIX ASPHALT 12.5 MM BASE	5,400.000 T	_____	_____	_____	_____
0170	409.15 BITUMINOUS TACK COAT - APPLIED	2,750.000 G	_____	_____	_____	_____
0180	411.10 UNTREATED AGGREGATE SURFACE COURSE (TRUCK MEASURE)	1,650.000 CY	_____	_____	_____	_____
0190	501.231 DYNAMIC LOADING TEST	2.000 EA	_____	_____	_____	_____
0200	501.50 STEEL H-BEAM PILES 89 LBS/FT, DELIVERED	236.000 LF	_____	_____	_____	_____
0210	501.501 STEEL H-BEAM PILES 89 LBS/FT, IN PLACE	236.000 LF	_____	_____	_____	_____
0220	501.90 PILE TIPS	8.000 EA	_____	_____	_____	_____
0230	501.92 PILE DRIVING EQUIPMENT MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0240	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP	SUM	_____	_____
0250	502.261 STRUCTURAL CONCRETE ROADWAY & SIDEWALK SLAB ON CONCRETE BRIDGE	LUMP SUM	LUMP	SUM	_____	_____
0260	502.31 STRUCTURAL CONCRETE APPROACH SLABS	LUMP SUM	LUMP	SUM	_____	_____
0270	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP	SUM	_____	_____
0280	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	17,000.000 LB	_____	_____	_____	_____
0290	503.13 REINFORCING STEEL, PLACING	17,000.000 LB	_____	_____	_____	_____
0300	503.17 MECHANICAL WELDED SPLICE	52.000 EA	_____	_____	_____	_____
0310	503.26 STAINLESS STEEL REINFORCEMENT - FABRICATED & DELIVERED	11,000.000 LB	_____	_____	_____	_____
0320	503.27 STAINLESS STEEL REINFORCEMENT - PLACING	11,000.000 LB	_____	_____	_____	_____
0330	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP	SUM	_____	_____
0340	507.0822 STEEL APPROACH RAILING, 3-BAR	LUMP SUM	LUMP	SUM	_____	_____

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE SPECIAL	LUMP SUM	LUMP	SUM	2,000.00	
0360	511.07 COFFERDAM: Downstream	LUMP SUM	LUMP	SUM		
0370	511.07 COFFERDAM: Upstream	LUMP SUM	LUMP	SUM		
0380	514.06 CURING BOX FOR CONCRETE CYLINDERS	1.000 EA				
0390	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP	SUM		
0400	520.232 EXPANSION DEVICE - ASPHALTIC PLUG JOINT	64.000 LF				
0410	524.301 TEMPORARY STRUCTURAL SUPPORT	LUMP SUM	LUMP	SUM		
0420	526.301 TEMPORARY CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM		
0430	526.305 TEMPORARY CONCRETE BARRIER, BRACED TYPE 1	LUMP SUM	LUMP	SUM		
0440	527.34 WORK ZONE CRASH CUSHIONS	4.000 UN				
0450	530.30 GFRP, REINFORCEMENT BARS, FABRICATED & DELIVERED	19,700.000 LF				

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0460	530.31 GFRP, REINFORCEMENT BARS, PLACING	19,700.000 LF	_____	_____	_____	_____
0470	535.622 PRESTRESSED STRUCTURAL CONCRETE NEXT BEAM	LUMP SUM	LUMP SUM		_____	_____
0480	603.159 12 INCH CULVERT PIPE OPTION III	118.000 LF	_____	_____	_____	_____
0490	603.16 15 INCH CULVERT PIPE OPTION I	1,880.000 LF	_____	_____	_____	_____
0500	603.169 15 INCH CULVERT PIPE OPTION III	260.000 LF	_____	_____	_____	_____
0510	603.17 18 INCH CULVERT PIPE OPTION I	110.000 LF	_____	_____	_____	_____
0520	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	544.000 LF	_____	_____	_____	_____
0530	603.19 24 INCH CULVERT PIPE OPTION I	160.000 LF	_____	_____	_____	_____
0540	603.199 24 INCH CULVERT PIPE OPTION III	200.000 LF	_____	_____	_____	_____
0550	603.209 30 INCH CULVERT PIPE OPTION III	120.000 LF	_____	_____	_____	_____
0560	603.215 36 INCH REINFORCED CONCRETE PIPE CLASS III	70.000 LF	_____	_____	_____	_____
0570	603.219 36 INCH CULVERT PIPE OPTION III	80.000 LF	_____	_____	_____	_____

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0580	603.229 42 INCH CULVERT PIPE OPTION III	80.000 LF	_____	_____	_____	_____
0590	603.9111 53" X 34" RCP ELLIPTICAL CULVERT PIPE	80.000 LF	_____	_____	_____	_____
0600	604.092 CATCH BASIN TYPE B1-C	11.000 EA	_____	_____	_____	_____
0610	604.24 CATCH BASIN TYPE F	1.000 EA	_____	_____	_____	_____
0620	605.09 6 INCH UNDERDRAIN TYPE B	4,850.000 LF	_____	_____	_____	_____
0630	605.10 6 INCH UNDERDRAIN OUTLET	200.000 LF	_____	_____	_____	_____
0640	605.11 12 INCH UNDERDRAIN TYPE C	80.000 LF	_____	_____	_____	_____
0650	605.12 15 INCH UNDERDRAIN TYPE C	540.000 LF	_____	_____	_____	_____
0660	605.13 18 INCH UNDERDRAIN TYPE C	574.000 LF	_____	_____	_____	_____
0670	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	720.000 LF	_____	_____	_____	_____
0680	606.1303 31" W-BM GR, MID-WAY SPLICE-15' RAD AND LESS	52.000 LF	_____	_____	_____	_____
0690	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	6.000 EA	_____	_____	_____	_____

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0700	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0710	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	16.000 EA				
0720	606.356 UNDERDRAIN DELINEATOR POST	48.000 EA				
0730	607.24 REMOVE AND RESET FENCE	350.000 LF				
0740	609.31 CURB TYPE 3	4,650.000 LF				
0750	610.08 PLAIN RIPRAP	613.000 CY				
0760	610.18 STONE DITCH PROTECTION	345.000 CY				
0770	613.319 EROSION CONTROL BLANKET	13,149.000 SY				
0780	613.40 TURF REINFORCEMENT MAT - (TRM)	900.000 SY				
0790	615.07 LOAM	4,775.000 CY				
0800	618.13 SEEDING METHOD NUMBER 1	220.000 UN				
0810	618.14 SEEDING METHOD NUMBER 2	1,555.000 UN				
0820	618.146 SEEDING HYDROMULCH MEDIUM	18.000 UN				

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0830	619.12 MULCH	1,705.000 UN	_____	_____	_____	_____
0840	619.14 EROSION CONTROL MIX	25.000 CY	_____	_____	_____	_____
0850	620.58 EROSION CONTROL GEOTEXTILE	3,759.000 SY	_____	_____	_____	_____
0860	620.66 DRAINAGE GEOCOMPOSITE	70.000 SY	_____	_____	_____	_____
0870	627.407 REFLECTORIZED PLASTIC WHITE OR YELLOW PAVEMENT MARKING	110.000 SF	_____	_____	_____	_____
0880	627.733 4" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	71,300.000 LF	_____	_____	_____	_____
0890	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	310.000 SF	_____	_____	_____	_____
0900	627.77 REMOVING PAVEMENT MARKINGS	980.000 SF	_____	_____	_____	_____
0910	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	72,070.000 LF	_____	_____	_____	_____
0920	629.05 HAND LABOR, STRAIGHT TIME	40.000 HR	_____	_____	_____	_____
0930	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.000 HR	_____	_____	_____	_____

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0940	631.121 HEAVY DUTY ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0950	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	60.000 HR	_____	 _____	_____	 _____
0960	639.18 FIELD OFFICE TYPE A	1.000 EA	_____	 _____	_____	 _____
0970	643.72 TEMPORARY TRAFFIC SIGNAL	LUMP SUM		LUMP SUM	_____	 _____
0980	643.72 TEMPORARY TRAFFIC SIGNAL - Hwy	LUMP SUM		LUMP SUM	_____	 _____
0990	652.311 TYPE II BARRICADE	34.000 EA	_____	 _____	_____	 _____
1000	652.312 TYPE III BARRICADE	4.000 EA	_____	 _____	_____	 _____
1010	652.33 DRUM	65.000 EA	_____	 _____	_____	 _____
1020	652.34 CONE	171.000 EA	_____	 _____	_____	 _____
1030	652.35 CONSTRUCTION SIGNS	626.000 SF	_____	 _____	_____	 _____
1040	652.36 MAINTENANCE OF TRAFFIC CONTROL DEVICES - Highway	428.000 CD	_____	 _____	_____	 _____
1050	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES - Doles Br.	LUMP SUM		LUMP SUM	_____	 _____

5/2/2019

Maine Department of Transportation

Proposal Schedule of Items

Page 10 of 10

Proposal ID: 011219.20

Project(s): 011219.20, 021924.00

SECTION: 1 Project Items

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1060	652.38 FLAGGER	9,160.000 HR	_____	_____	_____	_____
1070	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	2.000 EA	_____	_____	_____	_____
1080	653.22 2 INCH POLYSTYRENE PLASTIC INSULATION	125.000 SY	_____	_____	_____	_____
1090	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP	SUM	_____	_____
1100	659.10 MOBILIZATION	LUMP SUM	LUMP	SUM	_____	_____
Section: 1			Total:		_____	_____
			Total Bid:		_____	_____