

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012669.00

PROJECT(S): STP-1266(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
SECTION 0001 PROJECT ITEMS						
0010	201.11 CLEARING	2.500 AC				
0020	201.23 REMOVING SINGLE TREE TOP ONLY	20.000 EA				
0030	201.24 REMOVING STUMP	25.000 EA				
0040	202.202 REMOVING PAVEMENT SURFACE	20500.000 SY				
0050	203.20 COMMON EXCAVATION	26300.000 CY				
0060	203.2312 HEALTH AND SAFETY PLAN	LUMP	LUMP			
0070	203.2333 DISPOSAL OF SPECIAL EXCAVATION	500.000 T				
0080	203.24 COMMON BORROW	200.000 CY				
0090	203.242 DIRTY BORROW	900.000 CY				
0100	203.25 GRANULAR BORROW	5400.000 CY				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012669.00

PROJECT(S): STP-1266(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0110	206.061 STRUCTURAL EARTH EXCAVATION - DRAINAGE AND MINOR STRUCTURES, BELOW GRADE	165.000 CY				
0120	304.09 AGGREGATE BASE COURSE - CRUSHED	25900.000 CY				
0130	403.207 HOT MIX ASPHALT 19.0 MM HMA	4685.000 T				
0140	403.208 HOT MIX ASPHALT 12.5 MM HMA SURFACE	3440.000 T				
0150	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	225.000 T				
0160	409.15 BITUMINOUS TACK COAT - APPLIED	1540.000 G				
0170	504.07 CONCRETE PIPE TIES	27.000 GP				
0180	525.326 FIELD STONE RETAINING WALL	225.000 SF				
0190	603.16 15 INCH CULVERT PIPE OPTION I	450.000 LF				
0200	603.17 18 INCH CULVERT PIPE OPTION I	160.000 LF				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012669.00

PROJECT(S): STP-1266(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0210	603.175 18 INCH REINFORCED CONCRETE PIPE CLASS III	730.000 LF				
0220	603.195 24 INCH REINFORCED CONCRETE PIPE CLASS III	60.000 LF				
0230	603.235 48 INCH REINFORCED CONCRETE PIPE CLASS III	200.000 LF				
0240	604.092 CATCH BASIN TYPE B1-C	1.000 EA				
0250	605.09 6 INCH UNDERDRAIN TYPE B	1125.000 LF				
0260	605.10 6 INCH UNDERDRAIN OUTLET	60.000 LF				
0270	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	2.000 EA				
0280	606.356 UNDERDRAIN DELINEATOR POST	3.000 EA				
0290	606.366 GUARDRAIL, REMOVE & RESET TYPE 3C	125.000 LF				
0300	606.47 SINGLE WOOD POST	15.000 EA				
0310	606.79 GUARDRAIL 350 FLARED TERMINAL	1.000 EA				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012669.00

PROJECT(S): STP-1266(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0320	607.10 BARBED WIRE FENCE - WOOD POSTS	525.000 LF				
0330	607.24 REMOVE AND RESET FENCE	140.000 LF				
0340	609.31 CURB TYPE 3	770.000 LF				
0350	610.08 PLAIN RIPRAP	140.000 CY				
0360	610.18 STONE DITCH PROTECTION	335.000 CY				
0370	610.210 STREAM CHANNEL ROCK	10.000 CY				
0380	610.211 STREAM CHANNEL GRAVEL	10.000 CY				
0390	613.319 EROSION CONTROL BLANKET	6620.000 SY				
0400	615.07 LOAM	475.000 CY				
0410	618.1301 SEEDING METHOD NUMBER 1 - PLAN QUANTITY	38.000 UN				
0420	618.1401 SEEDING METHOD NUMBER 2 - PLAN QUANTITY	238.500 UN				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012669.00

PROJECT(S): STP-1266(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	618.1411 SEEDING METHOD NUMBER 3 - PLAN QUANTITY	2.000 UN				
0440	619.1201 MULCH - PLAN QUANTITY	278.500 UN				
0450	620.54 STABILIZATION GEOTEXTILE	6150.000 SY				
0460	620.58 EROSION CONTROL GEOTEXTILE	1550.000 SY				
0470	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	65.000 SF				
0480	627.76 TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	LUMP	LUMP			
0490	629.05 HAND LABOR, STRAIGHT TIME	20.000 HR				
0500	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	50.000 HR				
0510	631.14 GRADER (INCLUDING OPERATOR)	10.000 HR				
0520	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	100.000 HR				
0530	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012669.00

PROJECT(S): STP-1266(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	631.20 STUMP CHIPPER (INCLUDING OPERATOR)	10.000 HR				
0550	631.22 FRONT END LOADER (INCLUDING OPERATOR)	50.000 HR				
0560	639.19 FIELD OFFICE TYPE B	1.000 EA				
0570	645.103 DEMOUNT GUIDE SIGN	1.000 EA				
0580	645.113 REINSTALL GUIDE SIGN	1.000 EA				
0590	645.306 FLEXIBLE REFLECTORIZED DELINEATOR	6.000 EA				
0600	652.33 DRUM	15.000 EA				
0610	652.34 CONE	150.000 EA				
0620	652.35 CONSTRUCTION SIGNS	790.000 SF				
0630	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP	LUMP			
0640	652.38 FLAGGER	3470.000 HR				

SCHEDULE OF ITEMS

REVISED:

CONTRACT ID: 012669.00

PROJECT(S): STP-1266(900)X

CONTRACTOR : _____

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0650	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP	LUMP			
0660	659.10 MOBILIZATION	LUMP	LUMP			
	SECTION 0001 TOTAL					
	TOTAL BID					