

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 1 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0010	202.10 REMOVING EXISTING SUPERSTRUCTURE (PROPERTY OF CONTRACTOR)	LUMP SUM				
0020	202.13 REMOVING EXISTING RAILINGS (RETAINED BY DEPARTMENT)	1,046.000 LF				
0030	202.15 REMOVING EXISTING MANHOLE OR CATCH BASIN	5.000 EA				
0040	202.17 REMOVING EXISTING STRUCTURAL CONCRETE	LUMP SUM				
0050	202.202 REMOVING PAVEMENT SURFACE	2,400.000 SY				
0060	203.20 COMMON EXCAVATION	4,589.000 CY				
0070	203.25 GRANULAR BORROW	80.000 CY				
0080	206.07 STRUCTURAL ROCK EXCAVATION - DRAINAGE AND MINOR STRUCTURES	10.000 CY				
0090	206.082 STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	80.000 CY				
0100	304.10 AGGREGATE SUBBASE COURSE - GRAVEL	3,680.000 CY				
0110	403.2071 19 MM POLYMER MODIFIED HOT MIX ASPHALT	1,114.000 T				

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 2 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0120	403.2081 12.5 MM POLYMER MODIFIED HOT MIX ASPHALT	947.000 T	_____	 _____	_____	 _____
0130	403.209 HOT MIX ASPHALT 9.5 MM (SIDEWALKS, DRIVES, INCIDENTALS)	93.000 T	_____	 _____	_____	 _____
0140	403.2111 9.5 MM POLYMER MODIFIED HMA (SHIM)	140.000 T	_____	 _____	_____	 _____
0150	403.2131 12.5 MM POLYMER MODIFIED HMA BASE	1,209.000 T	_____	 _____	_____	 _____
0160	409.15 BITUMINOUS TACK COAT - APPLIED	694.000 G	_____	 _____	_____	 _____
0170	461.131 TEMPORARY PAVEMENT	33.000 T	_____	 _____	_____	 _____
0180	502.219 STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	LUMP SUM	LUMP SUM		_____	 _____
0190	502.23 STRUCTURAL CONCRETE PIERS	50.000 CY	_____	 _____	_____	 _____
0200	502.26 STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLABS ON STEEL BRIDGES	LUMP SUM	LUMP SUM		_____	 _____
0210	502.49 STRUCTURAL CONCRETE CURBS AND SIDEWALKS	LUMP SUM	LUMP SUM		_____	 _____
0220	502.77 FIBER REINFORCED POLYMER BRIDGE DRAIN - TYPE: E	8.000 EA	_____	 _____	_____	 _____

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 3 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0230	503.12 REINFORCING STEEL, FABRICATED AND DELIVERED	221,500.000 LB	_____	 _____	_____	 _____
0240	503.13 REINFORCING STEEL, PLACING	221,700.000 LB	_____	 _____	_____	 _____
0250	503.17 MECHANICAL WELDED SPLICE	2,062.000 EA	_____	 _____	_____	 _____
0260	503.19 LOW-CARBON, CHROMIUM REINFORCEMENT - FABRICATED & DELIVERED	31,400.000 LB	_____	 _____	_____	 _____
0270	503.20 LOW-CARBON, CHROMIUM REINFORCEMENT - PLACING	31,400.000 LB	_____	 _____	_____	 _____
0280	505.08 SHEAR CONNECTORS	LUMP SUM	LUMP SUM		_____	 _____
0290	507.0821 STEEL BRIDGE RAILING, 3 BAR	LUMP SUM	LUMP SUM		_____	 _____
0300	507.0822 STEEL APPROACH RAILING, 3-BAR	4.000 EA	_____	 _____	_____	 _____
0310	508.14 HIGH PERFORMANCE WATERPROOFING MEMBRANE	LUMP SUM	LUMP SUM		_____	 _____
0320	515.21 PROTECTIVE COATING FOR CONCRETE SURFACES	LUMP SUM	LUMP SUM		_____	 _____
0330	518.50 REPAIR OF UPWARD FACING SURFACES - TO REINFORCING STEEL < 8 IN.	154.000 SF	_____	 _____	_____	 _____

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 4 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0340	518.60 REPAIR OF VERTICAL SURFACES < 8 IN.	862.000 SF	_____	 _____	_____	 _____
0350	518.70 REPAIR OF OVERHEAD SURFACES < 8 IN.	180.000 SF	_____	 _____	_____	 _____
0360	518.80 CRACK REPAIR	51.000 LF	_____	 _____	_____	 _____
0370	520.21 EXPANSION DEVICE - GLAND SEAL	2.000 EA	_____	 _____	_____	 _____
0380	523.301 REFURBISH & RESET FIXED BEARING	13.000 EA	_____	 _____	_____	 _____
0390	523.52 BEARING INSTALLATION	7.000 EA	_____	 _____	_____	 _____
0400	523.5402 LAMINATED ELASTOMERIC BEARINGS, EXPANSION	7.000 EA	_____	 _____	_____	 _____
0410	524.301 TEMPORARY STRUCTURAL SUPPORT ABUTMENT NO. 1	LUMP SUM		LUMP SUM	_____	 _____
0420	524.301 TEMPORARY STRUCTURAL SUPPORT DECK	LUMP SUM		LUMP SUM	_____	 _____
0430	524.301 TEMPORARY STRUCTURAL SUPPORT PIER 3	LUMP SUM		LUMP SUM	_____	 _____
0440	524.40 PROTECTIVE SHIELD	LUMP SUM		LUMP SUM	_____	 _____

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 5 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0450	526.301 PORTABLE CONCRETE BARRIER TYPE I	LUMP SUM	LUMP	SUM	_____	_____
0460	526.304 PORTABLE CONCRETE BARRIER, ANCHORED TYPE 1	LUMP SUM	LUMP	SUM	_____	_____
0470	603.155 12 INCH REINFORCED CONCRETE PIPE CLASS III	50.000 LF	_____	_____	_____	_____
0480	603.159 12 INCH CULVERT PIPE OPTION III	44.000 LF	_____	_____	_____	_____
0490	603.165 15 INCH REINFORCED CONCRETE PIPE CLASS III	45.000 LF	_____	_____	_____	_____
0500	604.092 CATCH BASIN TYPE B1-C	10.000 EA	_____	_____	_____	_____
0510	604.18 ADJUSTING MANHOLE OR CATCH BASIN TO GRADE	8.000 EA	_____	_____	_____	_____
0520	604.262 CATCH BASIN TYPE B5-C	6.375 EA	_____	_____	_____	_____
0530	605.09 6 INCH UNDERDRAIN TYPE B	920.000 LF	_____	_____	_____	_____
0540	605.11 12 INCH UNDERDRAIN TYPE C	1,050.000 LF	_____	_____	_____	_____
0550	606.1301 31" W-BM GR, MID-WAY SPLICE-SGL FACED	1,400.000 LF	_____	_____	_____	_____
0560	606.1305 31" W-BM GR, MID-WAY SPLICE FLARED TERMINAL	1.000 EA	_____	_____	_____	_____

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 6 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0570	606.1721 BRIDGE TRANSITION - TYPE 1	4.000 EA				
0580	606.259 ANCHORAGE ASSEMBLY	3.000 EA				
0590	606.353 REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	6.000 EA				
0600	606.356 UNDERDRAIN DELINEATOR POST	6.000 EA				
0610	606.65 GUARDRAIL THRIE BEAM - SINGLE RAIL	580.000 LF				
0620	606.70 TRANSITION SECTION THRIE BEAM	2.000 EA				
0630	606.95 LOW MAINTENANCE/ SELF RESTORING CRASH CUSHION	1.000 EA				
0640	607.181 CHAIN LINK FENCE - 8 FOOT HIGH SECURITY	224.000 LF				
0650	607.183 CHAIN LINK SNOW FENCE 33 INCH	LUMP SUM				
0660	607.24 REMOVE AND RESET FENCE	40.000 LF				
0670	609.11 VERTICAL CURB TYPE 1	20.000 LF				
0680	609.21 CONCRETE SLIPFORM CURB	670.000 LF				

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 7 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0690	609.234 TERMINAL CURB TYPE 1 - 4 FOOT	4.000 EA				
0700	609.38 RESET CURB TYPE 1	2,300.000 LF				
0710	609.40 RESET CURB TYPE 5	800.000 LF				
0720	610.08 PLAIN RIPRAP	24.000 CY				
0730	613.319 EROSION CONTROL BLANKET	200.000 SY				
0740	615.07 LOAM	190.000 CY				
0750	618.14 SEEDING METHOD NUMBER 2	30.000 UN				
0760	619.12 MULCH	30.000 UN				
0770	620.58 EROSION CONTROL GEOTEXTILE	25.000 SY				
0780	626.11 PRECAST CONCRETE JUNCTION BOX	40.000 EA				
0790	626.21 METALLIC CONDUIT	90.000 LF				
0800	626.22 NON-METALLIC CONDUIT	11,450.000 LF				

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 8 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0810	626.251 NON-METALLIC UNDER PAVEMENT CONDUIT (SCHEDULE 80 OR GREATER RATING)	850.000 LF	_____	_____	_____	_____
0820	626.35 CONTROLLER CABINET FOUNDATION	1.000 EA	_____	_____	_____	_____
0830	626.36 REMOVE OR MODIFY CONCRETE FOUNDATION	46.000 EA	_____	_____	_____	_____
0840	626.38 GROUND MOUNTED CABINET FOUNDATION	1.000 EA	_____	_____	_____	_____
0850	626.411 18 INCH DIAMETER FOUNDATION	20.000 LF	_____	_____	_____	_____
0860	626.44 36 INCH DIAMETER FOUNDATION	134.000 LF	_____	_____	_____	_____
0870	626.46 48 INCH DIAMETER FOUNDATION	107.000 LF	_____	_____	_____	_____
0880	626.501 SPREAD FOOTING FOUNDATION	15.000 CY	_____	_____	_____	_____
0890	627.18 12 " SOLID WHITE PAVEMENT MARKING	1,200.000 LF	_____	_____	_____	_____
0900	627.744 6" WHITE OR YELLOW PAINTED PAVEMENT MARKING LINE	9,900.000 LF	_____	_____	_____	_____
0910	627.75 WHITE OR YELLOW PAVEMENT & CURB MARKING	490.000 SF	_____	_____	_____	_____

Maine Department of Transportation

Proposal Schedule of Items

Page 9 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0920	627.78 TEMPORARY 4 INCH PAINTED PAVEMENT MARKING LINE, WHITE OR YELLOW	14,900.000 LF	_____	 _____	_____	 _____
0930	629.05 HAND LABOR, STRAIGHT TIME	60.000 HR	_____	 _____	_____	 _____
0940	631.12 ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0950	631.13 BULLDOZER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0960	631.171 TRUCK - SMALL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0970	631.172 TRUCK - LARGE (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
0980	631.18 CHAIN SAW RENTAL (INCLUDING OPERATOR)	10.000 HR	_____	 _____	_____	 _____
0990	631.22 FRONT END LOADER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1000	631.32 CULVERT CLEANER (INCLUDING OPERATOR)	20.000 HR	_____	 _____	_____	 _____
1010	634.160 HIGHWAY LIGHTING	LUMP SUM	LUMP SUM		_____	 _____
1020	634.164 LUMINAIRES FOR HIGH MAST LIGHTING	29.000 EA	_____	 _____	_____	 _____

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 10 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1030	634.2042 LED LUMINARIES	44.000 EA				
1040	634.207 HIGH MAST LIGHT STANDARD	8.000 EA				
1050	634.210 CONVENTIONAL LIGHT STANDARD	41.000 EA				
1060	634.762 VIDEO CAMERA SYSTEM	LUMP SUM				
1070	639.18 FIELD OFFICE TYPE A	1.000 EA				
1080	643.21 NON-INVASIVE DETECTION - STOP LINE: STOP LINE	LUMP SUM				
1090	643.22 NON-INVASIVE DETECTION - ADVANCE: ADVANCE	LUMP SUM				
1100	643.80 TRAFFIC SIGNALS AT SP-6 AND ROUTE 1/SP-4	LUMP SUM				
1110	643.91 MAST ARM POLE 25' AND 35' MAST ARMS	1.000 EA				
1120	643.91 MAST ARM POLE 30' MAST ARM	1.000 EA				
1130	643.97 WOOD POLES WITH GUYS AND SPAN WIRE	1.000 EA				
1140	645.103 DEMOUNT GUIDE SIGN	5.000 EA				

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 11 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1150	645.106 DEMOUNT REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	8.000 EA				
1160	645.108 DEMOUNT POLE	10.000 EA				
1170	645.113 REINSTALL GUIDE SIGN	1.000 EA				
1180	645.116 REINSTALL REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGN	7.000 EA				
1190	645.118 REINSTALL POLE	9.000 EA				
1200	645.12 OVERHEAD GUIDE SIGN: STA 22+30	LUMP SUM				
1210	645.251 ROADSIDE GUIDE SIGNS, TYPE I	470.000 SF				
1220	645.289 STEEL H-BEAM POLES	170.000 LB				
1230	645.292 REGULATORY, WARNING, CONFIRMATION AND ROUTE MARKER ASSEMBLY SIGNS TYPE II	160.000 SF				
1240	645.305 SIGN MOUNTED BEACON ARRAY	LUMP SUM				
1250	652.30 FLASHING ARROW BOARD	4.000 EA				
1260	652.312 TYPE III BARRICADE	10.000 EA				

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 12 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID: Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1270	652.33 DRUM	220.000 EA	_____	 _____	_____	 _____
1280	652.34 CONE	145.000 EA	_____	 _____	_____	 _____
1290	652.35 CONSTRUCTION SIGNS	900.000 SF	_____	 _____	_____	 _____
1300	652.361 MAINTENANCE OF TRAFFIC CONTROL DEVICES	LUMP SUM	LUMP SUM		_____	 _____
1310	652.37 WARNING LIGHTS	1.000 GP	_____	 _____	_____	 _____
1320	652.38 FLAGGER	1,800.000 HR	_____	 _____	_____	 _____
1330	652.381 TRAFFIC OFFICER	16.000 HR	_____	 _____	_____	 _____
1340	652.41 PORTABLE CHANGEABLE MESSAGE SIGN	6.000 EA	_____	 _____	_____	 _____
1350	654.351 CONNECTED ROADSIDE UNIT (RSU)	1.000 EA	_____	 _____	_____	 _____
1360	656.75 TEMPORARY SOIL EROSION AND WATER POLLUTION CONTROL	LUMP SUM	LUMP SUM		_____	 _____
1370	658.20 ACRYLIC LATEX COLOR FINISH, GREEN	900.000 SY	_____	 _____	_____	 _____
1380	659.10 MOBILIZATION	LUMP SUM	LUMP SUM		_____	 _____

10/22/2024

Maine Department of Transportation

Proposal Schedule of Items

Page 13 of 13

Proposal ID: 012800.30

Project(s): 012800.30, 022258.00, 024363.00

SECTION: 1 HIGHWAY ITEMS

Alt Set ID:

Alt Mbr ID:

Contractor: _____

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1390	660.21 ON-THE-JOB TRAINING (BID)	1,000.000 HR	_____	_____	_____	_____
1400	910.301 SPECIAL WORK AERIAL UTILITY LINES	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 1			Total:	_____	_____	_____
			Total Bid:	_____	_____	_____